



## Wisconsin Department of Transportation

---

February 1, 2022

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #14: 2667-03-71, WISC 2022166**  
**N Humboldt Boulevard,**  
**E North Ave to E Keefe Ave**  
**Loc Str**  
**Milwaukee County**

### Letting of February 8, 2022

This is Addendum No. 02, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
7	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**

**2667-03-71**

**February 1, 2022**

**Special Provisions**

**7. Utilities.**

*Replace paragraph three with the following:*

The project contains numerous utility manholes located within the construction area. The utility companies have been advised of the requirement to coordinate adjusting their manhole covers in conjunction with the contractor's operations. Provide a minimum of 14 working days advance notice to each manhole owner before commencing construction operations over affected manholes. In addition, provide 14 working days advance notice so utilities may set their covers to match final pavement elevations.

*Replace entire second to last paragraph under section titled **A. AT&T Wisconsin** with the following:*

Manhole adjustments require 1 working day per location. Provide a 14 working day notice (and a 7 business day reminder notice) to inform Mr. Jay Bulanek that the site is ready for excavation or construction to coordinate work.

*Replace entire section titled **Section C.3. Forestry** with the following:*

The City of Milwaukee has irrigation within the existing medians throughout the project. The city will relocate irrigation taps within the project limits prior to construction.

Provide 14 working day notice to Forestry to inform that the site is ready for excavation or construction to coordinate locations near irrigation tap facilities.

City of Milwaukee Forestry plumbing contractor will furnish and install a new water service to be connected to the existing water main at Sta. 114+50 in coordination with paving operations. Plumbing facilities will be installed before paving within Stage 1 and will be completed within two (2) working days. Provide a 14 working day notice to Forestry to inform that the site is ready for excavation.

Contact James Kringer at (414) 708-2428 to coordinate the work and with any questions or concerns.

*Replace paragraph eight under section titled **Section C.4. Street Lighting** with the following:*

Report any accidental damages to street lighting facilities, as soon as possible to Street Lighting Shop Dispatcher (414) 286-5944.

*Replace paragraphs two and three under section titled **C.5. Traffic Signals** with the following:*

Remove existing pull boxes and signal bases. Furnish and install electrical conduit, pullboxes, concrete bases, electrical wiring, poles, arms, standards, pedestal bases, and traffic signals. Furnish and install all other items such as SPV.0060.201 through SPV.0060.269, SPV.0060.303, SPV.0090.201, SPV.0090.307 and other appurtenances to make the permanent traffic control equipment complete between East North Avenue and East Keefe Avenue.

Prior to construction, the City of Milwaukee will install temporary overhead and temporary traffic signals as needed; and remove/relocate conflicting traffic signal equipment including traffic signal poles, standards, and cabinets. Additionally, all existing vehicle loop detectors within the project limits will be discontinued by City

of Milwaukee forces prior to paving operations, or in coordination with paving operations. This work will take 30 working days to complete.

*Replace last three paragraphs under section titled **C.6. Water Works** with the following:*

Milwaukee Water Works anticipates hydrant relocation work will begin on April 4, 2022 and this work will take 20 working days.

Water manholes will be adjusted by the contractor as part of the paving project. See item Adjusting Water Manholes Frame and Lids.

Contact Mr. Dave Goldapp at (414) 286-6301 or (414) 708-2695 for coordination of the work.

*Replace entire section titled **F. Midwest Fiber Network (MWFN)** with the following:*

**F. Midwest Fiber Network (MWFN)**

Midwest Fiber Networks has underground facilities within the limits of the project. Contact Network Operations Center [NOC] at (866) 861-1661 to arrange verification for active facilities.

Midwest Fiber Networks forces will place fiber optic underneath sidewalk in the northern pedestrian way along E Chambers Street to a point crossing Humboldt Boulevard to its eastern pedestrian way at the following station:

Station 152+13

Midwest Fiber Networks forces will place fiber optic underneath sidewalk in the eastern pedestrian way within Humboldt Boulevard at the following stations and offset:

Station 152+13 to Station 155+72

Midwest Fiber Networks forces will place fiber optic underneath E Chambers Street at the following station to an existing handhole:

Station 155+72

Midwest Fiber Network anticipates fiber optic cable work will begin on February 14, 2022 and will take 15 working days.

Contact Cori Schmuki at (414) 459-3561 or (414) 349-2764 with questions or concerns.

*Replace paragraphs three and four under section titled **I. WE Energies - Electric** with the following:*

WE Energies – Electric forces will conduct work to adjust manhole frames and covers to the proposed roadway grades in conjunction with paving operations. WE Energies – Electric manhole frames will have to be adjusted before paving. For manhole frame adjustments, the contractor is required to provide a 14 working day notice (and a 3 working day reminder notice) to inform the utility that the site is ready. It is anticipated that this work will take 20 days to complete adjust manhole frames and covers. Please call (414) 840-4712 or (414) 540-5108 to make the notifications.

Exercise caution when excavating near any gas facilities. It is imperative that the highway contractor contact WE Energies before removing electrical underground cables (or unidentified gas facilities) to verify that they have been discontinued and carry no electrical current (or natural gas). The contractor must not assume that unmarked facilities have been discontinued. At no time is it acceptable to push, pull, cut, or drill an unmarked facility without explicit consent from WE Energies. Contractor must call the WE Energies 24 hour Dispatch lines to arrange this verification.

*Replace the eight paragraphs under section titled J. WE Energies - Gas with the following:*

Gas valves will be adjusted by WE Energies staff during construction in coordination with the paving contractor. WE Energies – Gas forces will conduct work to adjust gas valves. These gas valves will have to be adjusted before paving. For gas valve adjustments, the contractor is required to provide a 14 working day notice (and a 3 working day reminder notice) to inform the utility that the site is ready. It is anticipated that work will take 20 days to complete gas valve adjustments.

Please call 1 (800) 261-5325 to make the notifications, to get identifications if gas facilities are live, and for gas emergencies.

The contractor will be required to work around, protect, and support the gas mains.

Any facilities not explicitly identified as being relocated and/or adjusted have been deemed to be not in conflict and will remain in place as is. WE Energies has determined that the project is constructible with these facilities left within the work zone. The contractor will be required to work around existing WE Energies Gas facilities.

There is to be exercised caution when excavating near any gas facilities. It is imperative that the highway contractor contact WE Energies before removing any gas facilities or electrical underground cables, to verify that they have been discontinued and carry no natural gas or electrical current. The contractor must not assume that unmarked facilities have been discontinued. At no time is it acceptable to push, pull, cut, or drill an unmarked facility without explicit consent from WE Energies. Call WE Energies 24 hour Dispatch lines to arrange this verification.

Work will be complete by May 15, 2022.

WE Energies Electric Dispatch # 1 (800) 622-4797

WE Energies Gas Dispatch # 1 (800) 261-5325

Contact Alex Dantinne at (920) 621-6903 or Bob Sweigart at (414) 935-4438 with questions or concerns.

*Replace entire section titled K. Windstream with the following:*

Windstream has underground facilities within the limits of the project with no anticipated changes. Contact Lori Ketter at (414) 274-9215 with questions or concerns.

END OF ADDENDUM