



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

January 25, 2022

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #24: 4348-05-71, WISC 2022175**  
**T Rockland, CTH JJ**  
**Manitowoc River Bridge**  
**CTH JJ**  
**Manitowoc County**

### Letting of February 8, 2022

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
4	Traffic

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0420	Traffic Control Barricades, Type III	Days	2,178	297	2,475
643.0705	Traffic Control Warning Lights, Type A	Days	3,388	462	3,850
643.0900	Traffic Control Signs	Days	11,858	1,617	13,475

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
646.6464	Cold Weather Marking Epoxy 4-Inch	LF	0	2,571	2,571

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
15	Miscellaneous Quantities – Updates to Quantities

**Other**

Revise contract completion time from 65 working days contract to a completion date of November 11, 2022.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 1**

**4348-05-71**

**January 25, 2022**

**Special Provisions**

**3. Prosecution and Progress.**

*Replace paragraph two with the following:*

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

**4. Traffic.**

*Add the following paragraph after the first paragraph.*

Do not close, restrict, or alter CTH JJ travel lanes prior to June 1, 2022.

**Schedule of Items**

Attached, dated January 25, 2022, are the revised Schedule of Items Pages 4 and 5.

**Plan Sheets**

The following 8½ x 11-inch sheet is attached and made part of the plans for this proposal:

Revised: 15

END OF ADDENDUM

**REMOVING SIGNS TYPE II AND REMOVING SMALL SIGN SUPPORTS**

STATION DIR	LOCATION	DESCRIPTION	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORTS EACH
CATEGORY 0010				
104+05	RT CTH JJ	OBJECT MARKER	1	1
104+14	LT CTH JJ	OBJECT MARKER	1	1
106+68	RT CTH JJ	OBJECT MARKER	1	1
106+78	LT CTH JJ	OBJECT MARKER	1	1
PROJECT TOTALS			4	4

**SIGNS REFLECTIVE TYPE II & POSTS WOOD**

SIGN NO.	STATION DIR	LOCATION	CODE	SIGN SIZE HORIZ X VERT IN X IN	634.0612 POSTS WOOD 4X6-INCH X 12-FT EACH	637.2230 SIGNS TYPE II REFLECTIVE F SF
CATEGORY 0010						
1	103+98	LT CTH JJ	W5-52R	12 X 36	1	3.00
2	103+87	RT CTH JJ	W5-52L	12 X 36	1	3.00
3	106+95	LT CTH JJ	W5-52R	12 X 36	1	3.00
4	106+83	RT CTH JJ	W5-52L	12 X 36	1	3.00
PROJECT TOTAL					4	12

**TRAFFIC CONTROL**

LOCATION	EST. SERVICE PERIOD DAYS	643.0420 BARRICADES TYPE III NO DAYS	643.0705 WARNING LIGHTS TYPE A NO DAYS	643.0900 SIGNS NO DAYS	643.5000 TRAFFIC CONTROL EACH
CTH JJ	125	14	20	7	---
DETOUR	125	4	8	91	---
UNDISTRIBUTED	---	225	350	1225	1
PROJECT TOTALS		2,475	3,850	13,475	1

**MARKING LINE**

STATION - STATION	LOCATION	EPOXY 4-INCH (WHITE) LF	EPOXY 4-INCH (YELLOW) LF	646.6464 COLD WEATHER MARKING EPOXY 4-INCH LF
101+47 - 109+38	CTH JJ	1,582	989	2,571
PROJECT TOTALS		2,571		2,571

**CONSTRUCTION STAKING**

STATION TO STATION	LOCATION	650.4500 CONSTRUCTION STAKING SUBGRADE LF	650.5000 CONSTRUCTION STAKING BASE LF	650.9910 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL LS	650.9920 CONSTRUCTION STAKING SLOPE STAKES LF
101+05 - 104+06	CTH JJ	301	301	---	301
106+75 - 109+87	CTH JJ	312	312	---	312
UNDISTRIBUTED		---	---	1	---
PROJECT TOTALS		613	613	1	613

**SAW CUTTING**

STATION	DIR	LOCATION	690.0150 SAWING ASPHALT LF
101+47	R/L	STH JJ	25
109+38	R/L	CTH JJ	25
PROJECT TOTALS			50

Addendum No. 01  
ID 4348-05-71  
Revised Sheet 15  
January 25, 2022



Proposal Schedule of Items

Proposal ID: 20220208024 Project(s): 4348-05-71

Federal ID(s): WISC 2022175

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	629.0210 Fertilizer Type B	2.000 CWT	_____.	_____.
0100	630.0130 Seeding Mixture No. 30	43.000 LB	_____.	_____.
0102	630.0160 Seeding Mixture No. 60	13.000 LB	_____.	_____.
0104	630.0200 Seeding Temporary	43.000 LB	_____.	_____.
0106	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH	_____.	_____.
0108	637.2230 Signs Type II Reflective F	12.000 SF	_____.	_____.
0110	638.2602 Removing Signs Type II	4.000 EACH	_____.	_____.
0112	638.3000 Removing Small Sign Supports	4.000 EACH	_____.	_____.
0114	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0116	643.0420 Traffic Control Barricades Type III	2,475.000 DAY	_____.	_____.
0118	643.0705 Traffic Control Warning Lights Type A	3,850.000 DAY	_____.	_____.
0120	643.0900 Traffic Control Signs	13,475.000 DAY	_____.	_____.
0122	643.5000 Traffic Control 01. 4348-05-71	1.000 EACH	_____.	_____.
0124	645.0111 Geotextile Type DF Schedule A	84.000 SY	_____.	_____.
0126	645.0120 Geotextile Type HR	444.000 SY	_____.	_____.
0128	646.1020 Marking Line Epoxy 4-Inch	2,571.000 LF	_____.	_____.
0130	650.4500 Construction Staking Subgrade	613.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20220208024 Project(s): 4348-05-71

Federal ID(s): WISC 2022175

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0132	650.5000 Construction Staking Base	613.000 LF	_____.	_____.
0134	650.9910 Construction Staking Supplemental Control (project) 01. 4348-05-71	LS	LUMP SUM	_____.
0136	650.9920 Construction Staking Slope Stakes	613.000 LF	_____.	_____.
0138	690.0150 Sawing Asphalt	50.000 LF	_____.	_____.
0140	715.0502 Incentive Strength Concrete Structures	6,018.000 DOL	1.00000	6,018.00
0142	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0144	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. 105+40	1.000 EACH	_____.	_____.
0146	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0148	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0150	646.6464 Cold Weather Marking Epoxy 4-Inch	2,571.000 LF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.