



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

March 2, 2022

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #28: 1166-07-79, WISC 2022253
Coloma - Plainfield
Cottonville Avenue to CTH O, SB
IH 39
Waushara County

Letting of March 8, 2022

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
460.7224	HMA Pavement 4 HT 58-28 S	Ton	26,858	-3,485	23,373

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
6	Shaded inside shoulder black for full depth of HMA Pavement and revised layer thicknesses to the bottom Proposed Typical Section.
9	Revised the note in the Plan View of the HMA Mill & Overlay At Maintenance Crossovers Detail to reflect the new SDD being used.
62	Revised line item quantities and total quantities for item 460.7224 HMA Pavement 4 HT 58-28 S.
63	Revised line item quantities and total quantities for item 460.7224 HMA Pavement 4 HT 58-28 S.
64	Revised quantities in the PWL table per changes on sheets 62 & 63.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1166-07-79

March 2, 2022

Special Provisions

3. Prosecution and Progress.

Replace entire article language with the following:

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment.

Maintain a minimum of 1 mile between lane closures.

Construct from Station 606+00 to Station 803+79 in Stages 1 through 7. Construct stages 8, 9 & 10 during stages 1 through 7. Construct from Station 409+22 to Station 606+00 in Stages 11 through 14.

Complete Stages 1, 2 and 3 prior to Memorial Day.

Open both lanes of IH 39 SB for the Memorial Day holiday restrictions.

Begin Stage 4 after Memorial Day.

Complete Stages 4, 5, 8, 9 & 10 prior to the Independence Day holiday restrictions.

During Stages 6, 7 and 11 through 14 open both lanes of IH 39 SB between 7 pm Saturday and 6 am Monday pm on non-holiday weekends from Independence Day to Labor Day.

Open both lanes of IH 39 SB for the Independence Day and Labor Day holiday restrictions.

Allow mainline IH 39 SB and mainline CTH V traffic to run on milled surface for up to 96 hours.

Close CTH V ramps for up to 3 weekdays maximum to perform mill and overlay. The 3 weekdays shall be between a Monday and Friday.

Coordinate CTH V ramp closure with Project 1166-08-79 and Project 6170-00-73. Do not close STH 21 ramps and CTH V ramps at the same time.

Project 6170-00-73 uses NB IH 39, the CTH V interchange and SB IH 39 as a detour route while the NB IH 39 off-ramp at STH 21 is constructed. Project 1166-07-79 must close CTH V on-ramp to SB IH 39 for 3 days maximum during the NB IH 39 off-ramp at STH 21 closure. During these 3 days, a change to the detour for project 6170-0073 traffic is required. The detour route is CTH V, which was used during Stage 5 of project 1166-08-79. Because the STH 21 on-ramp to SB IH 39 and CTH V on-ramp to SB IH 39 cannot be closed at the same time, the signs detailed in the 1166-08-79 plan will need to be erected during the CTH V on-ramp to SB IH 39 closure. Coordination is required between contractors for project 6170-00-73, 1166-07-79 and 1166-08-79 to implement this 3-day detour.

Stage 1: Install traffic control devices for Stage 1. Close outside lane and shoulder, fill existing rumble strip in areas of concrete pavement removal, remove existing edge line pavement markings in areas of rumble strip filling, remove existing ramp gore pavement marking, install temporary pavement marking for Stage 2.

Stage 2: Install traffic control devices for Stage 2. Close inside lane and shoulder. Base patch median side lane concrete joints, in areas of concrete removal remove concrete pavement, excavate to subgrade, place base aggregate dense, repair underdrains, pave HMA pavement lower layers and dress shoulders, install

asphalt wedges adjacent to edges of higher existing pavement, install temporary pavement marking for Stage 3.

Place asphalt in base patches up to existing grade within 72 hours of joint removal.

Stage 3: Install traffic control devices for Stage 3. Close outside lane and shoulder. Base patch outside lane concrete joints, in areas of concrete removal remove concrete pavement, excavate to subgrade, place base aggregate dense, repair underdrains, pave HMA pavement lower layers and dress shoulders, install asphalt wedges adjacent to edges of higher existing pavement, install temporary pavement marking for Stage 4.

Place asphalt in base patches up to existing grade within 72 hours of joint removal.

Stage 4: Install traffic control devices for Stage 4. Close inside lane and shoulder. Remove asphaltic surface milling on inside lane and shoulder, pave HMA pavement lower layers on inside lane and shoulder, dress shoulder, install temporary pavement marking for Stage 5.

Stage 5: Install traffic control devices for Stage 5. Close outside lane and shoulder. Remove asphaltic surface milling on outside lane and shoulder, install concrete barrier, grade for energy absorbing terminals, pave HMA pavement lower and upper layers on outside lane and shoulder, remove existing beam guard, install new MGS beam guard, remove asphaltic surface milling on CTH V, pave HMA pavement surface layer on CTH V, install detour for CTH V ramp work and close ramps, remove asphaltic surface milling on CTH V ramps, pave HMA pavement surface layers on CTH V ramps, dress shoulders.

Stage 6: Install traffic control devices for Stage 6. Close inside lane and shoulder. Pave HMA pavement surface layer on inside lane and shoulder, remove asphaltic surface milling on median crossovers, pave HMA pavement surface layer on median crossovers, remove existing beam guard, install new MGS beam guard, install rumble strip on inside shoulder, install permanent pavement marking on inside lane and shoulder, dress shoulder.

Stage 7: Install traffic control devices for Stage 7. Close outside lane and shoulder. Install rumble strip on outside shoulder, install permanent pavement marking on outside shoulder and CTH V ramps.

Upon completion of Stage 7 open IH 39 to 2 lanes of traffic from Station 606+00 to Station 803+79. Begin Stage 8.

Stage 8: Install traffic control devices for Stage 8. Close outside lane and shoulder, fill existing rumble strip in areas of concrete pavement and concrete approach slab removal, remove existing edge line pavement markings in areas of rumble strip filling, install temporary pavement marking for Stage 9.

Stage 9: Install traffic control devices for Stage 9. Close inside lane, shoulder and weigh station. Base patch median side lane concrete joints, in areas of concrete removal remove concrete pavement and approach slabs, excavate to subgrade, place base aggregate dense, repair underdrains, install concrete approach slabs, pave HMA pavement lower layers and dress shoulders, install temporary pavement marking for Stage 10.

Place asphalt in base patches up to existing grade within 72 hours of joint removal.

Stage 10: Install traffic control devices for Stage 10. Close outside lane and shoulder. Base patch outside lane concrete joints, in areas of concrete removal remove concrete pavement, approach slabs and surface drains, excavate to subgrade, place base aggregate dense, repair underdrains, install concrete approach slabs and surface drain, pave HMA pavement lower layers and dress shoulders, install temporary pavement marking for Stage 11.

Place asphalt in base patches up to existing grade within 72 hours of joint removal.

Stage 11: Install traffic control devices for Stage 11. Close inside lane, shoulder and weigh station. Remove asphaltic surface milling on inside lane, shoulder and weigh station ramps, pave HMA pavement lower layers on inside lane and shoulder, pave HMA pavement surface layer on weigh station ramps, dress shoulder.

Stage 12: Install traffic control devices for Stage 12. Close outside lane and shoulder. Remove asphaltic surface milling on outside lane and shoulder, pave HMA pavement lower and upper layers on outside lane and shoulder, remove existing beam guard, install new MGS beam guard, dress shoulders.

Stage 13: Install traffic control devices for Stage 13. Close inside lane, shoulder and weigh station. Pave HMA pavement surface layer on inside lane and shoulder, remove asphaltic surface milling on median crossovers, pave HMA pavement surface layer on median crossovers, remove existing beam guard, install new MGS beam guard, install rumble strip on inside shoulder, install permanent pavement marking on inside lane and shoulder, install permanent pavement markings for weigh station, dress shoulder.

Stage 14: Install traffic control devices for Stage 14. Close outside lane and shoulder. Install rumble strip on outside shoulder, install permanent pavement marking on outside shoulder.

Schedule of Items


Attached, dated March 2, 2022, are the revised Schedule of Items Page 2.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 6, 9, and 62 – 64.

END OF ADDENDUM



PROPOSED CONCRETE BARRIER AT UNDERPASSES
 (SEE PLAN DETAILS FOR STATIONING)
 CTH C
 CTH V
 CTH O

PROPOSED TYPICAL SECTION
 STA 500+80 TO 501+68
 STA 503+03 TO 503+94
 STA 606+85 TO 611+88
 STA 686+15 TO 689+40
 STA 766+30 TO 770+48

NOTE: DURING STAGES 9 & 10, PAVE SURFACE LAYER AT BUTTERCUP AVENUE WITH HMA PAVEMENT 3 HT 58-28 S MIX TO FILL IN PAVEMENT DIP BETWEEN NEW CONCRETE UNDERDRAIN AND EXISTING ASPHALT UNDERDRAIN. MILL AND PATCH EXISTING ASPHALT UNDERDRAIN JOINTS DURING STAGE 11 FOR STAGE 12 TRAFFIC MILLING OPERATIONS, AND INSTALL WEDGE JOINTS DURING STAGE 11 FOR STAGE 12 TRAFFIC MILLING OPERATIONS.

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.

PROPOSED TYPICAL SECTION
 STA 409+22 TO 500+80
 STA 503+94 TO 606+85
 STA 611+88 TO 686+15
 STA 689+40 TO 766+30
 STA 770+48 TO 803+79

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.

PROPOSED TYPICAL SECTION
 STA 409+22 TO 500+80
 STA 503+94 TO 606+85
 STA 611+88 TO 686+15
 STA 689+40 TO 766+30
 STA 770+48 TO 803+79

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.

PROPOSED TYPICAL SECTION
 STA 409+22 TO 500+80
 STA 503+94 TO 606+85
 STA 611+88 TO 686+15
 STA 689+40 TO 766+30
 STA 770+48 TO 803+79

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.

PROPOSED TYPICAL SECTION
 STA 409+22 TO 500+80
 STA 503+94 TO 606+85
 STA 611+88 TO 686+15
 STA 689+40 TO 766+30
 STA 770+48 TO 803+79

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.


PROPOSED TYPICAL SECTION
 STA 409+22 TO 500+80
 STA 503+94 TO 606+85
 STA 611+88 TO 686+15
 STA 689+40 TO 766+30
 STA 770+48 TO 803+79

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.


PROPOSED TYPICAL SECTION
 STA 409+22 TO 500+80
 STA 503+94 TO 606+85
 STA 611+88 TO 686+15
 STA 689+40 TO 766+30
 STA 770+48 TO 803+79

NOTE: CONTRACTOR MAY ELECT TO SUBSTITUTE 4 HT 58-28 H MIX FOR 4 LT 58-28 S MIX ON OUTSIDE SHOULDERS. PAY ITEM WILL BE FOR 4 LT 58-28 S MIX.


Addendum No. 01
ID 1166-07-79
Revised Sheet 6
March 2, 2022



SECTION A-A



SECTION B-B



PLAN VIEW

NOTE: SEE S.D.D. "TRAFFIC CONTROL LANE CLOSURE, SPEED REDUCTION" FOR TRAFFIC CONTROL WHILE MILLING BUTT JOINT AND PAVING.

DETAIL FOR MAINTENANCE CROSSOVER

HMA OVERLAY AT MAINTENANCE CROSSOVERS
 STA 444+00
 STA 530+40
 STA 660+60
 STA 772+70
 SAT 803+20

Addendum No. 01
 ID 1166-07-79
 Revised Sheet 9
 March 2, 2022

PROJECT NO: 1166-07-79	COUNTY: WAUSHARA	SHEET: 9	E
FILE NAME: G:\WISDOT\1-391166-07-79 COTTONVILLE AVE TO CTHO (MIDDLE)\CADD\1166079\SHETS\OTHER\SHETS\PLAN\031001-CO.DWG	CONSTRUCTION DETAILS	1 IN:10 FT	WISDOT\CADD\SHETS 42
HWY: IH 39	HEIN, MIKE	PLOT NAME:	
LAYOUT NAME: 01			

PROJECT NO: 1166-07-79
FILE NAME: C:\MS07\391166-07-09 COTTONVILLE AVE TO CTH0 (MIDDLE)\CADD\1166079\SHEETS\OTHER\SHEETS\PLAN\030201-MQI.DWG
LAYOUT NAME: 09

HWY: IH 39

COUNTY: WAUSHARA

MISCELLANEOUS QUANTITIES

KUNERS, BRANDON

PLOT DATE: 2/25/2022 2:33 PM

PLOT BY: KUNERS, BRANDON

PLOT NAME:

1" = 1'

SHEET 62

E

WISDOT/CADD/SHEET-62

HMA PAVEMENT

CATEGORY	STATION	TO	STATION	LOCATION	455.0605				460.5224				460.7223				460.7424				REMARKS
					TACK COAT	TON	HMA PAVEMENT	TON	HMA PAVEMENT	TON	HMA PAVEMENT	TON	HMA PAVEMENT	TON	HMA PAVEMENT	TON	HMA PAVEMENT	TON	HMA PAVEMENT	TON	

STAGE 2																					
0010	606+84	-	611+88	MAINLINE	63	---	---	263	---	---	---	---	---	---	---	---	---	---	---	LOWER LAYERS	
0010	686+15	-	689+40	MAINLINE	40	---	---	170	---	---	---	---	---	---	---	---	---	---	---	---	
0010	766+30	-	770+48	MAINLINE	52	---	---	218	---	---	---	---	---	---	---	---	---	---	---	---	
0010	606+84	-	611+88	MAINLINE	63	---	---	---	---	---	---	---	---	---	---	---	---	---	---	88	
0010	686+15	-	689+40	MAINLINE	40	---	---	---	---	---	---	---	---	---	---	---	---	---	---	57	
0010	766+30	-	770+48	MAINLINE	52	---	---	---	---	---	---	---	---	---	---	---	---	---	---	73	
STAGE 2 SUBTOTAL					310	0	652	0	217	0	163	0	173	0	2643	0	1889	0	1960	0	788
STAGE 3																					
0010	606+84	-	611+88	MAINLINE	86	---	---	198	---	---	---	---	---	---	---	---	---	---	---	---	
0010	686+15	-	689+40	MAINLINE	56	---	---	127	---	---	---	---	---	---	---	---	---	---	---	---	
0010	766+30	-	770+48	MAINLINE	72	---	---	164	---	---	---	---	---	---	---	---	---	---	---	---	
0010	606+84	-	611+88	MAINLINE	86	---	---	---	---	---	---	---	---	---	---	---	---	---	---	66	
0010	686+15	-	689+40	MAINLINE	56	---	---	---	---	---	---	---	---	---	---	---	---	---	---	42	
0010	766+30	-	770+48	MAINLINE	72	---	---	---	---	---	---	---	---	---	---	---	---	---	---	55	
STAGE 3 SUBTOTAL					427	543	489	0	6738	0	130	0	1889	0	1960	0	788	0	918	0	163
STAGE 4																					
0010	602+00	-	606+85	MAINLINE	60	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	615+88	-	686+15	MAINLINE	924	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	689+40	-	766+30	MAINLINE	957	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	770+48	-	803+79	MAINLINE	415	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
STAGE 4 SUBTOTAL					2356	0	0	0	6738	0	130	0	1889	0	1960	0	788	0	918	0	163
STAGE 5																					
0010	602+00	-	606+85	MAINLINE	83	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	615+88	-	686+15	MAINLINE	1202	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	693+40	-	766+30	MAINLINE	1247	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	774+48	-	803+79	MAINLINE	502	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	602+00	-	606+85	MAINLINE	83	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	615+88	-	686+15	MAINLINE	1202	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	693+40	-	766+30	MAINLINE	1247	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	774+48	-	803+79	MAINLINE	502	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	53+39	-	64+65	ON RAMP	123	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	74+03	-	83+83	OFF RAMP	94	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	24+75	-	29+75	CTHV	124	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
STAGE 5 SUBTOTAL					6410	2567	0	4767	0	2818	0	4767	0	4767	0	3170	0	3170	0	3170	0
STAGE 6																					
0010	602+00	-	606+85	MAINLINE	60	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	615+88	-	686+15	MAINLINE	874	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	693+40	-	766+30	MAINLINE	907	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	774+48	-	803+79	MAINLINE	365	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	660+63	-		MAINTENANCE CROSSOVER	19	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	722+74	-		MAINTENANCE CROSSOVER	19	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
0010	803+19	-		MAINTENANCE CROSSOVER	19	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	
STAGE 6 SUBTOTAL					2264	0	0	0	3170	0	3170	0	3170	0	3170	0	3170	0	3170	0	
STAGE 9																					
0010	500+80	-	501+68	MAINLINE	15	---	---	84	---	---	---	---	---	---	---	---	---	---	---	---	
0010	503+03	-	503+94	MAINLINE	16	---	---	87	---	---	---	---	---	---	---	---	---	---	---	---	
STAGE 9 SUBTOTAL					31	0	171	0	0	0	0	0	0	0	0	0	0	0	0	0	0
CONTINUED NEXT PAGE																					

Addendum No. 01
 ID 1166-07-79
 Revised Sheet 62
 March 2, 2022

Addendum No. 01
ID 1166-07-79
Revised Sheet 63
March 2, 2022

CATEGORY	STATION	TO	STATION	LOCATION	TACK COAT GAL	455.0605 HMA PAVEMENT 4 LT 58-28 S	460.5224 HMA PAVEMENT 3 HT 58-28 S	460.7223 HMA PAVEMENT 4 HT 58-28 S	460.7424 HMA PAVEMENT 4 HT 58-28 H	REMARKS
STAGE 10	500+80	-	501+68	MAINLINE	15	38	46	---	---	
0010	503+03	-	503+94	MAINLINE	16	40	48	---	---	
				STAGE 10 SUBTOTAL	31	78	93	0	0	
STAGE 11	409+22	-	500+80	MAINLINE	1140	---	---	3259	---	LEVELING AND MIDDLE LAYER
0010	503+94	-	505+53	MAINLINE	27	---	---	77	---	LEVELING AND MIDDLE LAYER 10' INSIDE SHOULDER
0010	505+53	-	602+00	MAINLINE	1201	---	---	3433	---	LEVELING AND MIDDLE LAYER
0010	461+99	-	474+59	ON RAMP	161	---	---	---	266	WEIGH STATION
0010	497+73	-	501+22	OFF RAMP	49	---	---	---	78	WEIGH STATION
				STAGE 11 SUBTOTAL	2577	0	0	6770	344	
STAGE 12	409+22	-	500+80	MAINLINE	855	---	---	2462	---	LEVELING AND MIDDLE LAYER
0010	503+94	-	602+00	MAINLINE	915	---	---	2636	---	LEVELING AND MIDDLE LAYER
0010	409+22	-	501+68	MAINLINE	1582	1294	---	---	1208	SURFACE LAYER
0010	503+03	-	602+00	MAINLINE	1693	1386	---	---	1293	SURFACE LAYER
				STAGE 12 SUBTOTAL	5046	2680	0	5098	2501	
STAGE 13	409+22	-	501+68	MAINLINE	1151	---	---	---	1611	10' INSIDE SHOULDER
0010	503+03	-	505+53	MAINLINE	31	---	---	---	43	
0010	505+53	-	602+00	MAINLINE	1201	---	---	---	1681	
0010	443+99	-	602+00	MAINLINE	363	---	---	---	36	MAINTENANCE CROSSOVER
0010	530+38	-	602+00	MAINLINE	574	---	---	---	56	MAINTENANCE CROSSOVER
				STAGE 13 SUBTOTAL	3320	0	0	0	3427	
				TOTAL 0010	22,770	5,868	1,405	23,373	12,640	

PWL

CATEGORY	STATION	TO	STATION	LOCATION	460.0105.S HMA PERCENT WITHIN LIMITS (PWL) TEST STRIP VOLUMETRICS EACH	460.0110.S HMA PERCENT WITHIN LIMITS (PWL) TEST STRIP DENSITY EACH	460.2007 INCENTIVE DENSITY HMA PAVEMENT LONGITUDINAL JOINTS DOL
0010	409+22	-	803+79	TOTAL 0000	2	2	19,730
					2	2	19,730

Addendum No. 01
ID 1166-07-79
Revised Sheet 64
March 2, 2022

STATION - STATION	ROADWAY	LOCATION	MIXTURE USE	UNDERLYING SURFACE	BID ITEM	AVG LAYER DEPTH (IN)	TONS	QUALITY MANAGEMENT PROGRAM TO BE USED FOR		COMMENT			
								MIXTURE ACCEPTANCE	DENSITY ACCEPTANCE				
409+22 - 500+80 503+94 - 606+85 611+86 - 689+15 689+40 - 766+30 770+46 - 803+79	IH 39 SB	OVERLAY	UPPER LAYER	4 HT 58-28 S	4 HT 58-28 H	1.75	1606	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	DEPARTMENT INCENTIVE				
			MIDDLE LAYER	4 HT 58-28 S	4 HT 58-28 S	1.75	1661	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	DEPARTMENT INCENTIVE	INSIDE SHOULDER PAVED WITH INSIDE DRIVING LANE			
			LOWER LAYER	EXISTING CONCRETE PAVEMENT	4 HT 58-28 S	1.75	1661	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	INCENTIVE DENSITY HMA (QMP TESTING)				
			UPPER LAYER	4 HT 58-28 S	4 HT 58-28 H	1.75	11243	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	INCENTIVE DENSITY PWL HMA PAVEMENT 460.20005				
					DRIVING LANES	MIDDLE LAYER	4 HT 58-28 S	4 HT 58-28 S	1.75	9747	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	DEPARTMENT INCENTIVE	
						LOWER LAYER	EXISTING CONCRETE PAVEMENT	4 HT 58-28 S	1.85	10304	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	INCENTIVE DENSITY HMA (QMP TESTING)	
						UPPER LAYER	EXISTING HMA PAVEMENT	4 LT 58-28 S	2.25	5163	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
						UPPER LAYER	3 HT 58-28 S	4 HT 58-28 H	1.75	74	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	DEPARTMENT INCENTIVE	
			500+80 - 501+68 503+03 - 503+94 606+85 - 611+88 686+15 - 689+40 766+30 - 770+48	IH 39 SB	FULL DEPTH REPLACEMENT	MIDDLE LAYER	3 HT 58-28 S	3 HT 58-28 S	2	84	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
						LOWER LAYER	BASE AGGREGATE DENSE 1 1/4"	3 HT 58-28 S	3.25	137	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
UPPER LAYER	3 HT 58-28 S	4 HT 58-28 H				1.75	373	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	INCENTIVE DENSITY PWL HMA PAVEMENT 460.20005	INSIDE SHOULDER PAVED WITH INSIDE DRIVING LANE			
LOWER LAYER	3 HT 58-28 S	3 HT 58-28 S				2	426	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)				
		OUTSIDE SHOULDER				LOWER LAYER	BASE AGGREGATE DENSE 1 1/4"	3 HT 58-28 S	3.25	692	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
						UPPER LAYER	4 LT 58-28 S	4 LT 58-28 S	1.75	155	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
						MIDDLE LAYER	4 LT 58-28 S	4 LT 58-28 S	2	170	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
						LOWER LAYER	BASE AGGREGATE DENSE 1 1/4"	4 LT 58-28 S	3.25	276	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
	CTH V RAMPS	OVERLAY				UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 LT 58-28 S	1.75	15	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
						UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 HT 58-28 H	1.75	327	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
			UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 LT 58-28 S	1.75	25	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)				
			UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 LT 58-28 S	1.75	22	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)				
			CTH V	OVERLAY	DRIVING LANES	UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 HT 58-28 H	1.75	173	PWL INCENTIVE AIR VOIDS HMA PAVEMENT 460.2010	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)	
					UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 LT 58-28 S	1.75	22	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)		
					UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 HT 58-28 S	1.75	172	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)		
					UPPER LAYER	EXISTING ASPHALTIC PAVEMENT	4 HT 58-28 H	1.75	172	AS PER SS 460	INCENTIVE DENSITY HMA PAVEMENT 460.2000 (QMP TESTING)		



Proposal Schedule of Items

Proposal ID: 20220308028 Project(s): 1166-07-79

Federal ID(s): WISC 2022253

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	455.0605 Tack Coat	22,770.000 GAL	_____.	_____.
0036	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0038	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	2.000 EACH	_____.	_____.
0040	460.2000 Incentive Density HMA Pavement	21,090.000 DOL	1.00000	21,090.00
0042	460.2005 Incentive Density PWL HMA Pavement	22,730.000 DOL	1.00000	22,730.00
0044	460.2007 Incentive Density HMA Pavement Longitudinal Joints	19,730.000 DOL	1.00000	19,730.00
0046	460.2010 Incentive Air Voids HMA Pavement	51,440.000 DOL	1.00000	51,440.00
0048	460.5224 HMA Pavement 4 LT 58-28 S	5,868.000 TON	_____.	_____.
0050	460.7223 HMA Pavement 3 HT 58-28 S	1,405.000 TON	_____.	_____.
0052	460.7224 HMA Pavement 4 HT 58-28 S	23,373.000 TON	_____.	_____.
0054	460.7424 HMA Pavement 4 HT 58-28 H	12,640.000 TON	_____.	_____.
0056	465.0400 Asphaltic Shoulder Rumble Strips	75,290.000 LF	_____.	_____.
0058	603.1142 Concrete Barrier Type S42	150.000 LF	_____.	_____.
0060	603.8000 Concrete Barrier Temporary Precast Delivered	6,572.000 LF	_____.	_____.
0062	603.8125 Concrete Barrier Temporary Precast Installed	6,572.000 LF	_____.	_____.

