



Wisconsin Department of Transportation

May 5, 2022

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #03: 1011-01-65, WISC 2022 374
Madison - Portage
South County Line to STH 60
IH 039
Columbia County**

**1012-01-74, N/A
Madison - Portage
STH 60 Interchange, B-11-165 & 166
IH 039
Columbia County**

Letting of May 10, 2022

This is Addendum No. 04, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
51	Added special provision 51 outlining the requirements for completing work on new special provision item SPV. 0060.15 Emergency Response to Pavement Repairs.

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
416.1715	Concrete Pavement Repair SHES	SY	4,915	1,279	6,194
690.0250	Sawing Concrete	LF	41,404	1,898	43,302

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
465.0110	Asphaltic Surface Patching	Ton	0	20	20
SPV.0060.15	Emergency Response to Pavement Repairs	Each	0	10	10

Plan Sheets:

Revised Plan Sheets – 1011-01-65	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
21	Updated Miscellaneous Quantity Sheet

Revised Plan Sheets – 1012-01-74	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
215	Moved item 465.0475 onto added plan sheet 214A to match item numbering conventions.

Added Plan Sheets – 1012-01-74	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
214A	Added Misc. Quantity sheet to display quantities of the 2 added items associated with the emergency pavement repairs.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 04
1011-01-65/1012-01-74
May 5, 2022

Special Provisions

51. Emergency Response to Pavement Repairs, Item SPV.0060.15.

A Description

This special provision describes providing prompt response to an emergency repair request of damaged or deteriorated concrete or HMA pavement located on IH 39 or an IH 39 ramp. The provisions of this article will not be applicable during a project's winter shutdown period.

B Materials (Vacant)

C Construction

The contractor shall provide staff, equipment, and materials to the incident site within 45 minutes of receiving a repair request from the responding agency. The contractor shall consult with the department's representative on potential repair or replacement options to restore the damaged or deteriorated pavement section to a safe and drivable condition. Staff and equipment deployed shall be capable of completing the needed repairs as quickly as possible once repair work is started. The contractor shall provide a time log of when the repair request was received and when staff arrived at the incident site. This information shall be submitted to the engineer, for verification, within 24 hours of the repair completion.

Contact information for the contractor's responsible party (the person or persons in charge of coordinating and completing repair efforts) shall be submitted to the engineer at the pre-construction meeting. This person(s) shall be available 24/7 during the duration of this contract. The contact information for the department's representative will be supplied to the contractor at the pre-construction meeting.

If the contractor fails to be on-site of an incident with appropriate staff and equipment within 45 minutes of receiving a repair request, the department will assess the contractor \$2500 in liquidated damages for each 15-minute interval that the contractor is not present following the allotted 45-minute response time. Increments of 15 minutes or less will be assessed as a 15-minute increment. The engineer, or designated representative, will be the sole authority in determining assessable 15-minute increments. Liquidated damages will be assessed under the administrative item Failing to Open Road to Traffic.

Additional traffic control measures may be required depending on the severity and duration of the incident. The contractor shall provide any needed traffic control measures as directed by the department's representative.

D Measurement

The department will measure Emergency Response to Pavement Repairs as each individual response, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.15	Emergency Response to Pavement Repairs	EACH

Payment is full compensation for providing prompt response to an emergency repair request for damaged or deteriorated concrete or HMA pavement located within the project's construction limits.

The cost of providing the appropriate level of on-call staff, equipment, and materials for 24/7 incident response shall be included in the Mobilization bid item for this project.

The department will pay for concrete pavement or HMA pavement repairs under the respective concrete pavement or HMA pavement bid items in the contract.

The department will pay for any additional traffic control measures, if required, under the respective traffic control bid items in the contract.

(5/6/2019)

Schedule of Items

Attached, dated May 5, 2022, are the revised Schedule of Items Pages 4, 19, and 21.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

1011-01-65

Revised: 21

1012-01-74

Revised: 215

Added: 214A

END OF ADDENDUM

Addendum No. 04
 ID 1011-01-65
 Revised Sheet 21
 May 5, 2022

CONCRETE PAVEMENT

STATION	TO	STATION	416.0610 DRILLED TIE BARS	416.0620 DRILLED DOWEL BARS	416.1715 CONCRETE PAVEMENT REPAIR SHES	416.1725 CONCRETE PAVEMENT REPLACEMENT SHES	690.0250 SAWING CONCRETE	COMMENT
			(EACH)	(EACH)	(SY)	(SY)	(LF)	
1570+70'	'WB'	1594+00'	0	16	11	--	40	STAGE 1A
1594+00'	'WB'	1623+00'	0	16	12	--	41	
1623+00'	'WB'	1652+00'	0	0	--	--	--	
1652+00'	'WB'	1681+00'	0	32	23	--	82	
1681+00'	'WB'	1710+00'	0	48	34	--	122	
1710+00'	'WB'	1739+00'	0	32	25	--	84	
1739+00'	'WB'	1750+00'	0	48	33	--	120	
'WB' STAGE 1A TOTALS			0	192	138	0	489	
1570+70'	'WB'	1594+00'	161	912	650	188	2,593	STAGE 1B
1594+00'	'WB'	1623+00'	320	576	392	426	2,064	
1623+00'	'WB'	1652+00'	19	288	213	26	788	
1652+00'	'WB'	1681+00'	155	304	186	207	1,079	
1681+00'	'WB'	1710+00'	264	256	154	353	1,184	
1710+00'	'WB'	1739+00'	192	736	516	256	2,235	
1739+00'	'WB'	1750+00'	34	592	420	46	1,565	
'WB' STAGE 1B TOTALS			1,145	3,664	2,531	1,502	11,508	
'WB' TOTALS			1,145	3,856	2,669	1,502	11,997	
1570+75'	'EB'	1594+00'	0	32	22	--	79	STAGE 2A
1594+00'	'EB'	1623+00'	21	16	--	28	65	
1623+00'	'EB'	1652+00'	0	0	--	--	--	
1652+00'	'EB'	1681+00'	0	0	--	--	--	
1681+00'	'EB'	1710+00'	0	0	--	--	--	
1710+00'	'EB'	1739+00'	0	16	11	--	40	
1739+00'	'EB'	1750+00'	--	336	--	--	--	
'EB' STAGE 2A TOTALS			21	64	33	28	184	
1570+75'	'EB'	1594+00'	--	384	318	--	1030	STAGE 2B
1594+00'	'EB'	1623+00'	174	256	168	233	962	
1623+00'	'EB'	1652+00'	189	528	353	252	1,681	
1652+00'	'EB'	1681+00'	374	656	419	499	2,334	
1681+00'	'EB'	1710+00'	402	544	340	535	2,145	
1710+00'	'EB'	1739+00'	117	832	617	157	2,375	
1739+00'	'EB'	1750+00'	146	336	241	195	1,126	
'EB' STAGE 2B TOTALS			1,402	3,536	2,456	1,871	11,653	
'EB' TOTALS			1,423	3,600	2,489	1,899	11,837	
UNDISTRIBUTED			514	1,491	776	680	4,387	
PROJECT TOTALS			3,082	8,947	5,934	4,081	28,721	

** PATCHING TO BE EXTENDED 4 FEET PAST EXISTING
 TRANSVERSE JOINT. PATCHES SHALL BE 8-FEET MINIMUM.
 ***ALL ITEMS CATEGORY 0010 UNLESS OTHERWISE NOTED.

ASPHALT CENTERLINE RUMBLE STRIPS

465.0475		ASPHALT CENTERLINE RUMBLE STRIPS 2-LANE RURAL		REMARKS
CATEGORY	STATION	TO	STATION	LOCATION
0010	42+42 76+97		47+78 90+06	
				536 1,309
PROJECT ID 1012-01-74 TOTAL:				1,845

Addendum No. 04
 ID 1012-01-74
 Added Sheet 124A
 May 5, 2022

EMERGENCY RESPONSE TO PAVEMENT REPAIRS

CATEGORY	LOCATION	TON	465.0110		REMARKS
			ASPHALTIC SURFACE PATCHING	SPECIAL (EMERGENCY RESPONSE TO PAVEMENT REPAIRS)	
0010	NB IH 39 SB IH 39	10 10			5 5
PROJECT ID 1012-01-74 TOTAL:				20	10



Proposal Schedule of Items

Proposal ID: 20220510003 Project(s): 1011-01-65, 1012-01-74

Federal ID(s): N/A, WISC 2022374

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0094	416.1110 Concrete Shoulder Rumble Strips	8,587.000 LF	_____.	_____.
0096	416.1715 Concrete Pavement Repair SHES	6,194.000 SY	_____.	_____.
0098	416.1725 Concrete Pavement Replacement SHES	4,831.000 SY	_____.	_____.
0100	450.4000 HMA Cold Weather Paving	3,510.000 TON	_____.	_____.
0102	455.0605 Tack Coat	1,150.000 GAL	_____.	_____.
0104	460.2000 Incentive Density HMA Pavement	2,190.000 DOL	1.00000	2,190.00
0106	460.5224 HMA Pavement 4 LT 58-28 S	1,060.000 TON	_____.	_____.
0108	460.6224 HMA Pavement 4 MT 58-28 S	3,370.000 TON	_____.	_____.
0110	465.0125 Asphaltic Surface Temporary	1,540.000 TON	_____.	_____.
0112	465.0315 Asphaltic Flumes	61.000 SY	_____.	_____.
0114	465.0400 Asphaltic Shoulder Rumble Strips	1,200.000 LF	_____.	_____.
0116	465.0425 Asphaltic Shoulder Rumble Strips 2-Lane Rural	6,848.000 LF	_____.	_____.
0118	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	1,845.000 LF	_____.	_____.
0120	502.0100 Concrete Masonry Bridges	1,386.000 CY	_____.	_____.
0122	502.3200 Protective Surface Treatment	2,424.000 SY	_____.	_____.
0124	502.3210 Pigmented Surface Sealer	274.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20220510003 Project(s): 1011-01-65, 1012-01-74

Federal ID(s): N/A, WISC 2022374

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0556	673.1225.S Install Pole Mounted Cabinet	1.000 EACH	_____.	_____.
0558	674.0300 Remove Cable	4,085.000 LF	_____.	_____.
0560	675.0300 Install Mounted Controller Microwave Detector Assembly	2.000 EACH	_____.	_____.
0562	677.0150 Install Camera Pole 50-FT	1.000 EACH	_____.	_____.
0564	677.0200 Install Camera Assembly	1.000 EACH	_____.	_____.
0566	677.9051.S Removing 50-FT Camera Pole	1.000 EACH	_____.	_____.
0568	677.9200.S Removing CCTV Camera	1.000 EACH	_____.	_____.
0570	678.0006 Install Fiber Optic Cable Outdoor Plant 6-CT	1,090.000 LF	_____.	_____.
0572	678.0300 Fiber Optic Splice	4.000 EACH	_____.	_____.
0574	678.0400 Fiber Optic Termination	6.000 EACH	_____.	_____.
0576	678.0500 Communication System Testing	LS	LUMP SUM	_____.
0578	678.0600 Install Ethernet Switches	1.000 EACH	_____.	_____.
0580	690.0150 Sawing Asphalt	3,858.000 LF	_____.	_____.
0582	690.0250 Sawing Concrete	43,302.000 LF	_____.	_____.
0584	715.0502 Incentive Strength Concrete Structures	500.000 DOL	1.00000	500.00
0586	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	300.000 HRS	5.00000	1,500.00



Proposal Schedule of Items

Proposal ID: 20220510003 Project(s): 1011-01-65, 1012-01-74

Federal ID(s): N/A, WISC 2022374

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0616	SPV.0060 Special 13. Temporary Lighting System Northbound Ramp Terminal	1.000 EACH	_____.	_____.
0618	SPV.0060 Special 14. Construction Staking Roundabout Terminal	1.000 EACH	_____.	_____.
0620	SPV.0090 Special 01. Drain Slotted Vane Longitudinal	1,020.000 LF	_____.	_____.
0622	SPV.0090 Special 02. Fill and Restore Existing Concrete Rumble Strips	20,743.000 LF	_____.	_____.
0624	SPV.0090 Special 03. Concrete Barrier Temporary Precast Left in Place	3,904.000 LF	_____.	_____.
0626	SPV.0165 Special 01. Temporary Wall Wire Faced Mechanically Stabilized Earth	1,657.000 SF	_____.	_____.
0628	SPV.0165 Special 02. Wall Concrete Panel Mechanically Stabilized Earth	6,795.000 SF	_____.	_____.
0630	465.0110 Asphaltic Surface Patching	20.000 TON	_____.	_____.
0632	SPV.0060 Special 15. Emergency Response to Pavement Repairs	10.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.