



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

September 29, 2022

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #09: 7505-00-76, WISC 2023009
Northfield – Alma Center
CTH FF to STH 95
STH 121
Jackson County

Letting of October 11, 2022

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
203.0100	Removing Small Pipe Culvert	EACH	11	-2	9
643.0910	Covering Signs Type I	EACH	70	-68	2
643.0920	Covering Signs Type II	EACH	245	-238	7

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
29	Miscellaneous Quantities (1 Updated Bid Item)
36	Miscellaneous Quantities (2 Updated Bid Items)

Schedule of Items

Attached, dated September 29, 2022, are the revised Schedule of Items Pages 1 and 6.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 29 and 36.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 01
ID 7505-00-76
Revised Sheet 29
September 29, 2022

REMOVING SMALL PIPE CULVERT

PROJECT CATEGORY	LOCATION	STATION - STATION	(EACH)	REMARKS
7505-00-76			203,0100	
0010	CTHFF - CHURCH RD	190+01	1	30" C/CKP
	DEGROOT RD - BURNETTE RD	248+49	1	24" C/CKP
	DEGROOT RD - BURNETTE RD	294+78	1	24" C/CKP
	BURNETTE RD - HIXTON LEVIS RD	314+08	1	30" C/CKP
	BURNETTE RD - HIXTON LEVIS RD	347+13	1	30" C/CKP
	SE BURNETTE RD - BRANCH RD	422+14	1	30" C/CKP
	BRANCH RD - N GIESE RD	454+15	1	24" C/CKP
	BRANCH RD - N GIESE RD	468+83	1	24" C/CKP
	OLD STAGE RD - STH 95	547+32	1	24" C/CKP
PROJECT 7505-00-76 TOTAL				9

REMOVING GUARDRAIL

PROJECT CATEGORY	LOCATION	STATION - STATION	OFFSET	(LF)
7505-00-76				204,0165
0010	TOWNHOUSE RD - SE BURNETTE RD	380+59 - 382+87	LT	228
	TOWNHOUSE RD - SE BURNETTE RD	380+63 - 382+90	RT	227
	TOWNHOUSE RD - SE BURNETTE RD	407+29 - 408+68	LT	140
	TOWNHOUSE RD - SE BURNETTE RD	407+29 - 408+70	RT	141
PROJECT 7505-00-76 TOTAL				736

CLEARING AND GRUBBING

PROJECT CATEGORY	LOCATION	STATION - STATION	(STA)	CLEARING GRUBBING (STA)
7505-00-76			201,0105	201,0205
0010	CTHFF - CHURCH RD	183+38 - 199+86	2	2
	CHURCH RD - DEGROOT RD	199+86 - 242+72	1	1
	DEGROOT RD - BURNETTE RD	242+72 - 307+74	-	-
	BURNETTE RD - HIXTON LEVIS RD	307+74 - 361+88	-	-
	HIXTON LEVIS RD - TOWNHOUSE RD	361+88 - 376+37	-	-
	TOWNHOUSE RD - SE BURNETTE RD	376+37 - 417+69	1	1
	SE BURNETTE RD - BRANCH RD	417+69 - 428+06	1	1
	BRANCH RD - N GIESE RD	428+06 - 483+15	1	1
	N GIESE RD - OLD STAGE RD	483+15 - 535+83	-	-
	OLD STAGE RD - STH 95	535+83 - 550+35	-	-
PROJECT 7505-00-76 TOTAL				6

REMOVING ASPHALTIC SURFACE

PROJECT CATEGORY	LOCATION	STATION - STATION	(SY)	BUTT JOINTS (SY)	MILLING (SY)
7505-00-76			204,0110	204,0115	204,0120
0010	CTHFF - CHURCH RD	183+38 - 199+86	-	97	4,587
	CHURCH RD - DEGROOT RD	199+86 - 242+72	-	53	11,800
	DEGROOT RD - BURNETTE RD	242+72 - 307+74	-	59	17,587
	BURNETTE RD - HIXTON LEVIS RD	307+74 - 361+88	-	28	14,601
	HIXTON LEVIS RD - TOWNHOUSE RD	361+88 - 376+37	940	97	3,368
	TOWNHOUSE RD - SE BURNETTE RD	376+37 - 417+69	-	257	12,318
	SE BURNETTE RD - BRANCH RD	417+69 - 428+06	-	105	3,240
	BRANCH RD - N GIESE RD	428+06 - 483+15	-	100	16,529
	N GIESE RD - OLD STAGE RD	483+15 - 535+83	-	46	14,793
	OLD STAGE RD - STH 95	535+83 - 550+35	-	199	4,166
PROJECT 7505-00-76 TOTAL				940	1,040

Addendum No. 01
ID 7505-00-76
Revised Sheet 36
September 29, 2022

TRAFFIC CONTROL

PROJECT CATEGORY	LOCATION	MOVING SIGNS TYPE II (EACH)	DRUMS (DAY)	BARRICADES TYPE III (DAY)	WARNING LIGHTS TYPE A (DAY)	SIGNS (DAY)	FOR INFORMATION ONLY, PAID FOR UNDER ITEM 643.0910		FOR INFORMATION ONLY, PAID FOR UNDER ITEM 643.0927		
							NUMBER OF CYCLES	NUMBER OF SIGNS	COVERING TYPE (EACH)	NUMBER OF SIGNS	COVERING TYPE (EACH)
7505-00-76	0010	STAGE 1	-	-	-	20,168	-	-	-	-	15
		DETOUR	-	805	1,330	4,732	1	2	2	7	7
UNDISTRIBUTED		10	-	-	-	-	-	-	-	-	-
PROJECT 7505-00-76 TOTAL		10	22,880	805	1,330	24,900	-	2	7	7	100

PAVEMENT MARKING

PROJECT CATEGORY	LOCATION	STATION - STATION	ASPHALTIC CENTERLINE RUMBLE STRIPS 2-LANE RURAL (LF)		MARKINGS LINE EPOXY 4-INCH (LF)	
			WHITE (LF)	YELLOW (LF)	WHITE (LF)	YELLOW (LF)
7505-00-76	0010	183+38 - 199+86	1,042	3,154	3,278	3,278
		199+86 - 242+72	3,885	8,502	5,919	5,919
		242+72 - 307+74	7,000	12,989	5,081	5,081
		307+74 - 361+88	5,036	10,746	7,116	7,116
		361+88 - 376+37	656	2,706	2,106	2,106
		376+37 - 417+69	3,110	8,311	8,312	8,320
		417+69 - 428+06	631	1,961	1,320	1,330
		428+06 - 483+15	5,108	10,853	10,119	10,129
		483+15 - 535+83	4,579	10,414	6,751	6,754
		535+83 - 550+35	1,268	2,868	1,965	1,968
		PROJECT 7505-00-76 TOTAL		32,615	72,554	51,966

TEMPORARY PAVEMENT MARKING

PROJECT CATEGORY	LOCATION	STATION - STATION	TEMPORARY MARKING 4-INCH (LF)	
			WHITE (LF)	YELLOW (LF)
7505-00-76	0010	183+38 - 199+86	6,308	6,556
		199+86 - 242+72	17,004	11,838
		242+72 - 307+74	25,918	10,161
		307+74 - 361+88	21,492	14,232
		361+88 - 376+37	5,532	4,213
		376+37 - 417+69	16,629	16,632
		417+69 - 428+06	3,920	2,650
		428+06 - 483+15	21,696	20,248
		483+15 - 535+83	20,811	13,505
		535+83 - 550+35	5,721	3,935
		PROJECT 7505-00-76 TOTAL		145,031

PROJECT NO: 7505-00-76

HWY: STH 121

COUNTY: JACKSON

MISCELLANEOUS QUANTITIES

SHEET

36

FILE NAME:

ORIGINATOR: KL ENGINEERING, INC.

REV. DATE:

PRINT DATE: September 28, 2022



Proposal Schedule of Items

Proposal ID: 20221011009 Project(s): 7505-00-76

Federal ID(s): WISC 2023009

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	6.000 STA	_____.	_____.
0004	201.0205 Grubbing	6.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	9.000 EACH	_____.	_____.
0008	203.0220 Removing Structure (structure) 01. (239+37)	1.000 EACH	_____.	_____.
0010	203.0220 Removing Structure (structure) 02. (239+47)	1.000 EACH	_____.	_____.
0012	204.0110 Removing Asphaltic Surface	940.000 SY	_____.	_____.
0014	204.0115 Removing Asphaltic Surface Butt Joints	1,040.000 SY	_____.	_____.
0016	204.0120 Removing Asphaltic Surface Milling	103,000.000 SY	_____.	_____.
0018	204.0165 Removing Guardrail	736.000 LF	_____.	_____.
0020	204.9060.S Removing (item description) 01. Apron Endwall	5.000 EACH	_____.	_____.
0022	204.9060.S Removing (item description) 02. Cattle Pass	1.000 EACH	_____.	_____.
0024	204.9090.S Removing (item description) 01. Retaining Wall	20.000 LF	_____.	_____.
0026	205.0100 Excavation Common	4,950.000 CY	_____.	_____.
0028	213.0100 Finishing Roadway (project) 01. 7505- 00-76	1.000 EACH	_____.	_____.
0030	305.0110 Base Aggregate Dense 3/4-Inch	1,940.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20221011009 Project(s): 7505-00-76

Federal ID(s): WISC 2023009

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0152	630.0130 Seeding Mixture No. 30	59.000 LB	_____.	_____.
0154	630.0500 Seed Water	280.000 MGAL	_____.	_____.
0156	633.5200 Markers Culvert End	29.000 EACH	_____.	_____.
0158	638.2102 Moving Signs Type II	10.000 EACH	_____.	_____.
0160	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0162	643.0300 Traffic Control Drums	22,680.000 DAY	_____.	_____.
0164	643.0420 Traffic Control Barricades Type III	805.000 DAY	_____.	_____.
0166	643.0705 Traffic Control Warning Lights Type A	1,330.000 DAY	_____.	_____.
0168	643.0900 Traffic Control Signs	24,900.000 DAY	_____.	_____.
0170	643.0910 Traffic Control Covering Signs Type I	2.000 EACH	_____.	_____.
0172	643.0920 Traffic Control Covering Signs Type II	7.000 EACH	_____.	_____.
0174	643.1050 Traffic Control Signs PCMS	100.000 DAY	_____.	_____.
0176	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0178	645.0120 Geotextile Type HR	420.000 SY	_____.	_____.
0180	646.1020 Marking Line Epoxy 4-Inch	124,500.000 LF	_____.	_____.
0182	649.0105 Temporary Marking Line Paint 4-Inch	249,000.000 LF	_____.	_____.
0184	649.0120 Temporary Marking Line Epoxy 4-Inch	52,000.000 LF	_____.	_____.