



Wisconsin Department of Transportation

November 4, 2022

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #04: 3997-00-78, WISC 2023014
C of Watertown, N. Fourth Street
Jones St to Center St
Local Street
Dodge & Jefferson Counties

Letting of November 8, 2022

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
14	Geotextile Pavement Interlayer, Item SPV.0180.01

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

3997-00-78

November 4, 2022

14. Geotextile Pavement Interlayer, Item SPV.0180.01.

Replace entire article language with the following:

A Description

This special provision describes the geotextile interlayer.

B Materials

Furnish Tensar Glaspave 50 Hybrid Paving Mat, Huesker HaTelit G 50 Asphalt Reinforcement Grid, or approved equal.

C Construction

After completion of removing concrete pavement partial depth, cleaning and sealing cracks and joints with hot-applied sealant, and placing the leveling layer of HMA pavement install the geotextile pavement interlayer.

Install geotextile interlayer when surface temperature is between 40°F and 140°F.

The pavement surface shall be dry and free of dirt, swept or vacuum cleaned by a mechanical device, as well as free from oil, vegetation and other debris.

Install the geotextile interlayer over tack coat. The geotextile interlayer shall be laid out either by hand or by mechanical means under sufficient tension to eliminate ripples. Should ripples occur, these must be removed by pulling the grid tight or in extreme cases, by cutting and laying it flat. Transverse joints must be lapped in the direction of the paver by 3-6 inches. Overlap longitudinal joints 1-2 inches.

The geotextile layer must be laid and rolled over castings before cutting around the perimeter of the castings.

The surface of the geotextile interlayer shall be rolled with a rubber coated drum roller, or pneumatic tired roller, one or two passes being sufficient to activate the adhesive. Tires must be cleaned regularly with asphalt cleaning agent.

All geotextile interlayer placed in a day shall be covered with HMA pavement the same day.

D Measurement

The department will measure Geotextile Interlayer by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0180.01	Geotextile Interlayer	SY

Payment is full compensation for providing all necessary materials, placement, rolling, and cutting fabric around castings.

The department will pay separately for Tack Coat under the standard bid item.

END OF ADDENDUM