



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

November 18, 2022

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #38: 7520-00-77, WISC 2023120**  
**Merrillan - Neillsville**  
**E FK Halls Creek Bridge B-27-0171**  
**STH 95**  
**Jackson County**

### Letting of December 13, 2022

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
643.3150	Temporary Marking Line Removable Tape 4-Inch	LF	0	4,829	4,829
643.3850	Temporary Marking Stop Line Removable Tape 18-Inch	LF	0	24	24

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
649.0150	Temporary Marking Line Removable Tape 4-Inch	LF	4,829	-4,829	0
649.0850	Temporary Marking Stop Line Removable Tape 18-Inch	LF	24	-24	0

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
13	Miscellaneous Quantities (revised temporary marking bid item numbers)

**Schedule of Items**

Attached, dated November 18, 2022, are the revised Schedule of Items Pages 6 and 7.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 13.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

Addendum No. 01  
ID 7520-00-77  
Revised Sheet 13  
November 18, 2022

TRAFFIC CONTROL

PERMANENT MARKING

STATION	TO	STATION	LOCATION	LF	REMARKS
603.8000	700	700	CONCRETE BARRIER TEMPORARY PRECAST DELIVERED	700	
603.8125	1,400	1,400	CONCRETE BARRIER TEMPORARY PRECAST INSTALLED	1,400	
643.0300	7,065	7,065	TRAFFIC CONTROL DRUMS	7,065	
643.0420	157	157	TRAFFIC CONTROL BARRICADES	157	
643.0715	3,768	3,768	TRAFFIC CONTROL WARNING LIGHTS TYPE C	3,768	
643.0900	14	14	TRAFFIC CONTROL DAY	14	
643.0920	3,939	3,939	TRAFFIC CONTROL COVERING SIGNS TYPE II	3,939	
661.0101.01	1	1	TEMPORARY TRAFFIC SIGNALS FOR BRIDGES (STRUCTURE) (01.B-27-0171) EACH	1	
646.1020	850	850	MARKING LINE EPOXY 4-INCH	850	
TOTAL				1,806	

NOTE: TRAFFIC CONTROL COVERING SIGNS TYPE II INCLUDES 1 CYCLE FOR ALL NECESSARY SIGNS

TEMPORARY MARKING

STAGE	STATION	TO	STATION	LOCATION	LF	REMARKS
1	52+50	-	59+50	STH 95 CENTERLINE	1,400	YELLOW DOUBLE SOLID
1	59+50	-	61+50	STH 95 EB LANE	12	WHITESOLID
1	59+50	-	61+50	STH 95 CENTERLINE	250	YELLOW CENTERLINE
1	60+80	-	65+05	STH 95 EB LANE	425	WHITESOLID
1	60+00	-	65+80	STH 95 CENTER LANE EDGE	582	WHITESOLID
1	60+80	-	65+05	STH 95 EB LANE EDGE	425	WHITESOLID
1	64+50	-	66+30	STH 95 CENTERLINE	225	YELLOW CENTERLINE
1	66+30	-	73+30	STH 95 WB LANE	12	WHITESOLID
1	66+30	-	73+30	STH 95 CENTERLINE	1,400	YELLOW DOUBLE SOLID
2	60+00	-	65+80	STH 95 CENTER LANE EDGE	582	WHITESOLID
2	60+68	-	65+05	STH 95 WB LANE EDGE	440	WHITESOLID
2	60+68	-	61+37	STH 95 WB LANE EDGE	70	WHITESOLID
2	64+50	-	65+05	STH 95 WB LANE EDGE	55	WHITESOLID
TOTAL				4,829	24	

CONSTRUCTION STAKING

STATION	TO	STATION	LOCATION	LF	REMARKS
650.4000	3	3	CONSTRUCTION STAKING SEWER	3	
650.4500	313	313	CONSTRUCTION STAKING SUBGRADE	313	
650.5000	313	313	CONSTRUCTION STAKING BASE	313	
650.5500	24	24	CONSTRUCTION STAKING CURB AND GUTTER	24	
650.6000	240	240	CONSTRUCTION STAKING CONCRETE PAVEMENT	240	
650.6501.01	1	1	CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. STAKING SLOPE (01.B-27-0171) EACH	1	
650.7000	240	240	CONSTRUCTION STAKING CONSTRUCTION STAKES	240	
650.9911.01	1	1	CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) 01. STAKING SLOPE (01.B-27-0171) EACH	1	
650.9920	313	313	CONSTRUCTION STAKING CONSTRUCTION STAKES	313	
TOTAL				3,133	

SAWING CONCRETE & SAWING ASPHALT

STATION	TO	STATION	LOCATION	LF	REMARKS
61+37	-	61+37	LT&RT	8	690.0150 SAWING ASPHALT
64+50	-	62+50	LT&RT	4	690.0150 SAWING ASPHALT
63+33.92	-	64+50	2' RT	113	690.0150 SAWING ASPHALT
63+10	-	64+50	2' RT	140	690.0150 SAWING ASPHALT
TOTAL				12	313

PROJECT NO: 7520-00-77

HWY: STH 95

COUNTY: JACKSON

MISCELLANEOUS QUANTITIES

SHEET: 13

FILE NAME: N:\PDS\...030200\_mq.pptx

PLOT DATE: March 14, 2021

PLOT BY: J.J.

PLOT NAME:

E



Proposal Schedule of Items

Proposal ID: 20221213038 Project(s): 7520-00-77

Federal ID(s): WISC 2023120

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0162	646.9000 Marking Removal Line 4-Inch	1,025.000 LF	_____.	_____.
0168	650.4000 Construction Staking Storm Sewer	3.000 EACH	_____.	_____.
0170	650.4500 Construction Staking Subgrade	313.000 LF	_____.	_____.
0172	650.5000 Construction Staking Base	313.000 LF	_____.	_____.
0174	650.5500 Construction Staking Curb Gutter and Curb & Gutter	24.000 LF	_____.	_____.
0176	650.6501 Construction Staking Structure Layout (structure) 01. B-27-0171	1.000 EACH	_____.	_____.
0178	650.7000 Construction Staking Concrete Pavement	240.000 LF	_____.	_____.
0180	650.9911 Construction Staking Supplemental Control (project) 01. 7520-00-77	1.000 EACH	_____.	_____.
0182	650.9920 Construction Staking Slope Stakes	313.000 LF	_____.	_____.
0184	661.0101 Temporary Traffic Signals for Bridges (structure) 01. B-27-0171	1.000 EACH	_____.	_____.
0186	690.0150 Sawing Asphalt	12.000 LF	_____.	_____.
0188	690.0250 Sawing Concrete	313.000 LF	_____.	_____.
0190	715.0502 Incentive Strength Concrete Structures	1,416.000 DOL	1.00000	1,416.00
0192	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0194	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. 62+81	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20221213038 Project(s): 7520-00-77

Federal ID(s): WISC 2023120

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0196	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	300.000 HRS	5.00000	1,500.00
0198	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	300.000 HRS	5.00000	1,500.00
0200	643.3150 Temporary Marking Line Removable Tape 4-Inch	4,829.000 LF	_____.	_____.
0202	643.3850 Temporary Marking Stop Line Removable Tape 18-Inch	24.000 LF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

