

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
7520-00-77	WISC 2023120	1

# STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

## PLAN OF PROPOSED IMPROVEMENT

# MERRILLAN - NEILLSVILLE

E FK HALLS CREEK BRIDGE B-27-0171

STH 95

JACKSON COUNTY

STATE PROJECT NUMBER  
**7520-00-77**

ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 104



38

DESIGN DESIGNATION


A.A.D.T.	2022	=	2400
A.A.D.T.	2042	=	2800
D.H.V.		=	7.4
D.D.		=	60/40
T.		=	8.8%
DESIGN SPEED		=	50 MPH
ESALS		=	600,000

CONVENTIONAL SYMBOLS

PLAN	PROFILE
CORPORATE LIMITS	GRADE LINE
PROPERTY LINE	ORIGINAL GROUND
LOT LINE	MARSH OR ROCK PROFILE (To be noted as such)
LIMITED HIGHWAY EASEMENT	SPECIAL DITCH
EXISTING RIGHT OF WAY	GRADE ELEVATION
PROPOSED OR NEW R/W LINE	CULVERT (Profile View)
SLOPE INTERCEPT	UTILITIES
REFERENCE LINE	ELECTRIC
EXISTING CULVERT	FIBER OPTIC
PROPOSED CULVERT (Box or Pipe)	GAS
COMBUSTIBLE FLUIDS	SANITARY SEWER
	STORM SEWER
	TELEPHONE
	WATER
MARSH AREA	UTILITY PEDESTAL
	POWER POLE
WOODED OR SHRUB AREA	TELEPHONE POLE

BEGIN PROJECT  
STA 61+37  
Y= 154,212.92  
X= 91,266.76

END PROJECT  
STA 64+50



TOTAL NET LENGTH OF CENTERLINE = 0.056 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), JACKSON COUNTY, NAD83 ( 2011 ), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 ( 2012 ). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12B.

ORIGINAL PLANS PREPARED BY  
**MSA**  
1230 SOUTH BOULEVARD, BARABOO, WI 53913  
(608) 356-2774 www.msa-ps.com



DATE: 7/30/2022 (Signature)


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

PREPARED BY

Surveyor	WISDOT
Designer	MSA PROFESSIONAL SERVICES
Project Manager	JESSICA BOWKER
Regional Examiner	REGIONAL EXAMINER
Regional Supervisor	TYLER RONGSTAD, P.E.

APPROVED FOR THE DEPARTMENT  
DATE: 08/01/2022 Tyler Rongstad (Signature)

E



**DETAIL FOR COMPUTING INLET ELEVATIONS**

\*\* FILL WITH CONCRETE IF BOTTOM OF STRUCTURE IS BELOW LOWEST INVERT. THIS DOES NOT APPLY TO SUMPS

**ORDER OF TYPICAL SECTION & DETAIL SHEETS**

1. GENERAL NOTES
2. TYPICAL SECTIONS
3. STORM SEWER
4. TRAFFIC CONTROL

**DNR LIASON**

WISCONSIN DEPARTMENT OF NATURAL RESOURCES  
 ATTN: LEAH NICOL  
 DNR WEST CENTRAL REGION HEADQUARTERS  
 1300 WEST CLAIREMONT AVENUE  
 EAU CLAIRE, WI 54701  
 715-934-9014  
 LEAH.NICOL@WISCONSIN.GOV

**MSA DESIGN CONTACT**

MSA PROFESSIONAL SERVICES, INC  
 ATTN: JOSH SWENO, P.E.  
 1702 PANKRATZ STREET  
 MADISON, WI 53704  
 608-355-8852  
 JSWENO@MSA-PS.COM

**WISDOT CONTACT**

WISCONSIN DEPARTMENT OF TRANSPORTATION  
 ATTN: JESSICA BOWKER, PROJECT MANAGER  
 718 W CLAIREMONT AVENUE  
 EAU CLAIRE, WI 54701  
 715-577-2963  
 JESSICA.BOWKER@DOT.WI.GOV

**UTILITIES**

OVERHEAD ELECTRICITY: MERRILLAN ELECTRIC & WATER  
 ATTN: KARL MILLER  
 P.O. BOX 70  
 MERRILLAN, WI 54754  
 715-333-7702

BURIED GAS: WE ENERGIES  
 ATTN: TRAVIS KAHL  
 1921 8TH STREET SOUTH  
 WISCONSIN RAPIDS, WI 54494  
 715-421-7256  
 TRAVIS.KAHL@WE-ENERGIES.COM

OVERHEAD COMMUNICATIONS: LUMEN  
 ATTN: TOM MURRAY  
 333 NORTH FRONT STREET  
 LA CROSSE, WI 54601  
 608-615-4169  
 TOM.L.MURRAY@LUMEN.COM

BURIED COMMUNICATIONS: TRI-COUNTY COMMUNICATIONS COOPERATIVE  
 ATTN: BUCK WEBB  
 P.O. BOX 193  
 STRUM, WI 54770  
 715-695-2691  
 BWEBB@TCCPRO.NET

\* NOT A DIGGERS HOTLINE MEMBER

**RUNOFF COEFFICIENT TABLE**

	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
ROW CROPS	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIP-TURF	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPE: TURF			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT	.70 - .95											
CONCRETE	.80 - .95											
BRICK	.70 - .80											
DRIVES, WALKS	.75 - .85											
ROOFS	.75 - .95											
GRAVEL ROADS, SHOULDERS	.40 - .60											

TOTAL PROJECT AREA = 0.57 ACRES  
 TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.46 ACRES



Dial 811 or (800)242-8511

www.DiggersHotline.com


**GENERAL NOTES**

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE AREA THAT ARE NOT SHOWN.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT APPROVAL OF THE ENGINEER.


WETLANDS ARE PRESENT. AREAS OUTSIDE THE SLOPE INTERCEPTS SHALL NOT BE DISTURBED IN WETLAND AREA.

WHEN THE QUANTITY OF BASE AGGREGATE DENSE OR ASPHALTIC SURFACE IS MEASURED BY THE TON, THE THICKNESS SHOWN ON THE PLANS IS APPROXIMATE. THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER IN THE FIELD.




**EXISTING TYPICAL SECTION**

STA 61+37 - STA 62+31  
STA 63+30 - STA 64+50



**EXISTING TYPICAL SECTION**


STA 62+31 - STA 62+51  
STA 63+10 - STA 63+30



**FINISHED TYPICAL SECTION**

STA 61+37 - STA 62+29.75  
STA 63+32.25 - STA 64+50


◇ STA. 63+33.92 - STA. 63+45.92  
8-INCH CONCRETE SHOULDER SHALL BE 3'-8" WIDE  
TO MATCH WITH CURB AND GUTTER  
LONGITUDINAL JOINT.



**FINISHED TYPICAL SECTION**

STA 62+29.75 - STA 62+44.75  
STA 63+17.25 - STA 63+32.25



▲ 8-INCH CONCRETE SHOULDER SHALL EXTEND TO STA. 63+33.92




**FINISHED TYPICAL SECTION FOR ENERGY ABSORBING TERMINAL**

STA 63+77.05 - STA 64+27.05, LT.


\*\* SALVAGED TOPSOIL AND EROSION MAT URBAN CLASS I, TYPE B LIMITS  
\*\*\* SEEDING MIXTURE #20, SEEDING TEMPORARY, & FERTILIZER TYPE B LIMITS





**HWY 95 ROAD WORK BEGINS XXX-XX**  
 G20-57 96"X48"

PLACE TRAFFIC CONTROL SIGNS AT THE BEGINNING AND END OF THE PROJECT 7 DAYS PRIOR TO THE EXPECTED START OF THE PROPOSED WORK THAT WILL REQUIRE BRIDGE CLOSURE, ADJUST THE DATE ACCORDINGLY.



STAGE 1 TYPICAL SECTION

SEE S.D.D. "TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS" FOR ADDITIONAL INFORMATION AND ADVANCED SIGNING REQUIREMENTS.

SEE S.D.D. "BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION" FOR EXACT PLACEMENT OF TEMPORARY TRAFFIC SIGNALS.

SEE S.D.D. "ADVANCED WIDTH RESTRICTION SIGNING" FOR ADVANCED WIDTH SIGNING REQUIREMENTS.



TEMPORARY SIGNAL TIMINGS (SEC.) - STAGE 1  
 B-27-0171 WORK ZONE SEQUENCE: ALL DAY  
 TOTAL CYCLE TIME = 86

PHASE 1 STH 95 EB	PHASE 2 STH 95 WB	PROGRAM TYPE
15	15	MINIMUM GREEN TIME
5	5	MAXIMUM PASSAGE TIME DURING GREEN PHASE
3.5	3.5	MINIMUM PASSAGE TIME DURING GREEN PHASE
15	15	START OF REDUCTION OF PASSAGE FROM MAX. TO MIN. DURING GREEN PHASE
6	6	TIME TO REDUCE PASSAGE FROM MAX. TO MIN. DURING GREEN PHASE
17	15	MAXIMUM GREEN TIME
5	5	YELLOW
22	22	ALL-RED
NONE	NONE	RECALL MODE

NOTES:  
 REVIEW SIGNALS AFTER PROGRAMMING TO ASSURE THEY ARE NOT CONFLICTING MOVEMENTS.

THE TIMINGS ARE BASED ON A 25 MPH POSTED SPEED. NOTIFY THE DEPARTMENT WITH TIMING ADJUSTMENTS IF SLOWER THAN AVERAGE SPEEDS ARE OBSERVED WITHIN THE SINGLE LANE WORK ZONE.

- LEGEND**
- TRAFFIC CONTROL SIGN ON PERMANENT SUPPORT
  - TRAFFIC CONTROL SIGN ON TEMPORARY SUPPORT
  - TYPE III BARRICADE
  - TYPE III BARRICADE WITH ATTACHED SIGN
  - TRAFFIC CONTROL DRUM
  - TRAFFIC CONTROL DRUM WITH TYPE C STEADY-BURN LIGHT
  - CONCRETE BARRIER TEMPORARY PRECAST
  - WORK AREA
  - MARKING REMOVAL LINE 4-INCH
  - DIRECTION OF TRAFFIC
  - TRAILER MOUNTED TRAFFIC SIGNAL



SEE S.D.D. "TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS" FOR ADDITIONAL INFORMATION AND ADVANCED SIGNING REQUIREMENTS.

SEE S.D.D. "BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION" FOR EXACT PLACEMENT OF TEMPORARY TRAFFIC SIGNALS.

SEE S.D.D. "ADVANCED WIDTH RESTRICTION SIGNING" FOR ADVANCED WIDTH SIGNING REQUIREMENTS.

TEMPORARY SIGNAL TIMINGS (SEC.) - STAGE 2			
B-27-0171 WORK ZONE SEQUENCE: ALL DAY			
TOTAL CYCLE TIME 86			
PROGRAM TYPE			
PHASE 1 STH 95 EB	PHASE 2 STH 95 WB		
15	15	MINIMUM GREEN TIME	
5	5	MAXIMUM PASSAGE TIME DURING GREEN PHASE	
3.5	3.5	MINIMUM PASSAGE TIME DURING GREEN PHASE	
1.5	1.5	START OF REDUCTION OF PASSAGE FROM MAX. TO MIN. DURING GREEN PHASE	
6	6	TIME TO REDUCE PASSAGE FROM MAX. TO MIN. DURING GREEN PHASE	
1.7	1.5	MAXIMUM GREEN TIME	
5	5	YELLOW	
22	22	ALL-RED	
NONE	NONE	RECALL MODE	

NOTES:  
 REVIEW SIGNALS AFTER PROGRAMMING TO ASSURE THEY ARE NOT CONFLICTING MOVEMENTS.  
 THE TIMINGS ARE BASED ON A 25 MPH POSTED SPEED. NOTIFY THE DEPARTMENT WITH TIMING ADJUSTMENTS IF SLOWER THAN AVERAGE SPEEDS ARE OBSERVED WITHIN THE SINGLE LANE WORK ZONE.

- LEGEND**
- TRAFFIC CONTROL SIGN ON PERMANENT SUPPORT
  - TRAFFIC CONTROL SIGN ON TEMPORARY SUPPORT
  - TYPE III BARRICADE
  - TYPE III BARRICADE WITH ATTACHED SIGN
  - TRAFFIC CONTROL DRUM
  - TRAFFIC CONTROL DRUM WITH TYPE C STEADY-BURN LIGHT
  - CONCRETE BARRIER TEMPORARY PRECAST
  - WORK AREA
  - MARKING REMOVAL LINE 4-INCH
  - DIRECTION OF TRAFFIC
  - TRAILER MOUNTED TRAFFIC SIGNAL

Estimate Of Quantities

7520-00-77

Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	3.000	3.000
0004	201.0205	Grubbing	STA	3.000	3.000
0006	203.0211.S	Abatement of Asbestos Containing Material (structure) 01. B-27-0171	EACH	1.000	1.000
0008	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 01. B-27-147	EACH	1.000	1.000
0010	204.0100	Removing Concrete Pavement	SY	715.000	715.000
0012	204.0165	Removing Guardrail	LF	502.000	502.000
0014	205.0100	Excavation Common	CY	203.000	203.000
0016	206.1001	Excavation for Structures Bridges (structure) 01. B-27-171	EACH	1.000	1.000
0018	208.0100	Borrow	CY	175.000	175.000
0020	210.1500	Backfill Structure Type A	TON	518.000	518.000
0022	213.0100	Finishing Roadway (project) 01. 7520-00-77	EACH	1.000	1.000
0024	305.0110	Base Aggregate Dense 3/4-Inch	TON	43.000	43.000
0026	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	493.000	493.000
0028	415.0080	Concrete Pavement 8-Inch	SY	725.000	725.000
0030	415.0410	Concrete Pavement Approach Slab	SY	100.000	100.000
0032	416.0620	Drilled Dowel Bars	EACH	58.000	58.000
0034	455.0605	Tack Coat	GAL	10.000	10.000
0036	465.0105	Asphaltic Surface	TON	33.000	33.000
0038	465.0110	Asphaltic Surface Patching	TON	5.000	5.000
0040	465.0125	Asphaltic Surface Temporary	TON	8.000	8.000
0042	502.0100	Concrete Masonry Bridges	CY	236.000	236.000
0044	502.3200	Protective Surface Treatment	SY	304.000	304.000
0046	502.3210	Pigmented Surface Sealer	SY	108.000	108.000
0048	503.0136	Prestressed Girder Type I 36-Inch	LF	426.000	426.000
0050	505.0400	Bar Steel Reinforcement HS Structures	LB	5,300.000	5,300.000
0052	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	29,310.000	29,310.000
0054	505.0904	Bar Couplers No. 4	EACH	8.000	8.000
0056	505.0906	Bar Couplers No. 6	EACH	56.000	56.000
0058	506.2605	Bearing Pads Elastomeric Non-Laminated	EACH	12.000	12.000
0060	506.4000	Steel Diaphragms (structure) 01. B-27-171	EACH	5.000	5.000
0062	511.1200	Temporary Shoring (structure) 01. B-27-171	SF	442.000	442.000
0064	516.0500	Rubberized Membrane Waterproofing	SY	26.000	26.000
0066	522.0112	Culvert Pipe Reinforced Concrete Class III 12-Inch	LF	46.000	46.000
0068	522.1012	Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	EACH	1.000	1.000
0070	550.0020	Pre-Boring Rock or Consolidated Materials	LF	246.000	246.000
0072	550.1100	Piling Steel HP 10-Inch X 42 Lb	LF	320.000	320.000
0074	601.0590	Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBTT	LF	24.000	24.000
0076	603.8000	Concrete Barrier Temporary Precast Delivered	LF	700.000	700.000
0078	603.8125	Concrete Barrier Temporary Precast Installed	LF	1,400.000	1,400.000
0080	606.0300	Riprap Heavy	CY	256.000	256.000
0082	611.0654	Inlet Covers Type V	EACH	2.000	2.000
0084	611.3220	Inlets 2x2-FT	EACH	2.000	2.000
0086	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	150.000	150.000
0088	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0090	614.0200	Steel Thrie Beam Structure Approach	LF	82.600	82.600
0092	614.0305	Steel Plate Beam Guard Class A	LF	275.000	275.000
0094	614.0370	Steel Plate Beam Guard Energy Absorbing Terminal	EACH	1.000	1.000
0096	614.0400	Adjusting Steel Plate Beam Guard	LF	30.000	30.000
0098	614.0905	Crash Cushions Temporary	EACH	2.000	2.000



Estimate Of Quantities

7520-00-77

Line	Item	Item Description	Unit	Total	Qty
0100	614.0950	Replacing Guardrail Posts and Blocks	EACH	3.000	3.000
0102	618.0100	Maintenance And Repair of Haul Roads (project) 01. 7520-00-77	EACH	1.000	1.000
0104	619.1000	Mobilization	EACH	1.000	1.000
0106	624.0100	Water	MGAL	10.700	10.700
0108	625.0500	Salvaged Topsoil	SY	765.000	765.000
0110	628.1504	Silt Fence	LF	670.000	670.000
0112	628.1520	Silt Fence Maintenance	LF	670.000	670.000
0114	628.1905	Mobilizations Erosion Control	EACH	2.000	2.000
0116	628.1910	Mobilizations Emergency Erosion Control	EACH	2.000	2.000
0118	628.2008	Erosion Mat Urban Class I Type B	SY	765.000	765.000
0120	628.6005	Turbidity Barriers	SY	150.000	150.000
0122	629.0210	Fertilizer Type B	CWT	0.550	0.550
0124	630.0120	Seeding Mixture No. 20	LB	25.000	25.000
0126	630.0200	Seeding Temporary	LB	25.000	25.000
0128	630.0500	Seed Water	MGAL	20.000	20.000
0130	634.0612	Posts Wood 4x6-Inch X 12-FT	EACH	4.000	4.000
0132	637.2230	Signs Type II Reflective F	SF	12.000	12.000
0134	638.2102	Moving Signs Type II	EACH	2.000	2.000
0136	638.2602	Removing Signs Type II	EACH	4.000	4.000
0138	638.3000	Removing Small Sign Supports	EACH	4.000	4.000
0140	638.4000	Moving Small Sign Supports	EACH	2.000	2.000
0142	642.5001	Field Office Type B	EACH	1.000	1.000
0144	643.0300	Traffic Control Drums	DAY	7,065.000	7,065.000
0146	643.0420	Traffic Control Barricades Type III	DAY	157.000	157.000
0148	643.0715	Traffic Control Warning Lights Type C	DAY	3,768.000	3,768.000
0150	643.0900	Traffic Control Signs	DAY	3,939.000	3,939.000
0152	643.0920	Traffic Control Covering Signs Type II	EACH	3.000	3.000
0154	643.5000	Traffic Control	EACH	1.000	1.000
0156	645.0111	Geotextile Type DF Schedule A	SY	74.000	74.000
0158	645.0120	Geotextile Type HR	SY	426.000	426.000
0160	646.1020	Marking Line Epoxy 4-Inch	LF	1,806.000	1,806.000
0162	646.9000	Marking Removal Line 4-Inch	LF	1,025.000	1,025.000
0164	649.0150	Temporary Marking Line Removable Tape 4-Inch	LF	4,829.000	4,829.000
0166	649.0850	Temporary Marking Stop Line Removable Tape 18-Inch	LF	24.000	24.000
0168	650.4000	Construction Staking Storm Sewer	EACH	3.000	3.000
0170	650.4500	Construction Staking Subgrade	LF	313.000	313.000
0172	650.5000	Construction Staking Base	LF	313.000	313.000
0174	650.5500	Construction Staking Curb Gutter and Curb & Gutter	LF	24.000	24.000
0176	650.6501	Construction Staking Structure Layout (structure) 01. B-27-0171	EACH	1.000	1.000
0178	650.7000	Construction Staking Concrete Pavement	LF	240.000	240.000
0180	650.9911	Construction Staking Supplemental Control (project) 01. 7520-00-77	EACH	1.000	1.000
0182	650.9920	Construction Staking Slope Stakes	LF	313.000	313.000
0184	661.0101	Temporary Traffic Signals for Bridges (structure) 01. B-27-0171	EACH	1.000	1.000
0186	690.0150	Sawing Asphalt	LF	12.000	12.000
0188	690.0250	Sawing Concrete	LF	313.000	313.000
0190	715.0502	Incentive Strength Concrete Structures	DOL	1,416.000	1,416.000
0192	715.0720	Incentive Compressive Strength Concrete Pavement	DOL	500.000	500.000
0194	999.2000.S	Installing and Maintaining Bird Deterrent System (station) 01. 62+81	EACH	1.000	1.000
0196	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	300.000	300.000

Estimate Of Quantities

---

0198	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	300.000	7520-00-77	300.000
------	----------	---	-----	---------	------------	---------

3

CLEARING AND GRUBBING

STATION	TO	STATION	LOCATION	201.0105 CLEARING STA	201.0205 GRUBBING STA
61+50	-	64+50	LT & RT	3	3
TOTAL				3	3

NOTE: SAVE TREE AT STATION 63+85, 48' LT

REMOVING CONCRETE PAVEMENT

STATION	TO	STATION	204.0100 REMOVING CONCRETE PAVEMENT SY
61+37	-	62+32	317
63+30	-	64+50	398
TOTAL			715

REMOVING GUARDRAIL

STATION	TO	STATION	LOCATION	204.0165 REMOVING GUARDRAIL LF
61+35	-	62+54	LT	119
61+35	-	62+54	RT	119
63+09	-	64+30	LT	122
63+08	-	64+50	RT	142
TOTAL				502

EXCAVATION COMMON

STATION	TO	STATION	205.0100 EXCAVATION COMMON CY	208.0100 BORROW CY
61+37	-	64+50	203	175
TOTAL			203	175

BASE AGGREGATE DENSE

STATION	TO	STATION	305.0110 BASE AGGREGATE DENSE 3/4-INCH TON	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH TON	624.0100 WATER MGAL
61+37	-	64+50	43	493	10.7
TOTAL			43	493	10.7

CONCRETE PAVEMENT

STATION	TO	STATION	415.0080 CONCRETE PAVEMENT 8-INCH SY	415.0410 CONCRETE PAVEMENT APPROACH SLAB SY	416.0620 DRILLED DOWEL BARS EACH
61+37	-	62+29.75	310	-	29
62+29.75	-	62+44.75	10	50	-
63+17.25	-	63+32.25	10	50	-
63+32.25	-	64+50	395	-	29
TOTAL			725	100	58

ASPHALTIC SURFACE

STATION	TO	STATION	455.0605 TACK COAT GAL	465.0105 ASPHALTIC SURFACE TON	465.0110 ASPHALTIC SURFACE PATCHING TON	465.0125 ASPHALTIC SURFACE TEMPORARY TON
61+37	-	62+29.75	5	16	3	---
63+32.25	-	64+50	5	17	2	---
64+27	-	65+05	---	---	---	8
TOTAL			10	33	5	8

CURB AND GUTTER

STATION	TO	STATION	LOCATION	601.0590 CONCRETE CURB & GUTTER 4-INCH SLOPED 36-INCH TYPE TBTT LF
63+33.92	-	63+45.92	RT	12
63+33.92	-	63+45.92	LT	12
TOTAL				24

STORM SEWER

STRUCTURE NO.	STATION	LOCATION	GRATE ELEV.	TOP OF STRUCTURE ELEV.	INVERT ELEV.	STRUCTURE DEPTH	522.0112 CULVERT PIPE REINFORCED CONCRETE CLASS III 12-INCH LF	522.1012 APRON ENDWALLS FOR CULVERT PIPE REINFORCED CONCRETE 12- INCH EACH	611.0654 INLET COVERS TYPE V EACH	611.3220 INLETS 2X2-FT EACH
1.2	63+36.92	29.15' RT	-	-	897.68	-	-	1	-	-
1.1	63+36.92	17.06' RT	903.32	902.32	898.00	4.32	12	-	1	1
1.0	63+36.92	17.07' LT	903.32	902.32	900.02	2.30	34	-	1	1
TOTAL							46	1	2	2

3

BEAM GUARD

STATION	TO	STATION	LOCATION	614.0200 STEEL THRIE BEAM STRUCTURE APPROACH LF	614.0305 STEEL PLATE BEAM GUARD CLASS A LF	614.0370 STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL EACH	614.0400 ADJUSTING STEEL PLATE BEAM GUARD LF	614.0950 REPLACING GUARDRAIL POSTS AND BLOCKS EACH
61+35	-	62+30	LT	20.65	75	-	10	1
61+35	-	62+30	RT	20.65	75	-	10	1
63+32	-	64+27	LT	20.65	25	1	-	-
63+32	-	64+50	RT	20.65	100	-	10	1
TOTAL				82.6	275	1	30	3

CRASH CUSHIONS TEMPORARY

CATEGORY	LOCATION	614.0905 CRASH CUSHIONS TEMPORARY EACH	BACK WIDTH FT	OBJECT MARKING PATTERN	CRASH TEST LEVEL	TRAFFIC DIRECTION	TRAFFIC LOCATION	CRASH CUSHION SHIELDS
0010	61+15, 5' RT	1	2	OM-3L (W05-58L)	TL-3	BIDIRECTIONAL	RT	TEMPORARY CONCRETE BARRIER
0010	65+16, 7.5' LT	1	2	OM-3R (W05-58R)	TL-3	BIDIRECTIONAL	RT	TEMPORARY CONCRETE BARRIER
0010	60+17, 15' RT	1	2	OM-3R (W05-58R)	TL-3	BIDIRECTIONAL	LT	TEMPORARY CONCRETE BARRIER
0010	64+68, 4.5' LT	1	2	OM-3L (W05-58L)	TL-3	BIDIRECTIONAL	LT	TEMPORARY CONCRETE BARRIER
TOTAL 0010		4						

FINISHING ITEMS

STATION	TO	STATION	625.0500 SALVAGED TOPSOIL SY	628.2008 EROSION MAT URBAN CLASS I TYPE B SY	629.0210 FERTILIZER TYPE B CWT	630.0120 SEEDING MIXTURE NO. 20 LB	630.0200 SEEDING TEMPORARY LB	630.0500 SEED WATER MGAL
61+37	-	62+28	315	315	0.23	10	10	8
63+33	-	64+50	297	297	0.22	10	10	8
UNDISTRIBUTED			153	153	0.10	5	5	4
TOTAL			765	765	0.55	25	25	20

SILT FENCE

STATION	TO	STATION	628.1504 SILT FENCE LF	628.1520 SILT FENCE MAINTENANCE LF	628.6005 TURBIDITY BARRIERS SY
61+37	-	62+60	255	255	65
62+06	-	64+50	280	280	65
UNDISTRIBUTED			135	135	20
TOTAL			670	670	150

MOBILIZATION EROSION CONTROL

STATION	TO	STATION	628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL EACH
61+37	-	64+50	2	2
TOTAL			2	2

PERMANENT SIGNING

STATION	LOCATION	DESCRIPTION	634.0612 POSTS WOOD 4X6- INCH X 12-FT EACH	637.2230 SIGNS TYPE II REFLECTIVE F SF	638.2102 MOVING SIGNS TYPE II EACH	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORTS EACH	638.4000 MOVING SMALL SIGN SUPPORTS EACH
62+22	22' LT	W14-3	-	-	1	-	-	1
62+27	20' LT	W5-52L	1	3	-	-	-	-
62+27	20' RT	W5-52R	1	3	-	-	-	-
62+47	19' LT	-	-	-	-	1	1	-
62+47	20' RT	-	-	-	-	1	1	-
63+15	18' LT	-	-	-	-	1	1	-
63+14	19' RT	-	-	-	-	1	1	-
63+35	19' LT	W5-52L	1	3	-	-	-	-
63+35	19' RT	W5-52R	1	3	-	-	-	-
63+82	23' RT	W14-3	-	-	1	-	-	1
TOTAL			4	12	2	4	4	2

3

3

TRAFFIC CONTROL

PERMANANT MARKING

CALENDAR DAYS	603.8000 CONCRETE BARRIER TEMPORARY PRECAST DELIVERED LF	603.8125 CONCRETE BARRIER TEMPORARY PRECAST INSTALLED LF	643.0300 TRAFFIC CONTROL DRUMS DAY	643.0420 TRAFFIC CONTROL BARRICADES TYPE III DAY	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C DAY	643.0900 TRAFFIC CONTROL SIGNS DAY	643.0920 TRAFFIC CONTROL COVERING SIGNS TYPE II EACH	661.0101.01 TEMPORARY TRAFFIC SIGNALS FOR BRIDGES (STRUCTURE) (01. B-27-0171) EACH
7	---	---	---	---	---	14	---	---
157	700	1,400	7,065	157	3,768	3,925	3	1
TOTAL	700	1,400	7,065	157	3,768	3,939	3	1

STATION	TO	STATION	LOCATION	646.1020 MARKING LINE EPOXY 4-INCH LF	REMARKS
61+37	-	62+43	STH 95 EB CENTERLINE	75	DASHED YELLOW
59+50	-	62+43	STH 95 WB CENTERLINE	293	SOLID YELLOW
62+43	-	63+82	STH 95 CENTERLINE	278	DOUBLE YELLOW
63+82	-	66+30	STH 95 EB CENTERLINE	248	SOLID YELLOW
63+82	-	66+30	STH 95 WB CENTERLINE	62	DASHED YELLOW
60+80	-	65+05	STH 95 EDGELINES	850	SOLID WHITE
TOTAL				1,806	

NOTE: TRAFFIC CONTROL COVERING SIGNS TYPE II INCLUDES 1 CYCLE FOR ALL NECESSARY SIGNS

TEMPORARY MARKING

STAGE	STATION	TO	STATION	LOCATION	646.9000 MARKING REMOVAL LINE 4-INCH LF	649.0150 TEMPORARY MARKING LINE REMOVABLE TAPE 4-INCH LF	649.0850 TEMPORARY MARKING STOP LINE REMOVABLE TAPE 18-INCH LF	REMARKS
1	52+50	-	59+50	STH 95 CENTERLINE	-	1,400	-	YELLOW DOUBLE SOLID
1	59+50	-	59+50	STH 95 EB LANE	-	-	12	WHITE SOLID
1	59+50	-	61+50	STH 95 CENTERLINE	250	-	-	YELLOW CENTERLINE
1	60+80	-	65+05	STH 95 EB LANE	425	-	-	WHITE SOLID
1	60+00	-	65+80	STH 95 CENTER LANE EDGE	-	582	-	WHITE SOLID
1	60+80	-	65+05	STH 95 EB LANE EDGE	-	425	-	WHITE SOLID
1	64+50	-	66+30	STH 95 CENTERLINE	225	-	-	YELLOW CENTERLINE
1	66+30	-	66+30	STH 95 WB LANE	-	-	12	WHITE SOLID
1	66+30	-	73+30	STH 95 CENTERLINE	-	1,400	-	YELLOW DOUBLE SOLID
2	60+00	-	65+80	STH 95 CENTER LANE EDGE	-	582	-	WHITE SOLID
2	60+68	-	65+05	STH 95 WB LANE EDGE	-	440	-	WHITE SOLID
2	60+68	-	61+37	STH 95 WB LANE EDGE	70	-	-	WHITE SOLID
2	64+50	-	65+05	STH 95 WB LANE EDGE	55	-	-	WHITE SOLID
TOTAL					1,025	4,829	24	

CONSTRUCTION STAKING

SAWING CONCRETE & SAWING ASPHALT

STATION	TO	STATION	650.4000 CONSTRUCTION STAKING STORM SEWER EACH	650.4500 CONSTRUCTION STAKING SUBGRADE LF	650.5000 CONSTRUCTION STAKING BASE LF	650.5500 CONSTRUCTION STAKING CURB & GUTTER LF	650.6501.01 CONSTRUCTION STAKING STRUCTURE LAYOUT (STRUCTURE) (01. B-27-0171) EACH	650.7000 CONSTRUCTION STAKING CONCRETE PAVEMENT LF	650.9911.01 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (PROJECT) (01. 7520-00-77) EACH	650.9920 CONSTRUCTION STAKING SLOPE STAKES LF
61+37	-	64+50	-	313	313	-	-	240	-	313
63+36.92	-	63+36.92	3	-	-	-	-	-	-	-
63+33.92	-	63+45.92	-	-	-	24	-	-	-	-
TOTAL			3	313	313	24	1	240	1	313

STATION	TO	STATION	LOCATION	690.0150 SAWING ASPHALT LF	690.0250 SAWING CONCRETE LF
61+37	-	64+50	LT & RT	8	30
64+50	-	64+50	LT & RT	4	30
61+37	-	62+50	2' RT	-	113
63+10	-	64+50	2' RT	-	140
TOTAL				12	313

# TRANSPORTATION PROJECT PLAT NO: 7520-00-27 - 4.01

THAT PART OF OUTLOT 97 OF MERRILLAN ASSESSORS PLAT OF OUTLOTS 1919, IN THE SOUTHEAST 1/4 OF THE SOUTHWEST 1/4, IN SECTION 23, TOWN 23 NORTH, RANGE 4 WEST, IN THE VILLAGE OF MERRILLAN, JACKSON COUNTY, WISCONSIN.

RELOCATION ORDER: STH 95 MERRILLAN - NEILLSVILLE (E FORK HALLS CREEK, BRIDGE B-27-0147), JACKSON COUNTY

TO PROPERLY ESTABLISH, LAY OUT, WIDEN, ENLARGE, EXTEND, CONSTRUCT, RECONSTRUCT, IMPROVE, OR MAINTAIN A PORTION OF THE HIGHWAY DESIGNATED ABOVE, THE STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION DEEMS IT NECESSARY TO RELOCATE OR CHANGE SAID HIGHWAY AND ACQUIRE CERTAIN LANDS AND INTERESTS OR RIGHTS IN LANDS FOR THE ABOVE PROJECT.

TO EFFECT THIS CHANGE, PURSUANT TO AUTHORITY GRANTED UNDER SECTION 84.02 (3), 84.09, AND 84.30, WISCONSIN STATUTES, THE DEPARTMENT OF TRANSPORTATION

- THAT PORTION OF SAID HIGHWAY AS SHOWN ON THIS PLAT IS LAID OUT AND ESTABLISHED TO THE LINES AND WIDTHS AS SO SHOWN FOR THE ABOVE PROJECT.
- THE LANDS OR INTERESTS OR RIGHTS IN LANDS AS SHOWN ON THIS PLAT ARE REQUIRED BY THE DEPARTMENT FOR THE ABOVE PROJECT AND SHALL BE ACQUIRED IN THE NAME OF THE STATE OF WISCONSIN, PURSUANT TO THE PROVISIONS OF SECTION 84.09 (1) OR (2), WISCONSIN STATUTES.

### NOTES:

PROPERTY LINES SHOWN ON THIS PLAT ARE DRAWN FROM DATA DERIVED FROM MAPS AND DOCUMENTS OF PUBLIC RECORD AND/OR EXISTING OCCUPATIONAL LINES. THIS PLAT MAY NOT BE A TRUE REPRESENTATION OF EXISTING PROPERTY LINES, EXCLUDING RIGHT-OF-WAY, AND SHOULD NOT BE USED AS A SUBSTITUTE FOR AN ACCURATE FIELD SURVEY.

POSITIONS SHOWN ON THIS PLAT ARE WISCONSIN COORDINATE REFERENCE SYSTEM COORDINATES (WISCRS), JACKSON COUNTY, NAD83 (2011) IN US SURVEY FEET. VALUES SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES.

A TEMPORARY LIMITED EASEMENT (TLE) IS A RIGHT FOR CONSTRUCTION PURPOSES, AS DEFINED HEREIN, INCLUDING THE RIGHT TO OPERATE NECESSARY EQUIPMENT THEREON, THE RIGHT OF INGRESS AND EGRESS, AS LONG AS REQUIRED FOR SUCH PUBLIC PURPOSE, INCLUDING THE RIGHT TO PRESERVE, PROTECT, REMOVE, OR PLANT THEREON ANY VEGETATION THAT THE HIGHWAY AUTHORITIES MAY DEEM DESIRABLE. ALL (TLEs) ON THIS PLAT EXPIRE AT THE COMPLETION OF THE CONSTRUCTION PROJECT FOR WHICH THIS INSTRUMENT IS GIVEN.

ALL NEW RIGHT-OF-WAY MONUMENTS WILL BE TYPE 2 (TYPICALLY 3/4"x24" IRON REBARS) UNLESS OTHERWISE NOTED, AND WILL BE PLACED PRIOR TO THE COMPLETION OF THE PROJECT.

RIGHT-OF-WAY BOUNDARIES ARE DEFINED WITH COURSES OF THE PERIMETER OF THE HIGHWAY LANDS REFERENCED TO THE U.S. PUBLIC LAND SURVEY SYSTEM OR OTHER "SURVEYS" OF PUBLIC RECORD.

EXISTING RIGHT OF WAY FOR STH 95 ESTABLISHED FROM PLAT OF RIGHT OF WAY REQUIRED STATE PROJECT NO. 5423, MERRILLAN ASSESSORS PLAT OF OUTLOTS 1919, AND CSM 840 (DOC 246742).

EXISTING HIGHWAY EASEMENT FOR OUTLOT 97 OF MERRILLAN ASSESSORS PLAT OF OUTLOTS 1919, ESTABLISHED FROM DOC. 119263, VOL. 109, PG. 319.


FOR THE CURRENT ACCESS/DRIVEWAY INFORMATION, CONTACT THE PLANNING UNIT OF THE WISCONSIN DEPARTMENT OF TRANSPORTATION OFFICE IN EAU CLAIRE, WISCONSIN.

DIMENSIONING FOR THE NEW RIGHT-OF-WAY IS MEASURED ALONG AND PERPENDICULAR TO THE NEW REFERENCE LINES.

ALL RIGHT-OF-WAY LINES DEPICTED IN THE NON-ACQUISITION AREAS ARE INTENDED TO RE-ESTABLISH EXISTING RIGHT-OF-WAY LINES AS DETERMINED FROM PREVIOUS PROJECTS, OTHER RECORDED DOCUMENTS, OR FROM CENTERLINE OF EXISTING PAVEMENTS.

PARCEL AND UTILITY IDENTIFICATION NUMBERS MAY NOT POINT TO ALL AREAS OF ACQUISITION.

COURSE	BEARING	DISTANCE
100 - 101	S89° 32' 44"E	313.00'
102 - 103	N89° 32' 44"W	313.00'



UTILITY NUMBER	UTILITY OWNERS	INTEREST REQUIRED
50	TRI-COUNTY COMMUNICATIONS COOPERATIVE	RELEASE OF RIGHTS
51	WE ENERGIES	RELEASE OF RIGHTS

PARCEL NUMBER	OWNERS	INTEREST REQUIRED	TLE ACRES
1	TODD J YAHNKE	TLE	0.05 AC

OWNER'S NAMES ARE SHOWN FOR REFERENCE PURPOSES ONLY AND ARE SUBJECT TO CHANGE PRIOR TO THE TRANSFER OF LAND INTERESTS TO THE DEPARTMENT.

WATER	—W—
GAS	—G—
TELEPHONE	—T—
OVERHEAD TRANSMISSION LINES	—OH—
ELECTRIC	—E—
CABLE TELEVISION	—TV—
FIBER OPTIC	—FO—
SANITARY SEWER	—SAN—
STORM SEWER	—SS—
ELECTRIC TOWER	⊠

### CONVENTIONAL SYMBOLS

SECTION LINE	---	SECTION CORNER SYMBOL	⊕	R/W MONUMENT (TO BE SET)	●
QUARTER LINE	---	SECTION CORNER MONUMENT	⊕	NON-MONUMENTED R/W POINT	○
SIXTEENTH LINE	---	GEODETIC SURVEY MONUMENT	⊕	FOUND IRON PIN (1-INCH UNLESS NOTED)	⊙
NEW REFERENCE LINE	---	SIXTEENTH CORNER MONUMENT	⊕	OFF-PREMISE SIGN	⊕
NEW R/W LINE	---	SIGN	⊕	COMPENSABLE	⊕
EXISTING R/W OR HE LINE	---	PARCEL NUMBER (25)	⊕	NON-COMPENSABLE	⊕
PROPERTY LINE	---	UTILITY NUMBER (40)	⊕	ELECTRIC POLE	⊕
LOT, TIE & OTHER MINOR LINES	---	PARALLEL OFFSETS	⊕	TELEPHONE POLE	⊕
SLOPE INTERCEPT	---	BRIDGE	⊕	PEDESTAL (LABEL TYPE) (TV, TEL, ELEC, ETC.)	⊕
CORPORATE LIMITS	---	CULVERT	⊕	ACCESS RESTRICTED BY ACQUISITION	⊕
UNDERGROUND FACILITY (COMMUNICATIONS, ELECTRIC, ETC)	---	TO BE REMOVED	⊕	NO ACCESS (BY STATUTORY AUTHORITY)	⊕
NEW R/W (FEE OR HE) (HATCHING VARIES BY OWNER)	---	BRIDGE	⊕	ACCESS RESTRICTED (BY PREVIOUS PROJECT OR CONTROL)	⊕
TEMPORARY LIMITED EASEMENT AREA	---	CULVERT	⊕	NO ACCESS (NEW HIGHWAY)	⊕
EASEMENT AREA (PERMANENT LIMITED OR RESTRICTED DEVELOPMENT)	---	BRIDGE	⊕	PARCEL NUMBER (25)	⊕
TRANSMISSION STRUCTURES	---	CULVERT	⊕	UTILITY NUMBER (40)	⊕


### CONVENTIONAL ABBREVIATIONS

ACCESS RIGHTS	AR	POINT OF COMPOUND CURVE	PCC
ACRES	AC	POINT OF INTERSECTION	PI
AHEAD	AH	PROPERTY LINE	PL
ALUMINUM	ALUM	RECORDED AS	(100')
AND OTHERS	ET AL	REEL / IMAGE	R/I
BACK	BK	REFERENCE LINE	R/L
BLOCK	BLK	REMAINING	REM
CENTERLINE	C/L	RESTRICTIVE DEVELOPMENT EASEMENT	RDE
CERTIFIED SURVEY MAP	CSM	RIGHT	RT
CONCRETE	CONC	RIGHT OF WAY	R/W
COUNTY	CO	SECTION	SEC
COUNTY TRUNK HIGHWAY	CTH	SECTION	SEPV
DISTANCE	DIST	SEPTIC VENT	SF
CORNER	COR	SQUARE FEET	STH
DOCUMENT NUMBER	DOC	STATE TRUNK HIGHWAY	STA
EASEMENT	EASE	STATION	TP
EXISTING	EX	TELEPHONE PEDESTAL	TLE
GAS VALVE	GV	TEMPORARY LIMITED EASEMENT	TPP
GRID NORTH	GN	TRANSPORTATION PROJECT PLAT	USH
HIGHWAY EASEMENT IDENTIFICATION	HE	UNITED STATES HIGHWAY	V
LAND CONTRACT	ID	VOLUME	
LEFT MONUMENT	LC		
NATIONAL GEODETIC SURVEY NUMBER	LT		
OUTLOT	MON		
PAGE	NGS		
POINT OF TANGENCY	NO		
PERMANENT LIMITED EASEMENT	OL		
POINT OF BEGINNING	P		
POINT OF CURVATURE	PT		
	PLE		
	POB		
	PC		

### CURVE DATA ABBREVIATIONS

LONG CHORD	LCH
LONG CHORD BEARING	LCB
RADIUS	R
DEGREE OF CURVE	D
CENTRAL ANGLE	Δ / DELTA
LENGTH OF CURVE	L
TANGENT	T
DIRECTION AHEAD	DA
DIRECTION BACK	DB

RESERVED FOR REGISTER OF DEEDS  
 PROJECT NUMBER 7520-00-27 - 4.01



SCALE, FEET 0 25 50



**MSA** ENGINEERING | ARCHITECTURE | SURVEYING  
 FUNDING | PLANNING | ENVIRONMENTAL  
 1230 SOUTH BOULEVARD, BARABOO, WI 53913  
 (608) 356-2771 www.msa-ps.com  
 © MSA Professional Services, Inc.

I, ERIC SCHOOT PROFESSIONAL LAND SURVEYOR, HEREBY CERTIFY THAT IN FULL COMPLIANCE WITH THE PROVISIONS OF SECTION 84.095 OF THE WISCONSIN STATUTES AND UNDER THE DIRECTION OF THE DEPARTMENT OF TRANSPORTATION I HAVE SURVEYED AND MAPPED THIS TRANSPORTATION PROJECT PLAT AND SUCH PLAT CORRECTLY REPRESENTS ALL EXTERIOR BOUNDARIES OF THE SURVEYED LAND.

SIGNATURE: *Eric J. Schoot* DATE: 8/5/21  
 PRINT NAME: ERIC SCHOOT  
 REGISTRATION NUMBER: S-3149-8

SIGNATURE: *Heather L. Dreisel* DATE: 8/5/21  
 PRINT NAME: HEATHER L. DREISEL

THIS PLAT AND RELOCATION ORDER ARE APPROVED FOR THE WISCONSIN DEPARTMENT OF TRANSPORTATION



PROJECT NO:	7520-00-77	HWY:	STH 95	COUNTY:	JACKSON	PLAN AND PROFILE:	STH 95	SHEET	<b>E</b>
-------------	------------	------	--------	---------	---------	-------------------	--------	-------	----------

BENCHMARKS			
NO.	STATION, OFFSET	DESCRIPTION	ELEV.
50	62+15.32, 26.31' LT	SPIKE IN POWER POLE	902.97
51	63+16.28, 39.09' RT	SPIKE IN TREE	896.89

CONTROL POINTS				
NO.	STATION, OFFSET	DESCRIPTION	Y	X
101	62+24.00, 22.47' RT	REBAR W/ CAP	154,189.92	91,353.62
102	63+59.35, 38.38' LT	REBAR W/ CAP	154,249.94	91,489.34

LEGEND	
	RIPRAP HEAVY
	CONCRETE PAVEMENT APPROACH SLAB
	SILT FENCE
	TURBIDITY BARRIER

STA 62+81 STRUCTURE B-27-0171  
 SINGLE SPAN PRESTRESSED CONCRETE GIRDER  
 36.0 FT CLEAR ROADWAY WIDTH  
 73.83 FT OVERALL LENGTH  
 NO SKEW



REMOVE EXISTING STRUCTURE B-27-0147  
 STA 62+81  
 SINGLE SPAN STEEL DECK GIRDER  
 34.0 FT CLEAR ROADWAY WIDTH  
 60.0 FT OVERALL LENGTH  
 NO SKEW

EARTHWORK SUMMARY STA 61+37 - STA 64+50	
EXC. COMMON	203 CY
WASTE	13 CY
FILL	281 CY
FILL EXPANSION	30 %
BORROW	175 CY

## Standard Detail Drawing List

08A05-19C	INLET COVERS TYPE F, HM, HM-S, S, T, V, HM-GJ, & HM-GJ-S
08C07-02	INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT
08D01-22A	CONCRETE CURB & GUTTER
08D01-22B	CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS
08E09-06	SILT FENCE
08E11-02	TURBIDITY BARRIER
08F01-11	APRON ENDWALLS FOR CULVERT PIPE
09G02-05A	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
09G02-05B	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
09G02-05C	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
12A03-10	NAME PLATE (STRUCTURES)
13B02-09A	CONCRETE PAVEMENT APPROACH SLAB
13C01-19	CONCRETE PAVEMENT LONGITUDINAL JOINTS AND TIES
13C11-13A	RURAL DOWELED CONCRETE PAVEMENT
13C11-13B	RURAL DOWELED CONCRETE PAVEMENT
14B07-16A	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16B	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16C	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16D	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16E	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16F	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16G	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16H	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16I	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16J	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16K	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16L	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16M	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B15-11A	STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS
14B15-11B	STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS
14B15-11C	STEEL PLATE BEAM GUARD, CLASS "A", INSTALLATION & ELEMENTS
14B18-06A	STEEL PLATE BEAM GUARD, CLASS "A" (AT BRIDGES, OBSTACLES AND SIDEROADS/DRIVEWAYS)
14B20-11A	STEEL THREE BEAM STRUCTURE APPROACH
14B20-11B	STEEL THREE BEAM STRUCTURE APPROACH, CONNECTION TO SQUARE END PARAPETS
14B24-09A	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL
14B24-09B	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL
14B24-09C	STEEL PLATE BEAM GUARD ENERGY ABSORBING TERMINAL
15C02-08F	ADVANCED WIDTH RESTRICTION SIGNING
15C04-05	TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45 M. P. H. OR GREATER TWO-WAY UNDIVIDED ROAD OPEN TO TRAFFIC
15C06-10	SIGNING & MARKING FOR TWO LANE BRIDGES
15C08-21A	LONGITUDINAL MARKING (MAINLINE)
15C11-09B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15C12-09A	TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION
15C12-09B	TRAFFIC CONTROL, LANE CLOSURE WITH AUTOMATED FLAGGER ASSISTANCE DEVICE
15D28-04	TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY
15D33-07	TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS






**TYPE "F"**

USE WITH TYPES A & D CONCRETE CURB & GUTTER, 36 INCH.

**GENERAL NOTES**


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

DETAIL DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR INLET COVERS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.



**ALTERNATIVE CURB BOX FOR TYPE "HM" COVER**

USE WITH TYPES G & J CONCRETE CURB & GUTTER, 30 INCH NOTED AS TYPE HM-GJ ON DRAINAGE TABLE



**TYPE "HM"**



USE WITH TYPES A & D CONCRETE CURB & GUTTER, 36 INCH.

NOTE: SPECIAL GRATE FOR THE TYPE "H" COVER MAY ALSO BE USED FOR THE TYPE "HM" COVER NOTED AS TYPE HM-S ON DRAINAGE TABLE



NOTE: SPECIAL GRATE FOR THE TYPE "H" COVER MAY ALSO BE USED FOR THE TYPE "HM-GJ" COVER NOTED AS TYPE HM-GJ-S ON DRAINAGE TABLE

6


6



**TYPE "S"**




**TYPE "V"**



**TYPE "T"**

USE WITH TYPES R & T CONCRETE CURB & GUTTER, 36 INCH.




**INLET COVERS**  
TYPE F, HM, HM-S, S, T, V,  
HM-GJ, & HM-GJ-S

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION


APPROVED  
11/27/2013 DATE /s/ Jerry H. Zogg  
ROADWAY STANDARDS DEVELOPMENT ENGINEER  
FHWA

S.D.D. 8 A 5-19C


S.D.D. 8 A 5-19C




PLAN VIEW




PLAN VIEW



RISER JOINTS TO BE SEALED WITH A BUTYL RUBBER SEAL PER SEALANT MANUFACTURERS RECOMMENDATIONS CONFORMING TO ASTM C 990 (TYP)




SECTION A-A



SECTION B-B

PRECAST REINFORCED CONCRETE WITH MONOLITHIC BASE  
 PRECAST REINFORCED CONCRETE WITH INTEGRAL BASE  
 KEYWAY

CONSTRUCTION JOINT  
 CAST-IN-PLACE REINFORCED CONCRETE  
 CONCRETE BLOCK WITH CAST-IN-PLACE OR PRECAST REINFORCED CONCRETE BASE ①



SEPARATE PRECAST REINFORCED CONCRETE BASE OPTION

**GENERAL NOTES**

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

UNLESS OTHERWISE AUTHORIZED IN WRITING BY THE ENGINEER, THE CONTRACTOR SHALL NOT ORDER AND DELIVER PRECAST INLET UNITS REQUIRED FOR THE PROJECT UNTIL A LIST OF SIZES IS FURNISHED BY THE ENGINEER.

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.

ALL PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF ASTM C 913.

ALL DRAINAGE STRUCTURES ARE DESIGNATED ON THE PLANS AS "MANHOLES 3X3-L", "CATCH BASINS 4-B", "INLETS 2X3-H", ETC. THE FIRST NUMBERS DESIGNATES THE SIZE OF THE STRUCTURE, AND THE FOLLOWING LETTER DESIGNATES THE TYPE OF COVER TO BE USED TO COMPRISE THE COMPLETE UNIT.

BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH, WHICH MEETS THE REQUIREMENTS OF FOUNDATION BACKFILL. THIS BEDDING SHALL BE COMPACTED AND PROVIDE UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE.

ALL BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

PRECAST REINFORCED RISERS SHALL HAVE A TONGUE AND GROOVE JOINT WITH TONGUE UP OR DOWN.

4" OVERHANGING BASES ARE REQUIRED FOR CAST-IN-PLACE REINFORCED CONCRETE AND CONCRETE BLOCK INSTALLATIONS. 4" OVERHANG IS REQUIRED WHEN SEPARATE PRECAST BASE IS PROVIDED. OVERHANG IS NOT REQUIRED ON PRECAST STRUCTURES WITH AN INTEGRAL OR MONOLITHIC BASE.

MAXIMUM INSIDE PIPE DIAMETER DETERMINED BY 3 INCH CLEARANCE ON EACH SIDE OF THE OUTSIDE WALL OF THE PIPE. SEE DETAIL "A". ASSUMES PIPE ENTERS PERPENDICULAR TO THE STRUCTURE.

① FOR PRECAST INLETS PROVIDE REINFORCING STEEL IN ACCORDANCE TO ASTM C 913.


② CONTRACTOR TO PROVIDE DRAWING(S) STAMPED BY A PROFESSIONAL ENGINEER FOR STEEL REINFORCING DESIGN FOR CAST-IN-PLACE STRUCTURES.

**INLET COVER MATRIX**

INLET SIZE	INLET COVER TYPE		ALL A'S	ALL B'S	BW	F	ALL H'S	S	T	V	WM
	WIDTH (W) (FT)	LENGTH (L) (FT)									
2X2-FT	2	2	X	X				X		X	
2X2.5-FT	2	2.5			X			X	X	X	X
2X3-FT	2	3					X				
2.5X3-FT	2.5	3				X					

**PIPE MATRIX**

INLET SIZE	MAXIMUM INSIDE PIPE DIAMETER	
	WIDTH (IN)	LENGTH (IN)
2X2-FT	12	12
2X2.5-FT	12	18
2X3-FT	12	24
2.5X3-FT	18	24




DETAIL "A"

**INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT**


INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT

STATE OF WISCONSIN  
 DEPARTMENT OF TRANSPORTATION


APPROVED  
 Sept., 2016 /S/ Rodney Taylor  
 DATE ROADWAY STANDARDS DEVELOPMENT  
 FHWA UNIT SUPERVISOR




TYPES A<sup>①</sup> & D




6" SLOPED CURB TYPES G<sup>①</sup> & J



4" SLOPED CURB TYPES G<sup>①</sup> & J




TYPES K<sup>①</sup> & L  
(OPTIONAL CURB SHAPE)




TYPES K<sup>①</sup> & L

CONCRETE CURB AND GUTTER 30"




TYPES A<sup>①</sup> & D

CONCRETE CURB AND GUTTER 18"




6" SLOPED CURB TYPES A<sup>①</sup> & D




4" SLOPED CURB TYPES A<sup>①</sup> & D

CONCRETE CURB AND GUTTER 36"



4" SLOPED CURB TYPES R<sup>①</sup> & T

TBT & TBTT	X
30"	22"
36"	28"




TYPES TBT & TBTT<sup>①</sup>

CONCRETE CURB AND GUTTER


PAVEMENT THICKNESS AND MAXIMUM CONCRETE PANEL WIDTH TABLE

PAVEMENT THICKNESS	MAXIMUM PANEL WIDTH
LESS THAN 10"	12'
10" & ABOVE	15'



PARTIAL SECTION OF PAVEMENT \*  
WITH INTEGRAL CURB AND GUTTER

\* BIKE LANE IS NOT SHOWN



REVERSE SLOPE GUTTER<sup>⑥</sup>  
(TYPICAL FOR ALL CURB & GUTTER TYPES)

GENERAL NOTES


DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.


INTEGRAL CURB AND GUTTER SHALL CONFORM TO THE DETAILS SHOWN FOR CONCRETE CURB AND GUTTER INCLUDING THE TRANSVERSE GUTTER SLOPE.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.

- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ③ USE 8" MINIMUM GUTTER THICKNESS WHEN USED WITH AN ADJACENT CONCRETE TRUCK APRON PLACED BEHIND BACK OF CURB.
- ④ THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 8" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑤ UNLESS OTHERWISE NOTED, FOR STAKING PURPOSES THE FACE OF CURB IS 6" FROM THE BACK OF CURB.
- ⑥ WHEN REVERSE SLOPE GUTTER IS REQUIRED, THE LOCATION(S) WILL BE SHOWN ELSEWHERE IN THE PLAN.
- ⑦ USE 4% GUTTER CROSS SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.
- ⑧ INCLUDE LONGITUDINAL JOINT AND TIE BARS ALONG LANE EDGE WHEN CONCRETE PANEL WIDTH EXCEEDS THE MAXIMUM WIDTH PER TABLE BELOW. LONGITUDINAL JOINT(S) ARE NOT ALLOWED WITHIN TRAFFIC LANES AND BIKE LANES. LONGITUDINAL JOINT MAY BE SAWED.
- ⑨ CONCRETE CURB AND GUTTER 4-INCH SLOPED 30-INCH TYPE "R" AND "T" = 17 INCHES  
CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE "R" AND "T" = 23 INCHES



**END SECTION CURB AND GUTTER**



**DETAIL OF CURB AND GUTTER AT INLETS**  
(TYPICAL H INLET COVER SHOWN)


**GENERAL NOTES**

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.


PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.


- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑨ REFER TO SDD 08D18 AND 08D19 FOR ADDITIONAL DRIVEWAY ENTRANCE CURB DETAILS.



**TYPICAL TIE BAR LOCATION** ①




**TYPES A ① & D**




**TYPES G ① & J**

**CONCRETE CURB**




**PLAN VIEW**



**SECTION A - A**

**TIE BARS DRILLED INTO EXISTING PAVEMENT**




**DRIVEWAY ENTRANCE CURB** ⑨  
(WHEN DIRECTED BY THE ENGINEER)

**CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
February 2021 /S/ Rodney Taylor  
DATE ROADWAY STANDARDS DEVELOPMENT  
ENGINEER

FHWA



PLAN VIEW  
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2  
PLAN VIEW  
SILT FENCE AT MEDIAN SURFACE DRAINS

**GENERAL NOTES**


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL

NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS




SILT FENCE

\* NOTE: 8'-0" POST SPACING ALLOWED IF A WOVEN GEOTEXTILE FABRIC IS USED.



JOINING TWO LENGTHS OF SILT FENCE ⑤



SILT FENCE TIE BACK  
(WHEN REQUIRED BY THE ENGINEER)

**SILT FENCE**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION


APPROVED

4-29-05

DATE


FHWA

/S/ Beth Cannestra  
CHIEF ROADWAY DEVELOPMENT ENGINEER




**SECTION B - B**

**TURBIDITY BARRIER - FLOAT ALTERNATIVE  
CAUTION - SEE NOTE 6**




**PLAN VIEW**



**SECTION A - A**

**TURBIDITY BARRIER - STANDARD POST INSTALLATION**



**PLAN VIEW**


**TURBIDITY BARRIER PLACEMENT DETAILS**

**GENERAL NOTES**


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- ① DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- ② SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- ③ WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- ④ IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- ⑤ ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- ⑥ FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- ⑦ ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- ⑧ USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



**PLAN VIEW**



**SECTION C - C**

**TURBIDITY BARRIER DETAIL SHOWING  
TYPICAL PLACEMENT AT STRUCTURES**

**TURBIDITY BARRIER**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
6/4/02 DATE /S/ Beth Cannestra  
DATE CHIEF ROADWAY DEVELOPMENT  
ENGINEER


FHWA

METAL APRON ENDWALLS											
PIPE DIA. (IN.)	MIN. THICK. (Inches)		DIMENSIONS (Inches)							APPROX. SLOPE	BODY
	STEEL	ALUM.	A (±1")	B (MAX.)	H (±1")	L (±1 1/2")	L1	L2	W (±2")		
12	.064	.060	6	6	6	21	12	17 1/2	24	2 1/2 to 1	1 Pc.
15	.064	.060	7	8	6	26	14	21 3/4	30	2 1/2 to 1	1 Pc.
18	.064	.060	8	10	6	31	15	28 1/4	36	2 1/2 to 1	1 Pc.
21	.064	.060	9	12	6	36	18	29 5/8	42	2 1/2 to 1	1 Pc.
24	.064	.075	10	13	6	41	18	37 1/4	48	2 1/2 to 1	1 Pc.
30	.079	.075	12	16	8	51	18	52 1/4	60	2 1/2 to 1	1 Pc.
36	.079	.105	14	19	9	60	24	59 3/4	72	2 1/2 to 1	2 Pc.
42	.109	.105	16	22	11	69	24	75 5/8	84	2 1/2 to 1	2 Pc.
48	.109	.105	18	27	12	78	24	81	90	2 1/4 to 1	3 Pc.
54	.109	.105	18	30	12	84	30	85 1/2	102	2 1/4 to 1	3 Pc.
60	.109x	.105x	18	33	12	87	—	—	114	2 to 1	3 Pc.
66	.109x	.105x	18	36	12	87	—	—	120	2 to 1	3 Pc.
72	.109x	.105x	18	39	12	87	—	—	126	2 to 1	3 Pc.
78	.109x	.105x	18	42	12	87	—	—	132	1 1/2 to 1	3 Pc.
84	.109x	.105x	18	45	12	87	—	—	138	1 1/2 to 1	3 Pc.
90	.109x	.105x	18	37	12	87	—	—	144	1 1/2 to 1	3 Pc.
96	.109x	.105x	18	35	12	87	—	—	150	1 1/2 to 1	3 Pc.


\* EXCEPT CENTER PANEL SEE GENERAL NOTES

REINFORCED CONCRETE APRON ENDWALLS									
PIPE DIA. (IN.)	DIMENSIONS (Inches)							APPROX. SLOPE	
	T	A	B	C	D	E	G		
12	2	4	24	48 1/8	72 1/8	24	2	3 to 1	
15	2 1/4	6	27	46	73	30	2 1/4	3 to 1	
18	2 1/2	9	27	46	73	36	2 1/2	3 to 1	
21	2 3/4	9	36	37 1/2	73 1/2	42	2 3/4	3 to 1	
24	3	9 1/2	43 1/2	30	73 1/2	48	3	3 to 1	
27	3 1/4	10 1/2	49 1/2	24	73 1/2	54	3 1/4	3 to 1	
30	3 1/2	12	54	19 3/4	73 1/2	60	3 1/2	3 to 1	
36	4	15	63	34 3/4	97 3/4	72	4	3 to 1	
42	4 1/2	21	63	35	98	78	4 1/2	3 to 1	
48	5	24	72	26	98	84	5	3 to 1	
54	5 1/2	27	65	33 1/4-35	98 1/4-100	90	5 1/2	2 1/2 to 1	
60	6	30-35	60	39	99	96	5	2 to 1	
66	6 1/2	30-35	72-78	21-27	99	102	5 1/2	2 to 1	
72	7	30-35	78	21	99	108	6	2 to 1	
78	7 1/2	30-35	78	21	99	114	6 1/2	2 to 1	
84	8	36	90 1/2	21	111 1/2	120	6 1/2	1 1/2 to 1	
90	8 1/2	41	87 1/2	24	111 1/2	132	6 1/2	1 1/2 to 1	


\* MINIMUM  
\*\* MAXIMUM




END CORNER PLATES MAY BE FASTENED TO APRON PROPER BY BOLTS, RIVETS, OR RESISTANCE SPOT WELDS WHICH WILL HOLD THE SURFACES TIGHTLY TOGETHER




SIDE ELEVATION  
METAL ENDWALLS



PLAN




END VIEW




LONGITUDINAL SECTION  
CONCRETE ENDWALLS


1" WIDE, 12 GA. (0.109" THICK) GALVANIZED STRAP WITH STANDARD 6" X 1/2" BAND BOLT AND NUT




ALTERNATE FOR TYPE 1 CONNECTION  
END SECTION CONNECTOR STRAP




TYPE 1  
FOR 12" THRU 24" CORR. PIPE



TYPE 2  
FOR 30" THRU 96" CORR. PIPE



TYPE 3  
FOR 42" THRU 96" CORR. PIPE



TYPE 5  
ALTERNATE FOR:  
ALL SIZES CORRUGATED CIRCULAR PIPE


NOTE: DIMPLED BAND FITS OVER OUTSIDE OF ENDWALL, AND CORRUGATED BAND FITS INSIDE ENDWALL. DIMPLED BAND MAY BE USED WITH HELICALLY CORRUGATED PIPE.

FOR CIRCUMFERENTIALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2, 3 OR 5 AS APPLICABLE.

FOR HELICALLY CORRUGATED PIPE USE ENDWALL CONNECTION DETAILS 1, 2 OR 5.

FOR HELICALLY CORRUGATED PIPES WITH TWO CIRCUMFERENTIAL CORRUGATIONS AT EACH END USE ENDWALL CONNECTION DETAILS 1, 2 OR 3.

CONNECTION DETAILS



SECTION A-A

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

CONCRETE CULVERT ENDWALLS MAY NOT BE USED WITH GALVANIZED STEEL OR ALUMINUM CULVERT PIPE OR VICE VERSA. GALVANIZED STEEL OR ALUMINUM ENDWALLS SHALL NORMALLY BE INSTALLED ON CULVERT PIPE OF THE SAME METAL.

ALL THREE PIECE STEEL APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.109" SIDES AND 0.138" CENTER PANELS. ALL THREE PIECE ALUMINUM APRON ENDWALLS FOR 60" DIAMETER PIPE AND LARGER SHALL HAVE 0.105" SIDES AND 0.134" CENTER PANELS. THE WIDTH OF CENTER PANELS SHALL BE GREATER THAN 20 PERCENT OF THE PIPE PERIMETER.

LAP SEAMS SHALL BE TIGHTLY JOINED BY GALVANIZED RIVETS OR BOLTS FOR STEEL UNITS AND ALUMINUM RIVETS AND BOLTS FOR ALUMINUM UNITS. FOR THE 60" THROUGH 96" DIAMETER APRON ENDWALL SIZES, THE REINFORCED EDGES AND CENTER PANEL SEAMS SHALL BE FURTHER REINFORCED WITH GALVANIZED STEEL OR ALUMINUM STIFFENER ANGLES. THE ANGLES SHALL BE ATTACHED BY GALVANIZED NUTS AND BOLTS FOR STEEL UNITS AND ALUMINUM NUTS AND BOLTS FOR ALUMINUM UNITS.


WHERE TWO OR MORE PIPES WITH APRON ENDWALLS ARE LAID ADJACENT TO EACH OTHER, THEY SHALL BE SEPARATED BY A DISTANCE SUFFICIENT TO PROVIDE A MINIMUM CLEARANCE OF 6 INCHES BETWEEN APRON ENDWALLS.

① FOR PIPE SIZES UP TO 60" DIAMETER, A 180° ROLLED EDGE MAY BE USED INSTEAD OF STEEL ROD REINFORCEMENT. SEE SECTION A-A.

APRON ENDWALLS FOR  
CULVERT PIPE

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
11/30/94 DATE /S/ Rory L. Rhinesmith  
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER  
FHWA



**TYPICAL BRIDGE TEMPORARY TRAFFIC SIGNAL LOCATION**

**LEGEND**


- WOOD POLE (NON-BREAKAWAY)
- WOOD POST (BREAKAWAY)
- - - SIGNAL CABLE
- SIGNAL CABLE W/MESSENGER

DIRECTION OF TRAFFIC →


LED TRAFFIC SIGNAL WITH BACKPLATE  
3-12"

**GENERAL NOTES**


- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.
- POLE MOUNTED TRAFFIC SIGNAL CONTROL CABINET MAY BE MOUNTED ON THE SERVICE POLE IF THE ELECTRICAL UTILITY ALLOWS THE INSTALLATION.
- WHEN UTILITY POLES ARE USED TO SPAN THE TEMPORARY OVERHEAD CABLE, WRITTEN PERMISSION MUST BE OBTAINED FROM THE OWNER OF THE POLES AND GIVEN TO THE PROJECT MANAGER. ALL PERTINENT UTILITY AND CODE CLEARANCES SHALL BE MAINTAINED.
- WOOD POLES (NON-BREAKAWAY) SHALL BE NO CLOSER TO EDGE OF PAVEMENT THAN OFFSET DISTANCE CHART ALLOWS OR 4 FEET BEHIND PROTECTIVE BARRIER (BEAM GUARD, ETC.).
- WOOD POSTS (BREAKAWAY) SHALL BE NO CLOSER THAN 2 FEET OUTSIDE OF SHOULDER.
- VERTICAL CLEARANCE ETC. PER NEC.
- TRAFFIC SIGNAL FACES SHALL BE TYPICALLY PLACED 12 FEET FROM EDGE OF PAVEMENT.
- EACH TRAFFIC SIGNAL SHALL HAVE A BACKPLATE.
- SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.



**TYPICAL DROP TO TRAFFIC SIGNAL FACE**



**POLE MOUNT CABINET INSTALLATION**



**GROUND MOUNT CABINET INSTALLATION**

MINIMUM POLE LENGTHS	CLASS	POLE BURIAL DEPTHS
25'	V	5'
30'	V	6'
35'	IV	7'
40'	IV	8'
45'	IV	9'

OFFSET DISTANCES FOR TEMPORARY NON-BREAKAWAY POLES	
SPEED LIMIT	OFFSET DISTANCE*
GREATER THAN 45 MPH	18 FT
45 MPH OR LESS	12 FT
45 MPH OR LESS W/CURBS	2 FT

\* NOTE: OFFSET MEASURED FROM OUTER EDGE OF OUTSIDE THRU LANE.

**BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
March 2018 /S/ Ahmet Demirelek  
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA

6

6


SDD09G02 - 05a

SDD09G02 - 05a



**GENERAL NOTES**

USE 3/4" DRILL IN WOOD POLE TO PROVIDE FOR 5/8" BOLTS.



**SPAN WIRE POLE**

**GUY POLE**

**TYPICAL DEAD-ENDINGS OR GUYING**


<b>BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION</b>	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED June 2015 DATE	/S/ Ahmet Demerbilek ROADWAY STANDARDS DEVELOPMENT ENGINEER
<small>FHWA</small>	

6

6

**SDD09G02 - 05b**

**SDD09G02 - 05b**




**TRAILER MOUNTED TRAFFIC SIGNAL**

**GENERAL NOTES**






DETAIL OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.



**TYPICAL TRAILER MOUNTED TRAFFIC SIGNAL LOCATION**

**LEGEND**


-  POST MOUNTED SIGN
-  TEMPORARY PRECAST CONCRETE BARRIER
-  TRAILER MOUNTED TRAFFIC SIGNAL
-  REMOVE PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC

**BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
June 2015 /S/ Ahmet Demerbilek  
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA




**TYPICAL NAME PLATE**  
(BRIDGES, CULVERTS, AND RETAINING WALLS)

**GENERAL NOTES**


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.




**SECTION A-A**




SPREAD OPEN SO THE TOP OF LUG IS 1 1/4" WIDE

**ALTERNATE LUG**



**NUMBERING DESIGNATION  
MULTI-UNIT STRUCTURES**

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.




**ALTERNATE LUG**  
(FOR ATTACHMENT TO PRECAST STRUCTURES)


**NAME PLATE  
(STRUCTURES)**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION


APPROVED  
DATE 3/26/10 /S/ Scot Becker  
CHIEF STRUCTURAL DEVELOPMENT ENGINEER  
FHWA



**SKewed APPROACH  
(PAVEMENT MORE THAN TWO LANES)**




**SKews > 20°  
(PAVEMENT WIDTH ≤ 30')**




**SKews ≤ 20°  
(PAVEMENT WIDTH ≤ 30')**  
**APPROACH SLAB AND ADJACENT PAVEMENT**


- \* (RS) = REINFORCED CONCRETE SLAB
- \* (PS) = PAVED CONCRETE SHOULDER OR CONCRETE DRAINAGE SLAB
- \* (NRS) = NON - REINFORCED CONCRETE SLAB
- \*\*\* STANDARD DOWEL BAR DIAMETER (SEE SDD 13C11 AND SDD 13C13)



**SECTION A - A  
REINFORCEMENT POSITIONING DETAIL**




**SECTION B - B  
BEND DETAIL  
BOTTOM REINFORCEMENT**




**SECTION C - C  
TRANSITION DETAIL  
APPROACH SLAB TO ADJACENT PAVEMENT**

**GENERAL NOTES**

- THE CONTRACTOR MAY SPLICE NO. 6 BARS IN THE APPROACH SLAB FOR SKEWED STRUCTURES ONLY. STAGGER SPLICES WITH A MAXIMUM OF ONE SPLICE PER BAR. THE LENGTH OF LAP IS 20 INCHES.
- TACK WELD DOWEL BARS TO THE BASKETS ON ALTERNATE ENDS.
- ① THE CONTRACTOR MAY USE NO. 4 BARS SPACED AT 2' - 0" C - C IN BOTH THE LONGITUDINAL AND TRANSVERSE DIRECTIONS FOR TOP REINFORCEMENT AS AN ALTERNATIVE TO THE WELDED WIRE FABRIC.
  - ② THE CONTRACTOR MAY OMIT THE BARS BETWEEN REINFORCED SLABS WHERE SLAB REINFORCEMENT BARS EXTEND ACROSS THE CENTERLINE OR REFERENCE LINE.
  - ③ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING AN HMA PAVEMENT.
  - ④ USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
  - ⑤ PLACE EXPANSION CAP ON THE END OF THE DOWEL THAT IS NOT TACK WELDED TO THE BASKET. DO NOT FORCE DOWEL BAR PAST THE DOWEL STOP.
  - ⑥ EXTEND EXPANSION JOINT THROUGH ANY ADJACENT TIED CONCRETE.
  - (A) STANDARD CONTRACTION JOINT NORMAL TO  $\perp$  OR  $\parallel$ .
  - (B) STANDARD LONGITUDINAL JOINT WITH TIE BARS.
  - (C) 1 1/2" EXPANSION JOINT WITH DOWEL BARS NORMAL TO  $\perp$  OR  $\parallel$ .



**SECTION D - D  
CONTRACTION JOINT**




**EXPANSION JOINT DETAIL**

**CONCRETE PAVEMENT  
APPROACH SLAB**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
November 2018 /S/ Peter Kemp, P.E.  
DATE DATE PAVEMENT SUPERVISOR

FHWA




**CONSTRUCTION JOINT**



**SAWED JOINT**


**GENERAL NOTES**

- CREATE A LONGITUDINAL JOINT FOR PAVEMENT WIDTHS GREATER THAN 15 FEET.
- CORRELATE LONGITUDINAL JOINTS WITH LANE LINES WHEN POSSIBLE.
- ① ANCHOR TIE BARS INTO DRILLED HOLES WITH AN EPOXY.
- ② PAVEMENT THAT WAS IN PLACE PRIOR TO THE CONTRACT.




**PLAN VIEW**


NO. 6 TIE BARS SPACED 30" C-C, INSTALLED PERPENDICULAR TO THE LONGITUDINAL JOINT. ①




**SECTION A-A  
LONGITUDINAL CONSTRUCTION JOINT  
TIE BARS ANCHORED  
INTO EXISTING PAVEMENT**



**DETAIL "A"**



**DETAIL "B"**




**DETAIL "C"**

**TIE BAR TABLE**

PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
< 10 1/2"	NO. 4	30"	36"
≥ 10 1/2"	NO. 5	36"	36"
	NO. 4 *	30"	24" **

\* SUBSTITUTE BENT BARS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES)

\*\* CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.



**PLAN VIEW  
SHOWING LOCATION OF TIE BARS**

**CONCRETE PAVEMENT  
LONGITUDINAL JOINTS AND TIES**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
March 2018 /S/ Peter Kemp, P.E.  
DATE PAVEMENT SUPERVISOR

FHWA

6

6

S.D.D. 13 C 1-19

S.D.D. 13 C 1-19

**GENERAL NOTES**

CONTRACTION JOINTS

CONSTRUCT TRANSVERSE CONTRACTION JOINTS NORMAL TO THE CENTERLINE. SHOW THE LOCATION OF CONTRACTION JOINTS THROUGH INTERSECTIONS ON THE PLANS OR AS DIRECTED BY THE ENGINEER.


INSTALL DOWEL BARS PARALLEL TO THE PAVEMENT CENTERLINE AND PAVEMENT SURFACE.

FOR PAVEMENT SLABS OF VARYING WIDTHS, LOCATE THE OUTER MOST DOWEL BAR SO THAT THE CENTER OF THE BAR IS A MINIMUM OF 6 INCHES FROM AND A MAXIMUM OF 18 INCHES FROM THE FREE EDGE OF PAVEMENT.


CONSTRUCTION JOINTS

LOCATE CONSTRUCTION JOINTS A MINIMUM OF 6 FEET FROM THE NEAREST CONTRACTION JOINT AND ALIGN PARALLEL TO THE CONTRACTION JOINTS.


- ① REFER TO TYPICAL CROSS SECTIONS FOR ADDITIONAL DETAILS.
- ② MEASURE THE ENTIRE PAVED WIDTH INCLUDING THE PORTION(S) LABELED "PAVED SHOULDER" AS CONCRETE PAVEMENT.



**SECTION A - A  
TWO-LANE TWO-WAY HIGHWAY** ①




**SECTION B - B  
ALTERNATIVE SECTION B - B  
DIVIDED HIGHWAY** ①




**ALTERNATIVE SECTION B - B  
DIVIDED HIGHWAY** ①

**PAVEMENT DEPTH, DOWEL BAR SIZE AND JOINT SPACING TABLE**

PAVEMENT DEPTH (D)	DOWEL BAR DIAMETER	CONTRACTION JOINT SPACING
5 1/2", 6", 6 1/2"	NONE	12'
7", 7 1/2"	1"	14'
8", 8 1/2"	1 1/4"	15'
9" & ABOVE	1 1/4"	15'




**CONTRACTION JOINT LAYOUT FOR  
TWO-LANE TWO-WAY HIGHWAY**




**CONTRACTION JOINT LAYOUT FOR  
DIVIDED HIGHWAY**

**RURAL DOWELED  
CONCRETE PAVEMENT**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION



**PLAN VIEW**




**SIDE VIEW**  
(NORMAL TO CENTERLINE)


**CONTRACTION JOINT DOWEL ASSEMBLY** ①

**GENERAL NOTES**


- ① OBTAIN THE ENGINEER'S APPROVAL FOR THE USE OF ALTERNATIVE DESIGNS OF THE DOWEL ASSEMBLY. USE MECHANICAL DOWEL BAR INSERTERS OR DOWEL ASSEMBLIES WHEN CONSTRUCTION JOINTS.
- ② SECURE BASKETS WITH ANCHORS TO HOLD DOWEL BARS IN THE CORRECT POSITION AND ALIGNMENT. TYPE, LOCATION, NUMBER AND LENGTH OF ANCHORS ARE DEPENDENT UPON FIELD CONDITIONS.
- ③ FORM OR SAW CONSTRUCTION JOINTS. PROVIDE A 1/4" RADIUS AT FORMED JOINTS.
- ④ PROVIDE A SMOOTH VERTICAL FACE FOR THE ENTIRE DEPTH OF THE PAVEMENT WHEN FORMING CONSTRUCTION JOINTS.
- ⑤ INSTALL DOWEL BARS AT CONSTRUCTION JOINTS BY FORMING OR DRILLING. INSTALL FORMED DOWEL BARS 12 INCHES C - C AND 12 INCHES FROM PAVEMENT EDGE. REMOVE EXCESS CONCRETE FROM THE FREE END OF THE DOWEL BAR IF DOWEL BARS ARE FORMED THROUGH A HEADER BOARD. INSTALL DRILLED DOWEL BARS ACCORDING TO THE "DRILLED DOWEL BAR CONSTRUCTION JOINT" DETAIL.
- ⑥ APPLY A THIN UNIFORM COATING OF SURFACE TREATMENT TO THE FREE END OF DOWEL BARS TO PREVENT BONDING.
- ⑦ ANCHOR DOWEL BARS AND TIE BARS INTO DRILLED HOLES WITH AN EPOXY. MAXIMUM DRILLED HOLE SIZE IS 1/8" GREATER THAN DOWEL BAR DIAMETER, 9 INCHES IN LENGTH.



**DRILLED DOWEL BAR CONSTRUCTION JOINT** ⑦




**DOWELED CONTRACTION JOINT**




**TRANSVERSE CONSTRUCTION JOINT**

<b>RURAL DOWELED CONCRETE PAVEMENT</b>	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 00-00-00 DATE	/S/ <AUTHOR> PAVEMENT SUPERVISOR
<small>FHWA</small>	



**CROSS SECTION**




**PROFILE VIEW**

**GENERAL NOTES**


PLACE BARRIER ON PAVED SURFACE. BEFORE PLACEMENT OF TEMPORARY BARRIER, REMOVE ALL LOOSE MATERIAL FROM PAVED SURFACE.

LOOP BARS C1, C2 AND C3 ARE NOT FOR PLACEMENT OR MOVEMENT OF BARRIER.


- (100) PERMANENTLY FORM INTO ONE END OF BARRIER THE FOLLOWING INFORMATION:  
A. TYPE OF BARRIER: WI-CBTP  
B. MANUFACTURER  
C. DATE OF MANUFACTURE (MONTH AND YEAR)
- (101) 1" OPTIONAL CHAMFER
- (102) SEE LIFTING SLOT DETAIL
- (103) SEE ANCHOR BLOCK DETAIL
- (104) 1 3/4" MIN. CLEAR COVER
- (105) 2" MIN. CLEAR COVER
- (106) 1" MIN. CLEAR COVER
- (107) ± 1/8" MEASURED FROM FACE OF CONCRETE BARRIER TO OUTSIDE OF LOOP BAR (TYP.)
- (108) USE DELINEATORS CONFORMING TO SECTION 633 OF THE STANDARD SPECIFICATIONS. CONTRACTOR MY USE ALTERNATE SHAPES AND HOUSING. INSTALL DELINEATORS ACCORDING TO MANUFACTURERS INSTRUCTION. INSTALL YELLOW REFLECTORS WHEN BARRIER IS LOCATED LEFT OF TRAFFIC AND WHITE WHEN BARRIER IS LOCATED RIGHT OF TRAFFIC. SPACE DELINEATORS A MAXIMUM OF 25 FEET APART, PROVIDE TO MOUNTED DELINEATORS IN ADDITION TO SIDE MOUNTED DELINEATORS ON BARRIER INSTALLATIONS LOCATED ON A CURVED ALIGNMENT LONGER THAT 200 FEET AND ON BARRIERS USED TO SEPARATE OPPOSING TRAFFIC.






**ANCHOR BLOCK DETAIL**



**PLAN VIEW  
TEMPORARY BARRIER**



**LIFTING SLOT DETAIL  
(TYP.)**




**PROFILE VIEW  
TEMPORARY BARRIER REINFORCEMENT**


**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION









**B4 BAR DETAIL**



**B5 BAR DETAIL**





**PROFILE VIEW  
LOOP BAR ASSEMBLY**







**C BAR DETAILS**

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




- GENERAL NOTES**
- (300) SET WITH 3 5/8" WOOD BLOCK.
  - (301) HOLE IS OPTIONAL.
  - (302) CONNECTOR PIN ASSEMBLY.
  - (303) CONCRETE PAVEMENT, APPROACH SLAB, OR DECK.
  - (304) CONCRETE DECK.
  - (305) DO NOT USE ON CONCRETE BRIDGE DECK WITH ASPHALT OVERLAY OR CONCRETE PAVEMENT WITH ASPHALT OVERLAY.
  - (306) MINIMUM OF 2" OF ASPHALT.
  - (307) ASPHALT ANCHOR PIN ASSEMBLY




**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




**PLAN VIEW**  
**TRANSITION FROM FREE STANDING TO ANCHORED BARRIER**




**PROFILE VIEW**  
**ANCHORED BARRIER NEAR EXPANSION JOINT**




**CROSS SECTION**  
**FREE STANDING BARRIER**



**CROSS SECTION**  
**ANCHORED BARRIER FOR OBJECTS ABOVE THE GRADE LINE AND NEAR THE BARRIER**



**CROSS SECTION**  
**ANCHORED BARRIER NEAR VERTICAL DROP OFF**



**CROSS SECTION**  
**ANCHORED BARRIER NEAR A SLOPE**

**GENERAL NOTES**


- 400 NO SINGLE CONCRETE BARRIER SECTION SHALL BE ANCHORED TO BOTH THE BRIDGE DECK AND THE APPROACH SLAB. ALL ANCHOR BOLT LOCATIONS SHALL BE ANCHORED TO THE DECK IN ACCORDANCE WITH THE DETAIL. NO MORE THAN ONE ANCHOR BOLT SHALL BE ELIMINATED FROM A BARRIER SECTION WHEN SPANNING AN EXPANSION JOINT.
- 401 CONCRETE DECK
- 402 CONCRETE DECK OR APPROACH SLAB.
- 403 EXPANSION JOINT
- 404 ADHESIVE ANCHOR SHOWN. SEE ANCHOR DETAILS.
- 405 ANCHORED TEMPORARY BARRIER
- 406 TRANSITION FROM ANCHORED TEMPORARY BARRIER TO FREE STANDING
- 407 FREE STANDING BARRIER
- 408 REMOVE ALL ANCHORS WHEN NO LONGER NEEDED. FILL CONCRETE PAVEMENTS, DECKS AND APPROACH SLABS WITH NON-SHRINK COMMERCIAL GROUT FROM THE APPROVED PRODUCT LIST. FILL ASPHALT PAVEMENTS WITH ASTM D6690 TYPE II RUBBERIZED CRACK FILLER.
- 409 TRAFFIC SIDE
- 410 NON-TRAFFIC SIDE
- 411 ANCHOR LOCATION. SEE ANCHORING DETAILS.
- 412 WORK AREA
- 413 AREA FREE OF OBJECTS AND WORKERS
- 414 GRADE LINE
- 415 EXTENDED GRADE LINE
- 416 ANCHORED TEMPORARY BARRIER. SEE BOLT THROUGH DECK, REMOVABLE ADHESIVE ANCHOR, OR AN ASPHALT ANCHOR ROD DETAILS FOR MORE INFORMATION. ASPHALT ANCHOR ROD SHOWN.
- 417 WHEN OBJECTS EXTEND ABOVE THE GRADE. A MINIMUM OF 1 FOOT IS REQUIRED FROM BACK OF BARRIER TO OBJECT.
- 418 OBJECTS ARE NOT TO BE PLACED ON, MOUNTED TO, OR ALLOWED TO LEAN AGAINST THE BARRIER WITHOUT WRITTEN PERMISSION OF THE PROJECT ENGINEER.
- 419 DEPTHS OF 3 FEET OR MORE.
- 420 Y = 6.5'
- 421 OFFSET FROM BACK OF BARRIER EDGE:  
CONCRETE PAVEMENT 0.5'  
ASPHALT 0.5'
- 422 POSTED SPEED (MPH):  
45 OR GREATER 4.0'  
40 OR LOWER 2.0'

**CONCRETE BARRIER**  
**TEMPORARY PRECAST,**  
**12' - 6"**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES**


- (500) EXISTING RIGID BARRIERS (VARIES)
- (501) TEMPORARY BARRIER
- (502) SEE OTHER DETAIL ON HOW TO ANCHOR TEMPORARY BARRIER (BARRIER ASPHALT ANCHOR SHOWN).
- (503) ANCHORS ARE REQUIRED ON BOTH SIDE OF THE TEMPORARY BARRIER.
- (504) NESTED RAILS ARE REQUIRED ON BOTH SIDES OF THE TEMPORARY BARRIER FOR ALL INSTALLATIONS.
- (505) TRAFFIC TRAVELS FROM PERMANENT BARRIER TO TEMPORARY BARRIER.
- (506) TRAFFIC TRAVELS FROM TEMPORARY BARRIER TO PERMANENT BARRIER.
- (507) VERTICAL BARRIER
- (508) SAFETY SHAPE BARRIER
- (509) SINGLE SLOPE BARRIER
- (510) CAP END PLATE PLACED FLUSH WITH UPSTREAM END OF RIGID BARRIER.
- (511) BENT THRIE BEAM TO FIT.
- (512) THRIE BEAM PIECES ARE OFFSET 15 1/4" TO PREVENT INTERFERENCE FROM THE ANCHORS ON OPPOSING SIDES.
- (513) TWO (2) P1, P2 AND P3 ARE REQUIRED
- (514) FIVE (5) N1, N2 AND N3 ARE REQUIRED
- (515) TWO (2) R1, R2 AND R3 ARE REQUIRED
- (516) CUT WOOD BLOCK TO FIT.
- (517) SEE THRIE BEAM RAIL TERMINAL CONNECTOR DETAIL ASSEMBLY.
- (518) CAP ASSEMBLY
- (519) 4" MAX. GAP BETWEEN TEMPORARY BARRIER AND RIGID BARRIER.
- (520) ALL TWELVE SPLICE HOLES REQUIRE M1 AND M2




**PROFILE VIEW**




**PLAN VIEW  
TRANSITION TO RIGID BARRIER**




**PLAN DETAIL VIEW  
TRANSITION TO RIGID BARRIER**




**FRONT DETAIL VIEW  
TRANSITION TO RIGID BARRIER**




**CROSS SECTION  
TEMPORARY BARRIER  
PLACEMENT SINGLE SLOPE**




**CROSS SECTION  
TEMPORARY BARRIER  
PLACEMENT SAFETY SHAPE**



**CROSS SECTION  
TEMPORARY BARRIER  
PLACEMENT VERTICAL**




**BACK DETAIL VIEW  
TRANSITION TO RIGID BARRIER**




**(517) DETAIL PLAN VIEW  
THRIE BEAM RAIL TERMINAL CONNECTOR ASSEMBLY**

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




**TOP VIEW  
S1**




**ELEVATION VIEW  
S1**



**PLAN VIEW**




**BACK VIEW**




**SIDE VIEW (600)**


**42\"/>**




**SIDE VIEW  
S3**




**S2**




**S4**



**S5**



**S6**



**S7**

**GENERAL NOTES**


STITCH WELD GUSSET PLATES AND END PLATES ON THREE SIDES

STITCH WELD TWO SIDE PLATES TO TOP PLATE, END PLATE AND GUSSETS.


(600) SIDE PLATES (S3) NOT SHOWN FOR CLARITY.

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




**SIDE VIEW  
T4**



**SIDE VIEW  
T3**



**SIDE VIEW  
TOP PLATE T1**



**PLAN VIEW  
TOP PLATE T1**


**END VIEW**

**END VIEW**


**END VIEW**

**GENERAL NOTES**


- STITCH WELD GUSSET PLATES AND END PLATES ON THRIE SIDES
- STITCH WELD TWO SIDE PLATES TO TOP PLATE, END PLATE AND GUSSETS.
- SIDE PLATES, TOP PLATE, END PLATE AND GUSSETS ARE 12 GAUGE ASTM A36 GALVANIZED STEEL.
- (700) SIDE PLATES (T3 AND T4) NOT SHOWN FOR CLARITY.




**END VIEW  
56 INCH TOP CAP**




**ISOMETRIC  
56 INCH TOP CAP**




**SIDE VIEW  
56 INCH TOP CAP (700)**




**DETAIL "A"**



**DETAIL "B"**



**END PLATE T2**







**GUSSET PLATES  
T5 - T16**

GUSSET DIMENSIONS				
GUSSET NO.	A	B	C	D
T5	22 13/16"	5 1/16"	2 5/16"	8 1/16"
T6	21"	5 7/8"	2 3/16"	8 1/16"
T7	19 3/16"	6 1/8"	1 13/16"	8 1/16"
T8	17 3/8"	6 1/4"	1 13/16"	8 1/16"
T9	15 9/16"	6 7/16"	1 1/16"	8 1/16"
T10	13 3/4"	6 5/8"	1 7/16"	8 1/16"
T11	11 15/16"	6 13/16"	1 1/4"	8 1/16"
T12	10 1/8"	7"	1 1/16"	8 1/16"
T13	8 5/16"	7 3/16"	7/8"	8 1/16"
T14	6 1/2"	7 3/8"	1 1/16"	8 1/16"
T15	4 1/16"	7 1/16"	1/2"	8"
T16	2 7/8"	7 3/4"	1/4"	8"

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




**GENERAL NOTES**

- 800 FREE STANDING TEMPORARY BARRIER
- 801 GAP STIFFENER ASSEMBLY
- 802 THRIE BEAMS ARE NESTED ON BOTH SIDES OF THE TEMPORARY BARRIER.
- 803 SEE THRIE BEAM RAIL TERMINAL CONNECTOR DETAIL


**PORTABLE CONCRETE BARRIER GAP THRIE BEAM COVER**

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




**PLAN VIEW  
GAP WITHIN SPACING**




**PLAN VIEW  
TEMPORARY BARRIER GAP OVER 4" TO 1' MAX. 904**



**PLAN VIEW  
TEMPORARY BARRIER GAP OVER 1' TO 4' MAX. 904**



**PLAN VIEW  
TEMPORARY BARRIER GAP OVER 4' TO 7' MAX. 904**



**PLAN VIEW  
TEMPORARY BARRIER GAP OVER 7' TO 12.5' MAX. 904**

**GENERAL NOTES**

- 900 SEE OTHER DETAILS FOR TEMPORARY GAP HARDWARE (TYP.)
- 901 TEMPORARY BARRIER GAP
- 902 GAP STIFFENER ASSEMBLY CENTERED IN THE GAP.
- 903 GAP STIFFENER ASSEMBLY IS OFFSET 18 3/4" FROM CENTER
- 904 MINIMUM NUMBER OF GAP STIFFENERS SHOWN FOR THE GAP RANGE SHOWN.
- 905 MINIMUM OF 8 CONTINUOUS FREE STANDING TEMPORARY BARRIERS

6

6


SDD 14B07 - 16i

SDD 14B07 - 16i


**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION







**PROFILE VIEW**      **SIDE VIEW**  
**STIFFENER ASSEMBLY**  
**CENTER PANEL U1**




**FLAT PATTERN**      **SIDE VIEW**  
**STIFFENER ASSEMBLY**  
**SIDE PANEL U2**




**PROFILE VIEW**  
**STIFFENER ASSEMBLY**  
**BOTTOM PANEL U3**




**SECTION A - A**



**SECTION B - B**




**PLAN VIEW**




**PROFILE VIEW**      **SIDE VIEW**

**GAP STIFFENER ASSEMBLY**




**ISOMETRIC**




**SIDE VIEW**

**PLAN VIEW**  
**ELEVATION VIEW**  
**W1 TOE PLATE**




**CONCRETE BARRIER**  
**TEMPORARY PRECAST,**  
**12' - 6"**

STATE OF WISCONSIN  
 DEPARTMENT OF TRANSPORTATION




**ELEVATION VIEW**

**THRIE BEAM  
TERMINAL CONNECTOR**



**ELEVATION VIEW**


**ADDITIONAL THRIE BEAM  
TERMINAL CONNECTOR HOLE DETAIL**




**PLATE WASHER DETAIL  
G2, H3**

**GENERAL NOTES**

- (1100) 1" DIA. HOLE
- (1101) 3/4" DIA. HOLE
- (1102) PROVIDE HOLES IN THRIE BEAM TERMINAL CONNECTOR TO LIMIT STEEL REINFORCEMENT OR LOOP BAR CONFLICT. CONTRACTOR MAY FIELD DRILL ADDITIONAL HOLE OR PROVIDE THRIE BEAM TERMINAL CONNECTOR WITH ADDITIONAL HOLES FROM SUPPLIER.




**SLOTTED THRIE BEAM RAIL K1**




**SECTION THROUGH  
BEAM K1**

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




**SIDE ELEVATION**  
(FOR CONNECTION TO LEFT END OF BARRIER)



**SIDE ELEVATION**  
LOOP BAR ASSEMBLY INVERTED FOR OPPOSITE END  
(FOR CONNECTION TO RIGHT END OF BARRIER)


**GENERAL NOTES**

(1200) SEE LIFTING SLOT DETAIL. LOCATION OF LIFTING SLOTS DETERMINED BY CONTRACTOR.




**FLARE AT BARRIER END**


POSTED SPEED, (MPH)	FLARE RATE
40 OR LESS	6:1
45 OR GREATER	8:1




**PLAN VIEW**




**B12**




**FRONT ELEVATION**



**END SECTION**



**BENT BAR DETAIL**



BAR	A	B
B6	10"	1"
B7	1'- 1"	1 1/4"
B8	1'- 5"	1 5/8"
B9	1'- 8"	1 7/8"
B10	2'- 0 1/2"	2 3/8"
B11	2'- 3"	2 3/4"

**B BARS**

2 OF EACH SIZE REQUIRED FOR STIRRUP ASSEMBLY

**DETAILS OF BARRIER TAPER SECTION**

**CONCRETE BARRIER  
TEMPORARY PRECAST,  
12' - 6"**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

**BILL OF MATERIALS - CONCRETE BARRIER PRECAST**

PART	DESCRIPTION	MATERIALS SPECIFICATIONS	NOTES
A1	PRECAST TEMPORARY BARRIER - CONCRETE	MIN. = f <sub>c</sub> 5000 PSI	
B1	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#5 REBAR, LENGTH 12'-2"
B2	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 12'-2"
B3	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#5 REBAR, LENGTH 12'-2"
B4	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 6'-0"
B5	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#6 REBAR, LENGTH 2'-11"
B6	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 1'-11"
B7	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 2'-2"
B8	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 2'-6"
B9	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 2'-9"
B10	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 3'-2"
B11	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 3'-4"
B12	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 12'-0"
B13	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 7'-9"
B14	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#5 REBAR, LENGTH 11'-9"
C1	LOOP BAR	ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED	¾" DIA.
C2	LOOP BAR	ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED	¾" DIA.
C3	LOOP BAR	ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED	¾" DIA.
D1	CONNECTION PIN - ROD	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	1 ½" DIA.
D2	CONNECTION PIN - TOP PLATE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
G1	BOLT THROUGH ANCHOR - THREADED ROD	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 A307 GRADE A OR SAE J429 GRADE 2 UNC	1 ½" DIA.
G2	BOLT THROUGH ANCHOR - WASHER, SQUARE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
G3	BOLT THROUGH ANCHOR - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
H1	ADHESIVE ANCHOR - ADHESIVE	ICC-ES-AC308 5 ½" EMBEDMENT WITH A MIN. STRENGTH OF 1,800 PSI. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	
H2	ADHESIVE ANCHOR - THREADED ROD	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 A307 GRADE A / SAE J429 GRADE 2 UNC	1 ½" DIA.
H3	ADHESIVE ANCHOR - WASHER, SQUARE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
H4	ADHESIVE ANCHOR - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
J1	ASPHALT ANCHOR PIN - ROD	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	1 ½" DIA.
J2	ASPHALT ANCHOR PIN - STOP PLATE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
K1	THRIE BEAM RAIL	AASHTO M180 CLASS A TYPE 2 APPROVED PRODUCER	12 GAUGE
L1	THRIE BEAM RAIL - TERMINAL	AASHTO M180 CLASS A TYPE 2 APPROVED PRODUCER	12 GAUGE

PART	DESCRIPTION	MATERIALS SPECIFICATIONS	NOTES
M1	SPLICE BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GAL. TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 UNC AASHTO M180 HEAD ASTM A307 GRADE B OR SAE J429 GRADE 2 OR ASTM F1554 GRADE 36	¾" DIA.
M2	SPLICE BOLT - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
N1	THRIE BEAM RAIL TERMINAL - MECHANICAL ANCHOR	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	¾" DIA. LENGTH 6"
N2	THRIE BEAM RAIL TERMINAL - WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1	
N3	THRIE BEAM RAIL TERMINAL MECHANICAL OR ADHESIVE ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS: ULTIMATE TENSILE LOAD 17.9 KIPS AND ULTIMATE SHEAR LOAD 21.96 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	
P1	THRIE BEAM RAIL CONNECTION 1-BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	¾" DIA.
P2	THRIE BEAM RAIL CONNECTION 1-WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GAL. TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1	
P3	THRIE BEAM RAIL CONNETION 1- MECHANICAL OR ADHESIVE ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS: ULTIMATE TENSILE LOAD 9.48 KIPS AND ULTIMATE SHEAR LOAD 10.48 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	
Q1	BLOCK WOOD	SEE STANDARD SPEC. 614	
R1	CAP - BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	¾" DIA.
R2	CAP - BOLT - WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GAL. TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1	
R3	CAP - BOLT - MECHANICAL ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS ULTIMATE TENSILE LOAD 12.14 KIPS AND ULTIMATE SHEAR LOAD 17.5 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	12 GAUGE
S1	CAP 42-INCH TOP PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S2	CAP 42-INCH END PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S3	CAP 42-INCH SIDE PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S4	CAP 42-INCH GUSSET 1	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S5	CAP 42-INCH GUSSET 2	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S6	CAP 42-INCH GUSSET 3	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S7	CAP 42-INCH GUSSET 4	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE

6

6

SDD14B07 - 16m


SDD14B07 - 16m

**MIDWEST GUARDRAIL  
SYSTEM (MGS)  
TYPE 2 TERMINAL**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

**GENERAL NOTES**


- ① W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POSTS WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS. APPROVED PLASTIC BLOCKOUT DESIGNS MAY VARY FROM THIS TYPICAL DETAIL WHEN USED IN CONJUNCTION WITH STEEL POSTS. DO NOT MIX STEEL POSTS AND WOOD POSTS IN A SINGLE INSTALLATION.
  - ② USE STRUCTURAL STEEL POSTS CONFORMING TO ASTM A 36. GALVANIZED POSTS ACCORDING TO AASHTO M 111. EITHER SET THE POSTS IN DRILLED HOLES OR DRIVE TO GRADE. REMOVE MUSHROOMING CAUSED BY DRIVING AND REPAIR DAMAGED SPELTER COATING ON GALVANIZED POSTS.
  - ③ INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
  - ④ USE EITHER WOOD OR APPROVED PLASTIC BLOCKOUTS ON WOOD POSTS.
  - ⑤ IF THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING, W BEAM (LHW).
  - ⑥ IF ROCK IS ENCOUNTERED DURING EXCAVATION, THE ENGINEER MAY APPROVE USING A 12 INCH DIAMETER POST HOLE EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE APPROXIMATELY 2 1/2 INCHES DEEP. CUT THE POSTS TO LENGTH AND PLACE IN THE HOLE. BACKFILL WITH MATERIAL EXCAVATED FROM THE HOLE AND COMPACT ADEQUATELY.
  - ⑦ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- INSTALL BEAM GUARD SECTIONS AND ALL NECESSARY HARDWARE ACCORDING TO THE APPLICABLE PLAN AND CURRENT STANDARD AND SUPPLEMENTAL SPECIFICATIONS. ALL DIMENSIONS ARE SUBJECT TO MANUFACTURER'S TOLERANCES EXCEPT WHERE ALLOWABLE TOLERANCES ARE SHOWN.




**END VIEW SETTING STEEL OR WOOD POST IN ROCK** ⑥




**END VIEW LOCATED ALONG A CURBED ROADWAY**



**END VIEW LOCATED ALONG A ROADWAY SHOULDER STANDARD INSTALLATION**




**END VIEW STEEL POST & NOTCHED PLASTIC BLOCKOUT ALTERNATIVE STANDARD INSTALLATION**




**END VIEW LONGER POST AT HALF POST SPACING W BEAM (LHW)**


**TYPICAL INSTALLATION OF STEEL PLATE BEAM GUARD**




**STEEL POST & HOLE PUNCHING DETAIL (W6 X 9)** ①  
ALL HOLES 3/8" DIAMETER EXCEPT AS NOTED




**WOOD POST (6" X 8") NOMINAL**




**WOOD OR PLASTIC BLOCKOUT FOR WOOD POSTS**



**TYPICAL NOTCHED PLASTIC BLOCKOUT FOR STEEL POSTS** ①




**PLAN VIEW WOOD POST, BLOCKOUT & BEAM**




**PLAN VIEW STEEL POST, NOTCHED PLASTIC BLOCKOUT & BEAM**

**STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION



**FRONT VIEW  
POST SPACING STANDARD INSTALLATION**



**SECTION THRU W BEAM**




**FRONT VIEW  
BEAM SPLICE AT WOOD POST  
AND POST MOUNTING DETAIL**


**GENERAL NOTES**

FURNISH GUARDRAIL DEFLECTORS FROM APPROVED PRODUCTS LIST.


- ⑨ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINA. START REFLECTORS AT POST #9 AND SPACE EVENLY EVERY 100 FEET (MAX.) TO THE END OF GUARDRAIL RUN, USING A MINIMUM OF 3 REFLECTORS.
- ⑫ 8 - 5/8"  $\phi$  X 2" BUTTON HEAD BOLTS WITH OVAL SHOULDERS & RECESS NUTS.
- ⑬ 5/8" DIA. BUTTON HEAD BOLT AND RECESS NUT WITH 5/8" DIA. F844 FLAT WASHER UNDER NUT.



**FRONT VIEW  
POST SPACING FOR LONGER POST  
AT HALF POST SPACING W BEAM (LHW)**




**FRONT VIEW  
BEAM SPLICE AT STEEL POST  
TYPICAL SPLICING DETAILS  
OF STEEL PLATE BEAM GUARD**




**NESTED W BEAM (NW)**  
USE ALL OTHER STANDARD BEAM GUARD DETAILS FOR  
CONSTRUCTING NESTED W BEAM (NW)

\* USE DOUBLE SIDED WHITE GUARDRAIL REFLECTORS ON ROADWAYS WITH BI-DIRECTIONAL TRAFFIC (NO MEDIAN). USE SINGLE SIDED WHITE (RIGHT SIDE) AND SINGLE SIDED YELLOW (LEFT SIDE) ON ROADWAYS WITH MEDIAN SEPARATION.




**4" X 12" GUARDRAIL REFLECTOR DETAIL  
AND TYPICAL INSTALLATION \***



**4" x 12" GUARDRAIL REFLECTOR**


**STEEL PLATE BEAM GUARD,  
CLASS "A",  
INSTALLATION & ELEMENTS**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION



**DETAIL FOR DOUBLE BLOCKS**

THE NUMBER OF DOUBLE BLOCK POSTS WITHIN A BARRIER RUN IS UNLIMITED




**DETAIL FOR TRIPLE BLOCKS**


TRIPLE BLOCK DETAIL IS LIMITED TO ONE LOCATION WITHIN A BEAM GUARD RUN.

NOTES: USE DOUBLE OR TRIPLE BLOCKS WHEN UNDERGROUND OBSTACLES PREVENT THE POST FROM BEING INSTALLED.

DO NOT USE EXTRA BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.




**PLAN VIEW  
BEAM LAPPING DETAIL**




**POST DRIVING FOR CONTINUOUS  
UNDERGROUND OBSTRUCTION**

<b>STEEL PLATE BEAM GUARD, CLASS "A", INSTALLATION &amp; ELEMENTS</b>	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED June 2017	/s/ Rodney Taylor
DATE	ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	



**BEAM GUARD AT SIDEROADS OR DRIVEWAYS**



**BEAM GUARD AT OBSTACLES  
EXIT END - ONE WAY TRAFFIC**

**GENERAL NOTES**


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE PERTINENT STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

W6 X 9 OR W6 X 8.5 STEEL POSTS WITH NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POSTS WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.


THE LOCATIONS AND LENGTHS OF BEAM GUARD ARE SHOWN ELSEWHERE IN THE PLAN.

- ① STEEL THRIE BEAM STRUCTURAL APPROACH (STBSA) - SEE CURRENT SDD 14B20.
- ② USE AN APPROVED END TREATMENT FOR THE TRAFFIC APPROACH SIDE OF BRIDGE/OBSTACLES. USE TYPE 2 ANCHORAGE ONLY AT THE DOWNSTREAM ENDS OF BEAM GUARD LOCATED ALONG ROADWAYS WITH ONE WAY TRAFFIC.

MINIMUM LATERAL DISTANCE FROM FACE OF BEAM GUARD TO FIXED OBJECT	POST SPACING
3'-6"	3' - 1/2"
4'-6"	6' - 3"



**BEAM GUARD AT FULL WIDTH BRIDGES**




**BEAM GUARD AT OBSTACLES - TWO WAY TRAFFIC**

(RAIL TO OBSTACLE CLEARANCE 3'-6" TO 4'-6")

**TABLE 1  
FLARE RATES FOR BEAM  
GUARD AT NARROW BRIDGES**

POSTED SPEED (MPH)	FLARE RATE
25	13:1
30	15:1
35	16:1
40	18:1
45	21:1
50	24:1
55	26:1
65	30:1



**BEAM GUARD AT NARROW BRIDGES  
(FLARED TO SHOULDER EDGE, THEN PARALLEL TO ROADWAY)**

**STEEL PLATE BEAM GUARD  
CLASS "A"  
AT BRIDGES, OBSTACLES  
AND SIDEROADS/DRIVEWAYS**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
8-21-07 /s/ Jerry H. Zogg  
DATE ROADWAY STANDARDS DEVELOPMENT  
ENGINEER  
FHWA









PLATE WASHER DETAIL

GENERAL NOTES

- BOLT THE THRIE BEAM TO ALL POSTS AND BLOCKOUTS, DRILL OR PUNCH BOLT HOLES IN THE BEAM IF THE POST SPACING IS LESS THAN 6'-3".
- DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.
- IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B15 FOR MORE DETAILS.
- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② MINIMUM EMBEDMENT SHALL BE 4'-0". WHERE EXISTING CONDITIONS DO NOT PERMIT THE APPROPRIATE EARTHWORK SHOWN ON THE PLAN TYPICAL SECTIONS OR DETAILS, THE ENGINEER MAY ALLOW THE REDUCTION OR ELIMINATION OF THE 2 FOOT DISTANCE TO THE HINGE POINT. OTHERWISE BUILD AS THE PLAN SHOWS OR AS THE ENGINEER DIRECTS. IF THE 2 FOOT DISTANCE TO THE HINGE POINT IS REDUCED OR ELIMINATED, INCREASE THE POST EMBEDMENT DEPTH TO 4'-6" OR MORE.
- ③ POST BOLTS ARE 5/8" DIAMETER ASTM A307 BUTTON HEAD BOLT. A POST BOLT REQUIRES A 5/8" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX AND A 5/8" DIAMETER F844 FLAT WASHER. LENGTH OF POST BOLT MAY VARY.
- ④ ALL WOOD POSTS MUST BE 6" X 8" AND AT LEAST 7'-0" LONG.




TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE




THRIE BEAM TERMINAL CONNECTOR

THRIE BEAM SPLICE




SECTION THRU THRIE BEAM RAIL ELEMENT



SECTION A-A

<b>STEEL THRIE BEAM STRUCTURE APPROACH</b>	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 8/31/2012 DATE	/s/ Jerry H. Zogg ROADWAY STANDARDS DEVELOPMENT ENGINEER
FHWA	

① ② 7/8" DIA. HEX HEAD CAP SCREWS INTO  
 THREADED INSERTS (FURNISHED WITH THE BRIDGE)  
 WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER  
 7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED  
 1" DIA. HOLES DRILLED THRU PARAPET (5 REQ'D.)



FRONT VIEW

SECTION B-B


**THRIE BEAM CONNECTION TO BRIDGE  
 PARAPET WITH SQUARE ENDS**

**GENERAL NOTES**

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

BOLTS, NUTS AND WASHERS SHALL CONFORM TO ASTM A325, A449 AND GALVANIZED PER STANDARD SPECIFICATIONS 614.



- ① DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ② BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM TERMINAL CONNECTOR. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/8" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ③ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ④ W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POST WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.  
 DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.



① ② 7/8" DIA. HEX HEAD CAP SCREWS INTO THREADED INSERTS (FURNISHED WITH THE BRIDGE)  
 WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER 7/8" DIA. H.S. HEX BOLT AND  
 WASHERS REQUIRED  
 1" DIA. HOLES DRILLED THRU PARAPET (5 REQ'D.)

FRONT VIEW

**W BEAM TRANSITION AND CONNECTION TO  
 BRIDGE PARAPETS WITH SQUARE ENDS  
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)**



SECTION C-C

**STEEL THRIE BEAM STRUCTURE  
 APPROACH, CONNECTION TO  
 SQUARE END PARAPETS**

STATE OF WISCONSIN  
 DEPARTMENT OF TRANSPORTATION

APPROVED  
 8/31/2012 DATE /S/ Jerry H. Zogg  
 ROADWAY STANDARDS DEVELOPMENT  
 ENGINEER  
 FHWA

**BILL OF MATERIALS**

NOTE NO.	DESCRIPTION
①	WOOD BREAKAWAY TERMINAL POST: 5 1/2" X 7 1/2" X 3'-9"
②	STEEL TUBE TS 8" X 6" X 0.188", 6'-0"
④	WOOD BREAKAWAY CRT POST: 6" X 8" X 6'-0"
⑤	WOOD OFFSET BLOCKS: 6' X 8" X 1'-2"
⑥	PIPE SLEEVE: 2" X 5 1/2" STANDARD PIPE
⑦	BEARING PLATE
⑧	BCT CABLE ASSEMBLY
⑨	CABLE ANCHOR BOX
⑩	STRUT & YOKE
⑪	STEEL PLATE BEAM, END PANEL 12 GA.
⑫	STEEL PLATE BEAM: 12 GA. 13'-6 1/2"
⑬	IMPACT HEAD
⑭	0.040" ALUMINUM SHEET WITH REFLECTIVE SHEETING TYPE F PER SECTION 637 OF THE STANDARD SPECIFICATIONS








**GENERAL NOTES**

FOLLOW MANUFACTURE'S BOLTING RECOMMENDATIONS.

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE (HPL), AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
- (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED.
- (D) THE TOP OF THE STEEL TUBE ON POSTS 1 AND 2 SHALL NOT BE MORE THAN 3" ABOVE THE FINISH GROUND ELEVATION.
- (E) THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST 3 THROUGH 8 SHALL BE 3/4" ABOVE THE FINISHED GROUND LINE.
- (F) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF-TAPPING SCREWS, ONE SCREW PER CORNER.

STEEL POSTS SHALL NOT BE ALLOWED FOR USE WITH ENERGY ABSORBING TERMINALS.  
DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.

\*DO NOT ATTACH BLOCKOUTS TO POSTS 1 AND 2.



**STEEL PLATE BEAM GUARD  
ENERGY ABSORBING TERMINAL**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

6



6

S.D.D. 14 B 24-9a


S.D.D. 14 B 24-9a



⑩ STRUT DETAIL




⑨ CABLE ANCHOR BOX




⑦ STEEL BEARING PLATE

6


6



② 72" STEEL TUBE  
(POSTS NO. 1-2)



① TERMINAL POST




④ CRT POST  
(POSTS NO'S 5-8)


WOOD BREAKAWAY POSTS

GENERAL NOTES

WHEN ROCK IS ENCOUNTERED DURING EXCAVATION, A 12 INCH DIA. POST HOLE EXTENDING 20 INCHES DEEP INTO THE ROCK MAY BE USED IF APPROVED BY THE ENGINEER. GRANULAR MATERIAL SHALL BE PLACED IN THE BOTTOM OF THE HOLE APPROXIMATELY 2 1/2" INCHES DEEP TO PROVIDE DRAINAGE. THE SOIL TUBES SHALL BE FIELD CUT TO LENGTH, PLACED IN THE HOLE AND BACKFILLED WITH ADEQUATELY COMPACTED MATERIAL EXCAVATED FROM THE HOLE.




⑤ WOOD OFFSET BLOCK  
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2



⑭ REFLECTIVE SHEETING DETAILS

TYPE H  
YELLOW REFLECTIVE  
SHEETING 3" X 9".  
SEE STANDARD  
SPECIFICATION 637.



FRONT VIEW      SIDE VIEW


E.A.T. MARKER POST

E.A.T. MARKER  
POST (YELLOW)  
SEE APPROVED  
PRODUCTS LIST


STEEL PLATE BEAM GUARD  
ENERGY ABSORBING TERMINAL

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
June 2017 /S/ Rodney Taylor  
DATE ROADWAY STANDARDS DEVELOPMENT  
FHWA UNIT SUPERVISOR



**WIDTH RESTRICTION SIGNING**



**WIDTH RESTRICTION SIGNING  
2 LANE HIGHWAY**

**LEGEND**

⊙ SIGN ON PERMANENT SUPPORT

**GENERAL NOTES**

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

WIDTH ON SIGN TO BE APPROXIMATELY ONE FOOT LESS THAN AVAILABLE WIDTH.

\* PLACE 500 FEET AFTER THE W20 - 1A AND 500 FEET BEFORE ADDITIONAL SIGNS FOR ROADWAYS WITH A PRE - CONSTRUCTION SPEED LIMIT OF 45 MPH OR MORE. FOR 35-40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25-30 MPH, USE 200 FOOT TYPICAL SPACING.

\*\* SIGN SHALL BE VISIBLE FROM ROADWAY.

\*\*\* ADDITIONAL SIGNS NEEDED IF THERE IS AN ON RAMP BETWEEN SIGNS.



WIDTH ON SIGN TO BE APPROX. 1 - FOOT LESS THAN AVAILABLE WIDTH

**ADVANCED WIDTH RESTRICTION SIGNING**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
February 2020 /S/ Andrew Heidtke  
DATE WORK ZONE ENGINEER  
FHWA

**GENERAL NOTES**

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.




ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.


SIGNS THAT WILL BE IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

IF A "STOP" SIGN MUST BE REMOVED FOR A WORK OPERATION, A TEMPORARY "STOP" SIGN SHALL BE PLACED PRIOR TO THE SIGN REMOVAL, OR A FLAGGER SHALL BE PROVIDED UNTIL THE SIGN IS REESTABLISHED.


- \* OMIT G20-1 SIGNS IF LENGTH OF WORK AREA IS 2 MILES OR LESS
- \*\* PLACE AN ADDITIONAL W20-1A "ROAD WORK AHEAD" SIGN IF WORK AREA WITHIN THE PROJECT IS SEPARATED BY MORE THAN 2 MILES FROM PREVIOUS WORK AREA.

**LEGEND**

-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC
-  WORK AREA



**TYPICAL SIDE ROAD APPROACH  
WARNING SIGN DETAIL**




**TRAFFIC CONTROL, ADVANCE WARNING SIGNS 45MPH OR GREATER**

**TRAFFIC CONTROL, ADVANCE WARNING  
SIGNS 45 MPH OR GREATER TWO-WAY  
UNDIVIDED ROAD OPEN TO TRAFFIC**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
DATE July 2018 /S/ Andrew Heidtke  
WORK ZONE ENGINEER

FHWA



**SITUATION 1**  
 WARRANTING CRITERIA:  
 BRIDGE WIDTH IS AT LEAST 16 FEET BUT LESS THAN 24 FEET.



**SITUATION 2**  
 WARRANTING CRITERIA:  
 1. BRIDGE WIDTH IS AT LEAST 24 FEET AND  
 2. BRIDGE SHOULDER WIDTH IS LESS THAN 6 FEET

**GENERAL NOTES**

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THE DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

LOCATE W5-52 SIGN POST(S) BEHIND GUARDRAIL WHEN PRESENT.

PLACE THE EDGE OF THE W5-52 SIGN IN LINE WITH FACE OF CURB OR PARAPET.

ON BRIDGE ONLY PROJECTS, PLACE 300 FEET OF EDGELINE.

OMIT EDGELINES ON ROADWAYS WITHOUT EXISTING EDGELINES.

① OMIT ON ONE-WAY TRAVELED WAYS.

**LEGEND**

- SIGN ON PERMANENT SUPPORT
- DIRECTION OF TRAFFIC

**DISTANCE TABLE**

POSTED OR 85TH PERCENTILE SPEED	DISTANCE "A"
25	150'
30	200'
35	250'
40	300'
45	400'
50	550'
55	700'

**SIGNING AND MARKING FOR TWO LANE BRIDGES**

STATE OF WISCONSIN  
 DEPARTMENT OF TRANSPORTATION

APPROVED  
 May 2022 /S/ Jeannie Silver  
 DATE STATE SIGNING AND MARKING ENGINEER







**GENERAL NOTES**

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.


- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.

**LEGEND**

-  "T" MARKING
-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC




**TWO WAY TRAFFIC**



**ONE WAY TRAFFIC**

**PERMANENT PAVEMENT MARKING**



6

6

SDD 15C08 - 21a


SDD 15C08 - 21a

**PERMANENT LONGITUDINAL PAVEMENT MARKINGS**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
DATE: May 2022 /S/ Jeannie Silver  
STATEWIDE SIGNING AND MARKING ENGINEER

FHWA




**DRUM**



**42" CONE**

DO NOT USE IN TAPERS  
 1/2 SPACING OF DRUMS




**VERTICAL PANEL**

THE STRIPES SHALL SLOPE DOWNWARD TO THE TRAFFIC SIDE FOR CHANNELIZATION.


**GENERAL NOTES**

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.



**TYPE II BARRICADE**

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD TO THE TRAFFIC SIDE FOR CHANNELIZATION.








**TYPE III BARRICADE**

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

\* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

<b>CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS</b>	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2021 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
<small>FHWA</small>	

**LEGEND**

-  SIGN ON PORTABLE OR PERMANENT SUPPORT
-  TEMPORARY PORTABLE RUMBLE STRIP ARRAY
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLAGGER, EQUIPPED WITH STOP/SLOW PADDLE FASTENED ON SUPPORT STAFF

**GENERAL NOTES**

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP OR QUEUE.

WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.

**FLAGGING**

FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING.

- ① FOR MOVING WORK OPERATIONS, POST ADDITIONAL W20-7A FLAGGER SIGNS AT APPROXIMATELY 3,500' INTERVALS IN THE MOVING WORK OPERATION OR AS APPROVED BY THE ENGINEER.
- ② SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA.

WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED.

**TEMPORARY PORTABLE RUMBLE STRIPS**

UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS.


- ③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSE ACROSS THE LANE AT THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER

ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST.

INSTALL TEMPORARY RUMBLE STRIPS PER MANUFACTURER'S RECOMMENDATIONS.

PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS.

DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS.




**STOP/SLOW PADDLE ON SUPPORT STAFF**

**SIGN AND TEMPORARY RUMBLE STRIP ARRAY SPACING TABLE**

SPEED LIMIT	SPACING "A"
25-30 MPH	200'
35-40 MPH	350'
45-55 MPH	500'



USE OF W03-4 SIGN IS OPTIONAL. WHEN USED, THIS SIGN SHALL BE LOCATED BETWEEN THE W20-7A AND W20-4A SIGNS, USING SPACING "A".



**TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION**








STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
DATE: May 2022 /S/ Andrew Heidtke  
WORK ZONE ENGINEER

SDD 15C12 - 09a

SDD 15C12 - 09a

**GENERAL NOTES**

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL CONE 42-INCH
-  TRAFFIC CONTROL DRUM
-  TEMPORARY PORTABLE RUMBLE STRIP ARRAY
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  **AFAD** AUTOMATED FLAGGER ASSISTANCE DEVICE (AFAD)

**GENERAL NOTES**

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP OR QUEUE.

WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.

**FLAGGING**

IF THE AUTOMATED FLAGGER ASSISTANCE DEVICE (AFAD) STOPS WORKING, FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING.

WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED.

- ① SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA.
- ② IF FLAGGERS ARE PHYSICALLY NEEDED TO FLAG, REPLACE WO3-4 SIGNS WITH W20-7A SIGNS.

**TEMPORARY PORTABLE RUMBLE STRIPS**


UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS.

ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST.

PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS.


DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS.

③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSELY AT THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER.



**SIGN AND TEMPORARY RUMBLE STRIP ARRAY SPACING TABLE**

SPEED LIMIT	SPACING "A"
25-30 MPH	200'
35-40 MPH	350'
45-55 MPH	500'







**TRAFFIC CONTROL, LANE CLOSURE WITH AUTOMATED FLAGGER ASSISTANCE DEVICE**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
May 2022 /S/ Andrew Heidtke  
DATE WORK ZONE ENGINEER

FHWA

**LEGEND**

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  DIRECTION OF TRAFFIC
-  WORK ZONE

**GENERAL NOTES**

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY THE REGIONAL TRAFFIC UNIT.

"WO" SIGN IS THE SAME AS "W" SIGN EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.


CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

W20-1A AND G20-2A SIGNS ARE NOT REQUIRED IF THE WORK AREA IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT. G20-2A SIGNS MAY ALSO BE OMITTED IF DURATION OF WORK IS LESS THAN 7 CONTINUOUS DAYS AND NIGHTS.

6

6



POSTED SPEED LIMIT PRIOR TO WORK STARTING (MPH)	ADVANCE WARNING SIGN SPACING (A) FEET	SHOULDER TAPER L / 3 W, LATERAL OFFSET (FT)						BUFFER SPACE (B) FEET
		3	4	5	6	7	8	
25	200'	10	14	17	21	24	28	55
30	200'	15	20	25	30	35	40	85
35	350'	20	27	34	40	47	54	120
40	350'	26	35	44	53	62	70	170
45	500'	45	59	74	89	104	119	220
50	500'	50	66	83	99	116	132	280
55	500'	54	73	91	109	127	145	335'

OR  
IF TRAFFIC CONTROL DEVICES  
ENCROACH ONTO TRAVELED WAY, USE



**TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
May 2020 /S/ Andrew Heidtke  
DATE STATEWIDE WORK ZONE TRAFFIC SAFETY ENGINEER

FHWA


SDD 15D28 - 04

SDD 15D28 - 04

**LEGEND**

- TYPE III BARRICADE WITH ATTACHED SIGN
- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TRAFFIC CONTROL DRUM
- FLAGS, 16" X 16" MIN. (ORANGE)
- REMOVING PAVEMENT MARKING
- DIRECTION OF TRAFFIC
- ASPHALTIC PAVEMENT WIDENING
- CONCRETE BARRIER TEMPORARY PRECAST
- TEMPORARY SIGNAL. SEE SDD 09G02 FOR EXACT PLACEMENT


WIDTH ON SIGN TO BE APPROX. 1-FOOT LESS THAN AVAILABLE WIDTH. (OMIT IF AVAILABLE WIDTH IS MORE THAN 16 FEET)



TEMPORARY PAVEMENT MARKING LINE, 4 INCH WHITE (STOPLINE TO STOPLINE). REMOVE EXISTING EDGELINE AND OFFSET THE TEMPORARY EDGELINE IF THE DISTANCE FROM THE EDGELINE TO CONCRETE BARRIER WALL IS LESS THAN 9 FEET.

**GENERAL NOTES**

- THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.
- THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE..
- THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.
- ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.
- "WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.
- ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.
- REMOVE PAVEMENT MARKING AND PLACE TEMPORARY PAVEMENT MARKING LINES IF THE CLOSURE IS TO BE IN PLACE FOR 4 OR MORE CONTINUOUS DAYS AND NIGHTS.
- ① 500 FOOT SPACING SHOWN IS FOR ROADWAYS WITH A PRE-CONSTRUCTION REGULATORY SPEED LIMIT OF 45 MPH OR MORE. FOR 35 - 40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25 - 30 MPH, USE 200 FOOT TYPICAL SPACING.
  - ② USE 300 FOOT SPACING IF THE PRE - CONSTRUCTION REGULATORY SPEED IS 35 MPH OR LESS.
  - ③ DIMENSION DETERMINED BY CBTP TAPER FROM EDGE LINE TO TANGENT SECTION OF THE ROAD.
  - ④ TEMPORARY PAVEMENT MARKING LINE, 18 INCH WHITE STOP LINE.
  - ⑤ 700 FOOT TEMPORARY PAVEMENT MARKING LINE, 4 INCH DOUBLE YELLOW . WHEN THE DISTANCE FOR THE PRECEDING NO - PASSING ZONE IS LESS THAN THE MINIMUM DISTANCE BETWEEN ZONES AS INDICATED IN THE SPECIFICATIONS, THE TWO ZONES SHALL BE CONNECTED.
  - ⑥ SEE SDD 15C02 - SHEET "F" FOR ADVANCED WIDTH RESTRICTION SIGNING.



IF DRUMS ARE USED INSTEAD OF CONCRETE BARRIER WALL  
SEE DETAIL ABOVE


**TRAFFIC CONTROL,  
ONE LANE ROAD  
WITH TEMPORARY SIGNALS**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION




APPROVED  
February 2022 /S/ Andrew Heidtke  
DATE WORK ZONE ENGINEER

FHWA

URBAN AREA



RURAL AREA (See Note 2)



GENERAL NOTES

1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
2. If signs are mounted on or behind barrier wall, see A4-10 sign plate.  
The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).
3. For expressways and freeways, mounting height is 7'- 3" (±) or 6'-3" (±) depending upon existence of a sub-sign.
4. Minimum mounting height for signs mounted on traffic signal poles is 5'- 3" (±).
5. Offset distance shall be consistent with existing signs or consistent throughout length of project.
6. The (±) tolerance for mounting height is 3 inches.
7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the Engineer.

POST EMBEDMENT DEPTH

Area of Sign Installation ( Sq. Ft. )	D ( Min )
20 or Less	4'
Greater than 20	5'

\* \* The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.


\* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

TYPICAL INSTALLATION OF PERMANENT TYPE II SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer


DATE 5/13/2020 PLATE NO. A4-3.22



**ELEVATION VIEW**


**DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT**

- NOTES:**
1. ALL MATERIAL TO BE APPROVED BY ENGINEER PRIOR TO INSTALLATION
  2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
  3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.



**ELEVATION VIEW**

**DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT**



**PLAN VIEW**

**FOR NEW CONCRETE/ ASPHALT INSTALLATIONS**

**SIGN POST  
BOX-OUTS  
A4-3B**

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 1/27/14 PLATE NO. A4-3B.1

7


7





GENERAL NOTES

1. For 3 or 4 post installations, individual post spacing shall be greater than 3'-6".
2. See tables below for required number of posts.
3. For expressways and freeways, mounting height is 7'-3" (±) or 6'-3" (±) depending upon existence of sub-sign.
4. The (±) tolerance for mounting height is 3 inches.
5. J-Assemblies are considered to be one sign for mounting height.
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the engineer.
8. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).


URBAN AREA




RURAL AREA (See Note 3)



2' Min - 4' Max (See Note 6)



48" DIAMOND WARNING SIGN



48" DIAMOND WARNING SIGN

\* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

\*\* The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

\*\*\* See A4-3 sign plate for signs 4' or less in width and less than 20 S.F. in area.

SIGN SHAPE OTHER THAN DIAMOND (TWO POSTS REQUIRED)	
L	E
Greater than 48" Less than 60"	12"
60" to 108"	L/5

\*\*\*


SIGN SHAPE OTHER THAN DIAMOND (THREE POSTS REQUIRED)	
L	E
Greater than 108" to 144"	12"

POST EMBEDMENT DEPTH

Area of Sign Installation ( Sq. Ft. )	D ( Min )
20 or Less	4'
Greater than 20	5'

TYPICAL INSTALLATION OF TYPE II SIGNS ON MULTIPLE POSTS

WISCONSIN DEPT OF TRANSPORTATION  
 APPROVED *Matthew R. Rauch*  
 For State Traffic Engineer  
 DATE 8/21/17 PLATE NO. A4-4.15



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :

- Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3.

Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.


- STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)
- MACHINE BOLTS -  $\frac{5}{16}$ " X 1-3/4" Length w/ lock nuts
- WOOD POSTS (4" x 6")
- LAG SCREWS -  $\frac{3}{8}$ " X 3" (NO STRINGERS ON BACK OF SIGN)  
 $\frac{3}{8}$ " X 4" (STRINGERS ON BACK OF SIGN)
- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS -  $\frac{3}{8}$ " X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)  
 $\frac{3}{8}$ " X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)
- RIVETS -  $\frac{9}{32}$ " (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL  
 O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH
- WASHERS (ALL POSTS) -
- 1-1/4" O.D. X  $\frac{3}{8}$ " I.D. X  $\frac{1}{16}$ " STEEL
- 1-1/4" O.D. X  $\frac{3}{8}$ " I.D. X .080 NYLON

\* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.


ATTACHMENT OF SIGNS TO POSTS	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R Rauch</i> For State Traffic Engineer
DATE 4/1/2020	PLATE NO. A4-8.9

**TELESCOPIC TUBING ANCHORS  
TWO PIECE SYSTEM**


**2 1/4" SQUARE  
12 GAUGE  
PERFORATED  
GALVANIZED FINISH**





**2 1/2" SQUARE  
12 GAUGE  
OMNI-DIRECTIONAL  
PERFORATED  
SOIL STABILIZING SLEEVE  
GALVANIZED FINISH**



**DETAIL OF TUBULAR STEEL SIGN POST  
(IN POURED CONCRETE OR ASPHALT)**



**DETAIL OF TUBULAR STEEL SIGN POST  
(IN LOCATIONS OTHER THAN POURED CONCRETE OR ASPHALT)**



Area of Sign Installation (Sq. Ft.)	Number of Required Posts
9 or less	1
Greater than 9 less than or equal to 18	2
Greater than 18 less than or equal to 27	3

Signs wider than 3 feet or larger than 9 sq. ft shall be mounted on multiple posts (see above table).

**TUBULAR STEEL  
SIGN POST  
A4-9**

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 2/05/15 PLATE NO. A4-9.9



PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E



GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two 1½" diameter holes drilled perpendicular to the roadway centerline.


7

7

<b>4 X 6 WOOD POST MODIFICATIONS</b>	
<i>WISCONSIN DEPT OF TRANSPORTATION</i>	
APPROVED	<i>Chester J Spang</i> for State Traffic Engineer
DATE <u>3/27/97</u>	PLATE NO. <u>A4-11.2</u>

NOTES

1. Sign is Type II - Type F Reflective
2. Color:  
Background - Orange  
Message - Black
3. Message Series - D
4. Substitute appropriate numeral and adjust spacing to achieve proper balance.



G20-57

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2																											
3	72	36	1 1/8	1/2	5/8	6	5	4	15 5/8	1 5/8	5	9 1/4	21 1/4	3 1/2	1 1/2	23 1/4		29 7/8	1 3/4	3 1/4	28 1/2						18.0
4	96	48	2 1/4	3/4	1	8	6 1/2	5 1/2	20 5/8	2 1/4	6	12 1/4	28 1/4	4 3/8	1 5/8	31		39 1/4	2	4	37 7/8						32.0
5																											

STANDARD SIGN  
G20-57

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R Rauch*  
For State Traffic Engineer

DATE 1/22/19 PLATE NO. G20-57.3

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Red  
Message - White
3. Message Series - C



7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	30				5/8	10	12 1/2	45°		12 3/4																	5.18
2S	30				5/8	10	12 1/2	45°		12 3/4																	5.18
2M	36				3/4	12	15	45°		15 3/8																	7.46
3	36				3/4	12	15	45°		15 3/8																	7.46
4	48				1	16	20	45°		20 1/2																	13.25
5	48				1	16	20	45°		20 1/2																	13.25
6	18				3/8	6	7 3/4	45°		7 3/4																	1.86
7	12				1/4	4	5	45°		5 1/8																	0.78


PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**

STANDARD SIGN  
R1-1

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 11/12/15 PLATE NO. R1-1.13



R2-1

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - White  
Message - Black
3. Message Series - E
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Substitute appropriate numerals and optically adjust spacing to achieve proper balance.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	18	24	1 1/8	3/8	1/2	3	8	3	2	2	3	7 1/4	5 1/2														3.0
2S	24	30	1 1/8	3/8	1/2	4	10	3	2 1/4	3 3/8	3 3/8	9 5/8	7 3/8														5.0
2M	30	36	1 3/8	1/2	5/8	5	12	5	2 1/2	2 1/2	4	12	9 1/4														7.5
3	36	48	1 3/8	1/2	5/8	6	14	6	5	5	6	14 3/8	11														12.0
4	36	48	1 3/8	1/2	5/8	6	14	6	5	5	6	14 3/8	11														12.0
5	48	60	2 1/4	3/4	1	8	20	6	4 1/2	6 3/4	6 3/4	19 1/4	14 5/8														20.0


STANDARD SIGN  
R2-1

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
For State Traffic Engineer


DATE 5/26/10 PLATE NO. R2-1.13

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: \_\_\_\_\_ E



NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - White  
Message - See note 4
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. Border & Arrow are non reflective black, the circle with diagonal bar is reflective red.



ARROW DETAIL

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	24		1 1/8	3/8	1/2	10 1/2	4	7 1/2	2	1 1/2	2 1/2	45	8 1/2	5	6	1/2	12										4.0
2S	24		1 1/8	3/8	1/2	10 1/2	4	7 1/2	2	1 1/2	2 1/2	45°	8 1/2	5	6	1/2	12										4.0
2M	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45	12 3/4	7 1/2	9	3/4	18										9.0
3	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45	12 3/4	7 1/2	9	3/4	18										9.0
4	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4	18										9.0
5	48		2 1/4	3/4	1	21	8	15	4	3	5	45°	17	10	12	1	24										16.0

STANDARD SIGN  
R3-1

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 12/08/10 PLATE NO. R3-1.5

PROJECT NO:


HWY:

COUNTY:

SHEET NO:

E






R3-2

**NOTES**

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - White  
Message - See note 4
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. Border & Arrow are non reflective black, the circle with diagonal bar is reflective red.



ARROW DETAIL

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. Ft.
1	24		1 1/8	3/8	1/2	10 1/2	4	7 1/2	2	1 1/2	2 1/2	45°	8 1/2	5	6	1/2											4.0
2S	24		1 1/8	3/8	1/2	10 1/2	4	7 1/2	2	1 1/2	2 1/2	45°	8 1/2	5	6	1/2											4.0
2M	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4											9.0
3	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4											9.0
4	36		1 5/8	5/8	3/4	15 3/4	6	11 1/4	3	2 1/4	3 3/4	45°	12 3/4	7 1/2	9	3/4											9.0
5	48		2 1/4	3/4	1	21	8	15	4	3	5	45°	17	10	12	1											16.0

**STANDARD SIGN**  
**R3-2**

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*  
For State Traffic Engineer

DATE 12/08/10 PLATE NO. R3-2.10

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: \_\_\_\_\_ E

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - White  
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. R3-53L same as R3-53R except LEFT is substituted for RIGHT.



R3-53R

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	24	30	1 1/8	3/8	1/2	5	8 3/4	9 1/2	7 3/4	8	4	3 1/4	4 1/2	7 1/2													5.0
2M	24	30	1 1/8	3/8	1/2	5	8 3/4	9 1/2	7 3/4	8	4	3 1/4	4 1/2	7 1/2													5.0
3	24	30	1 1/8	3/8	1/2	5	8 3/4	9 1/2	7 3/4	8	4	3 1/4	4 1/2	7 1/2													5.0
4																											
5																											


STANDARD SIGN  
R3-53

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
For State Traffic Engineer

DATE 3/24/2011 PLATE NO. R3-53.8


PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: \_\_\_\_\_ E



R10-6

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - White  
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



Arrow Detail

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	O	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	24	36	1 1/8	3/8	1/2	5	3	7	2 1/2	4	8	8 3/8	9	1	3	5	5 5/8	6 1/4	60°	5 1/4	2 1/4	7 1/8	1/2	3/8	1 3/8	6.0	
2M	24	36	1 1/8	3/8	1/2	5	3	7	2 1/2	4	8	8 3/8	9	1	3	5	5 5/8	6 1/4	60°	5 1/4	2 1/4	7 1/8	1/2	3/8	1 3/8	6.0	
3																											
4																											
5																											

**STANDARD SIGN**  
R10-6

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 4/5/11 PLATE NO. R10-6.6

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: \_\_\_\_\_ E

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - White  
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



R11-2B

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
2M	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
3	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
4	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
5	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0



**STANDARD SIGN**  
R11-2B

*WISCONSIN DEPT OF TRANSPORTATION*

APPROVED *Matthew R. Rauch*  
For State Traffic Engineer

DATE 4/1/11 PLATE NO. R11-2B.2

PROJECT NO: \_\_\_\_\_ SHEET NO: \_\_\_\_\_ E



NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Yellow  
Message - Black
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. Alternate colors of stripes as shown.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	12	36				4 3/8	3 1/2	5 5/8	45°	4	4																3.0
2M	12	36				4 3/8	3 1/2	5 5/8	45°	4	4																3.0
3	18	54				6	5 1/2	8 1/2	45°	6	6 9/16																6.75
4																											
5																											


STANDARD SIGN  
W5-52L & W5-52R

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 5/29/12 PLATE NO. W5-52.9


PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: \_\_\_\_\_ E



W12-52

**NOTES**

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Orange  
Message - Black
3. Message Series - See note 5
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. The top line is series E, the numerals are series C, and the bottom line is series D.
6. Substitute appropriate numerals and adjust spacing as required.



**ARROW DETAIL**

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48		2 1/4	3/4	1	6	12	11 3/8	9 5/8	11 1/2	16	13	12	15 5/8	8	9 1/4	1 1/4	10 5/8									16.0
2M	48		2 1/4	3/4	1	6	12	11 3/8	9 5/8	11 1/2	16	13	12	15 5/8	8	9 1/4	1 1/4	10 5/8									16.0
3																											
4																											
5																											

**STANDARD SIGN**  
W12-52


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 3/16/11 PLATE NO. W12-52.7

NOTES

1. Sign is Type II - Type F Reflective
2. Color:  
Background - Yellow  
Message - Black
3. Message Series - Lines 1 and 2 are Series D.  
Line 3 is series C.
4. Corners and borders shall be rounded on all base materials for this sign.



7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	36	2 1/4	5/8	7/8	5	2	8 1/2	3	8	26 3/4	12 3/4															5.56
2M																											
3																											
4																											
5																											







STANDARD SIGN  
W14-3

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 3/21/17 PLATE NO. W14-3.10

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**



**NOTES**

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Orange  
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	5	2 3/8	6	3 3/4	10 3/8	2 3/8	8	13 1/2	7	8 7/8	9	1 3/8	1 7/8	5 5/8	10 1/8	2 1/2	1 1/8	4 1/2	3 1/2	10 3/4	1 3/4	9.0
2S	48		2 1/4	3/4	1	7	3 1/8	8	5 1/4	14 5/8	3 1/4	10 5/8	17 3/4	9 3/4	12 5/8	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	14 3/8	2 3/8	16.0
2M	48		2 1/4	3/4	1	7	3 1/8	8	5 1/4	14 5/8	3 1/4	10 5/8	17 3/4	9 3/4	12 5/8	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	14 3/8	2 3/8	16.0
3	48		2 1/4	3/4	1	7	3 1/8	8	5 1/4	14 5/8	3 1/4	10 5/8	17 3/4	9 3/4	12 5/8	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	14 3/8	2 3/8	16.0
4	48		2 1/4	3/4	1	7	3 1/8	8	5 1/4	14 5/8	3 1/4	10 5/8	17 3/4	9 3/4	12 5/8	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	14 3/8	2 3/8	16.0
5	48		2 1/4	3/4	1	7	3 1/8	8	5 1/4	14 5/8	3 1/4	10 5/8	17 3/4	9 3/4	12 5/8	12	1 7/8	2 5/8	7 1/2	13 1/2	3 3/8	1 1/2	6	4 5/8	14 3/8	2 3/8	16.0


STANDARD SIGN  
W20-4A, B, C, D, F & G

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 3/18/11 PLATE NO. W20-4.9





NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Orange  
Message - Black
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. W01-4L is the same as W01-4R except the arrow is reversed along the vertical centerline.

7

7

W01-4R

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	5 1/4	4	12 3/8	7 7/8	16 7/8	10 1/2	1 5/8	6	4 1/2	1	1/2	2 1/4	7 1/2									9.0
2S	48		2 1/4	3/4	1	7	5 1/4	16 1/2	10 1/2	22 1/2	14	2 1/4	8	6	1 1/4	5/8	3	10									16.0
2M	48		2 1/4	3/4	1	7	5 1/4	16 1/2	10 1/2	22 1/2	14	2 1/4	8	6	1 1/4	5/8	3	10									16.0
3	48		2 1/4	3/4	1	7	5 1/4	16 1/2	10 1/2	22 1/2	14	2 1/4	8	6	1 1/4	5/8	3	10									16.0
4	48		2 1/4	3/4	1	7	5 1/4	16 1/2	10 1/2	22 1/2	14	2 1/4	8	6	1 1/4	5/8	3	10									16.0
5	48		2 1/4	3/4	1	7	5 1/4	16 1/2	10 1/2	22 1/2	14	2 1/4	8	6	1 1/4	5/8	3	10									16.0

STANDARD SIGN  
W01-4

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 11/18/13 PLATE NO. W01-4.1

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Orange  
Message - Black
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



W01-6

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	24	1 3/8	1/2	5/8		12	13 1/4	1	7 1/2	6 1/2	3 1/4	19 1/2	39													8.0
2M	48	24	1 3/8	1/2	5/8		12	13 1/4	1	7 1/2	6 1/2	3 1/4	19 1/2	39													8.0
3	60	30	1 3/8	1/2	5/8		15	16 1/4	1 1/4	9 1/4	8	4	24 3/8	48 3/4													12.5
4	60	30	1 3/8	1/2	5/8		15	16 1/4	1 1/4	9 1/4	8	4	24 3/8	48 3/4													12.5
5	60	30	1 3/8	1/2	5/8		15	16 1/4	1 1/4	9 1/4	8	4	24 3/8	48 3/4													12.5


**STANDARD SIGN**  
**W01-6**

*WISCONSIN DEPT OF TRANSPORTATION*

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 11/18/13 PLATE NO. W01-6.1

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**



NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Orange  
Message - See Note 4
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. Symbol and border are non-reflective black.  
Top circle - Type H ReflectORIZED Red  
Center circle - Same as background  
Bottom circle - Type H ReflectORIZED Green

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4		10	15 3/4	5 3/4	4 1/4																	9.0
2S	48		2 1/4	3/4	1		12 1/2	20	7 1/2	5																	16.0
2M	48		2 1/4	3/4	1		12 1/2	20	7 1/2	5																	16.0
3	48		2 1/4	3/4	1		12 1/2	20	7 1/2	5																	16.0
4	48		2 1/4	3/4	1		12 1/2	20	7 1/2	5																	16.0
5	48		2 1/4	3/4	1		12 1/2	20	7 1/2	5																	16.0


**STANDARD SIGN**  
**W03-3**

*WISCONSIN DEPT OF TRANSPORTATION*

APPROVED *Matthew R. Rauch*  
for State Traffic Engineer

DATE 11/20/13 PLATE NO. W03-3.1


PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**



NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color: \*  
Background - ORANGE\*  
Message - BLACK
3. Message Series - C for numbers Series E for wording
4. Substitute appropriate numerals and optically adjust spacing to achieve proper balance

\*Speed Limit Sign shall have a White Background



ARROW DETAIL


SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	O	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	14 1/2	9 1/2	11 1/2	5/8	24	2	3	1	12	7 1/8	1 1/2	3/8	5 3/4	7 1/4	7 1/8	9	6	19 1/4	3/8	9 3/4	1 5/8	9.0
2S	48		2 1/4	3/4	1	19 1/4	10 3/4	17 3/8	7/8	30	2 1/4	4	1 1/4	15	10	1 5/8	1/2	8	9 1/4	9 3/8	12	8	25 5/8	3/8	13	2	16.0
2M	48		2 1/4	3/4	1	19 1/4	10 3/4	17 3/8	7/8	30	2 1/4	4	1 1/4	15	10	1 5/8	1/2	8	9 1/4	9 3/8	12	8	25 5/8	3/8	13	2	16.0
3	48		2 1/4	3/4	1	19 1/4	10 3/4	17 3/8	7/8	30	2 1/4	4	1 1/4	15	10	1 5/8	1/2	8	9 1/4	9 3/8	12	8	25 5/8	3/8	13	2	16.0
4	48		2 1/4	3/4	1	19 1/4	10 3/4	17 3/8	7/8	30	2 1/4	4	1 1/4	15	10	1 5/8	1/2	8	9 1/4	9 3/8	12	8	25 5/8	3/8	13	2	16.0
5	48		2 1/4	3/4	1	19 1/4	10 3/4	17 3/8	7/8	30	2 1/4	4	1 1/4	15	10	1 5/8	1/2	8	9 1/4	9 3/8	12	8	25 5/8	3/8	13	2	16.0

**STANDARD SIGN**  
**W03-5**


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*  
For State Traffic Engineer

DATE 11/20/13 PLATE NO. W03-5.1



W05-52L



W05-52R

**NOTES**

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:  
Background - Orange  
Message - Black
3. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
4. Alternate colors of stripes as shown.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	12	36				4 3/8	3 1/2	5 5/8	45°	4	4																3.0
2M	12	36				4 3/8	3 1/2	5 5/8	45°	4	4																3.0
3	18	54				6	5 1/2	8 1/2	45°	6	6 9/16																6.75
4																											
5																											

**STANDARD SIGN**  
W05-52L & W05-52R

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Raub*  
for State Traffic Engineer

DATE 11/20/13 PLATE NO. W05-52.1

PROJECT NO: \_\_\_\_\_ HWY: \_\_\_\_\_ COUNTY: \_\_\_\_\_ SHEET NO: **E**

**DESIGN DATA**

**LIVE LOAD:**  
 DESIGN LOADING: HL-93  
 INVENTORY RATING FACTOR: RF = 1.10  
 OPERATING RATING FACTOR: RF = 1.43  
 WISCONSIN STANDARD PERMIT VEHICLE (WIS.-SPV): 250(KIPS)

STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 POUNDS PER SQUARE FOOT.

**MATERIAL PROPERTIES:**  
 CONCRETE MASONRY:  
 SUPERSTRUCTURE  $f'c = 4,000$  P.S.I.  
 ALL OTHER  $f'c = 3,500$  P.S.I.

BAR STEEL REINFORCEMENT:  
 GRADE 60  $f_y = 60,000$  P.S.I.

36" PRESTRESSED GIRDERS:  
 CONCRETE MASONRY  $f'c = 8,000$  P.S.I.  
 STRANDS: 0.6" DIA. WITH ULTIMATE TENSILE STRENGTH OF 270,000 P.S.I.

**FOUNDATION DATA**

ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 PILING, SEATED IN HOLES PRE-BORED TO AN ELEVATION OF 878.5. PILE DRIVING IS NOT REQUIRED.

THE FACTORED AXIAL RESISTANCE OF THE PILES IN COMPRESSION, USED FOR DESIGN, IS 180 TONS MULTIPLIED BY A RESISTANCE FACTOR OF 0.5. ESTIMATED PILE LENGTH 20 FEET LONG, AT BOTH ABUTMENTS.

**HYDRAULIC DATA**

**100 YEAR FREQUENCY**  
 $Q_{100} = 1770$  C.F.S.  
 $VEL_{100} = 5.8$  F.P.S.  
 $HW_{100} = EL. 898.6$   
 WATERWAY AREA = 306 SQ. FT.  
 DRAINAGE AREA = 26.4 SQ. MI.  
 ROADWAY OVERTOPPING = N/A  
 SCOUR CRITICAL CODE = 5

**2 YEAR FREQUENCY**  
 $Q_2 = 533$  C.F.S.  
 $VEL_2 = 3.4$  F.P.S.  
 $HW_2 = EL. 895.7$


**TRAFFIC VOLUME**

**STH 95**  
 ADT = 2800 (2042)  
 R.D.S. = 50 M.P.H.


Ⓢ INDICATES WING NUMBER

\* PROVIDE FOR THRIE BEAM GUARD RAIL ATTACHMENT. AT UNUSED ANCHOR ASSEMBLIES CAULK HOLES SHUT WITH "100% SILICONE CAULK".

SURFACE DRAIN ANCHORS REQ'D. AT WINGS 3 & 4.




NAME PLATE & BENCH MARK CAP (WHEN SUPPLIED)- FOR LOCATION SEE SHEET "SINGLE SLOPE PARAPET 42SS"





**PLAN**

SINGLE SPAN - 36" PRESTRESSED GIRDER



**STRUCTURE DESIGN CONTACTS:**  
 ALEXANDER CRABTREE (608) 266-3686  
 LAURA SHADEWALD (608) 267-9592



**LIST OF DRAWINGS**


1. GENERAL PLAN
2. CROSS SECTION & QUANTITIES
3. STAGING PLANS
4. SUBSURFACE EXPLORATION
5. WEST ABUTMENT
6. WEST ABUTMENT DETAILS
7. EAST ABUTMENT
8. EAST ABUTMENT DETAILS
9. 36" PRESTRESSED GIRDER DETAILS
10. STEEL DIAPHRAGM
11. SUPERSTRUCTURE DETAILS 1
12. SUPERSTRUCTURE DETAILS 2
13. SINGLE SLOPE PARAPET 42SS

NO.	DATE	REVISION	BY
<p><b>BUREAU OF STRUCTURES</b></p>			
ACCEPTED		DATE	
		10/11/22	
<p><b>STRUCTURE B-27-171</b></p>			
<p>STH 95 OVER E. FORK HALLS CREEK</p>			
COUNTY	JACKSON	TOWN/CITY/VILLAGE	MERRILLAN
DESIGN SPEC.	AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS		
DESIGNED BY	ARC	DRAWN BY	MJH
PLANS CK'D.	ARC	DATE	
<b>GENERAL PLAN</b>			SHEET 1 OF 13


SCALE = 8.00

**GENERAL NOTES**

- DRAWINGS SHALL NOT BE SCALED.
- BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
- THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.
- BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS OTHERWISE NOTED.
- THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES B-27-171" SHALL BE THE EXISTING GROUNDLINE.
- AT THE BACK FACE OF ABUTMENT ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL TYPE A.
- EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.
- THE QUANTITY FOR BACKFILL STRUCTURE IS CALCULATED BASED ON THE DETAIL SHOWN IN THE PLANS.
- ELASTOMERIC BEARING PADS NEED NOT BE INDIVIDUALLY MOLDED PROVIDED THE CUT EDGES ARE SMOOTH AND TRUE.
- PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO THE ENTIRE EXPOSED TOP OF DECK AND TO THE VERTICAL AND HORIZONTAL SURFACES OF THE PAVING NOTCHES AT ABUTMENT DIAPHRAGMS.
- PIGMENTED SURFACE SEALER TO BE APPLIED TO THE FRONT FACE AND THE TOP OF THE PARAPETS, INCLUDING PARAPETS ON ABUTMENT WINGS.
- THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH HEAVY RIPRAP AND GEOTEXTILE TYPE "HR" TO THE EXTENT SHOWN ON SHEET 1 AND THE ABUTMENT DETAILS.
- THE HAUNCH CONCRETE QUANTITY IS BASED ON THE AVERAGE HAUNCH SHOWN ON THE "36-INCH PRESTRESSED GIRDER DETAILS SHEET.



**CROSS SECTION THRU ROADWAY LOOKING EAST**




**ABUTMENT BACKFILL DIAGRAM FOR WINGS PARALLEL TO ROADWAY**


- L = OUT TO OUT OF ABUTMENT, INCLUDING WINGS (FT)
- H = AVERAGE ABUTMENT FILL HEIGHT (FT)
- EF = EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)
- $V_{CF} = (L)(3.0')(H) + (L)(0.5)(1.5H)(H)$
- $V_{CY} = V_{CF}(EF)/27$
- $V_{TON} = V_{CY}(2.0)$

**TOTAL ESTIMATED QUANTITIES**

BID ITEM NUMBER	BID ITEMS	UNIT	SUPER.	WEST ABUT.	EAST ABUT.	TOTALS
203.0260	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS B-27-147	EACH	---	---	---	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGES B-27-171	EACH	---	---	---	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	---	259	259	518
502.0100	CONCRETE MASONRY BRIDGES	CY	122.5	56.9	56.8	236
502.3200	PROTECTIVE SURFACE TREATMENT	SY	304	---	---	304
502.3210	PIGMENTED SURFACE SEALER	SY	108	---	---	108
503.0136	PRESTRESSED GIRDER TYPE I 36-INCH	LF	426	---	---	426
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	---	2,650	2,650	5,300
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	22,330	3,470	3,510	29,310
505.0904	BAR COUPLERS NO. 4	EACH	4	2	2	8
505.0906	BAR COUPLERS NO. 6	EACH	20	18	18	56
506.2605	BEARING PADS ELASTOMERIC NON-LAMINATED	EACH	---	6	6	12
506.4000	STEEL DIAPHRAGMS B-27-171	EACH	5	---	---	5
511.1200	TEMPORARY SHORING B-27-171	SF	---	221	221	442
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	---	13	13	26
550.0020	PRE-BORING ROCK OR CONSOLIDATED MATERIALS	LF	---	123	123	246
550.1100	PILING STEEL HP 10-INCH X 42 LB	LF	---	160	160	320
606.0300	RIPRAP HEAVY	CY	---	140	116	256
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	---	75	75	150
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	4	---	---	4
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	---	37	37	74
645.0120	GEOTEXTILE TYPE HR	SY	---	231	195	426
NON-BID ITEMS						
	FILLER	SIZE	---	---	---	1/2", 3/4"




**PROFILE GRADE LINE - R STH 95**



**TYPICAL SECTION THRU ABUTMENT**


- ▲ BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- PIPE UNDERDRAIN WRAPPED (6 INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
		DRAWN BY	PLANS CK'D.
		MJH	ARC
<b>CROSS SECTION &amp; QUANTITIES</b>			SHEET 2




**STAGE 1A TRAFFIC & REMOVAL**

(LOOKING EAST UPSTATION)



**STAGE 1B CONSTRUCTION & STAGE 2A REMOVAL**

(LOOKING EAST UPSTATION)



**STAGE 2B TRAFFIC & CONSTRUCTION**

(LOOKING EAST UPSTATION)

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY MJH		PLANS CKD. ARC	
STAGING PLANS			SHEET 3




BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
1	9/09/2021	154200	91368
2	9/09/2021	154223	91450
3	9/09/2021	154222	91369
4	9/09/2021	154200	91449


BORINGS COMPLETED BY: AET  
 REPORT COMPLETED BY: WISDOT  
 ALL COORDINATES REFERENCED TO WCCS NAD 83(91) JACKSON COUNTY  
 COORDINATES COLLECTED USING NON-SURVEY GRADE EQUIPMENT



E. FORK  
HALL'S CREEK



STATE PROJECT NUMBER		
<b>7520-00-77</b>		
MATERIAL SYMBOLS		
	ASPHALT	
	CONCRETE	
	SAND	
	BOULDERS OR COBBLES	
	SHALE	
	PEAT	
	GRAVEL	
	BEDROCK (UNKNOWN)	
	IGNEOUS/META	




(1) UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)  
 (2) UNLESS OTHERWISE, SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION  
 ▽ AT TIME OF DRILLING  
 ▽ END OF DRILLING  
 ▽ AFTER DRILLING

ABBREVIATIONS  
 F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.




8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY: TLP/MJH		PLANS CKD. ARC	
<b>SUBSURFACE EXPLORATION</b>			SHEET 4

SCALE =

STEEL TROWEL TOP SURFACE OF ABUTMENT. PLACE MULTIPLE LAYERS OF POLYETHYLENE SHEETS OVER ENTIRE ABUTMENT TOP BEFORE PLACING BEARING PADS. TOTAL THICKNESS OF SHEETS SHALL BE AT LEAST 0.03".



**ELEVATION**  
(LOOKING WEST)




**SECTION THRU BODY**


- ☉ BAR COUPLERS REQUIRED
- ⊙ 4" x 1/2" PREFORMED JOINT FILLER X ABUTMENT LENGTH
- ★ 3/4" CORK FILLER ON VERTICAL BEAM SEAT FACES.
- ⓐ06 ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 STEEL PILING, FIRMLY SEATED IN HOLES PRE-BORED TO AN ELEVATION OF 878.5. PILES ESTIMATED 20'-0" LONG. PILE DRIVING IS NOT REQUIRED. FACTORED AXIAL RESISTANCE, USED FOR DESIGN, IS 180 TONS PER PILE. PILE SPLICE DETAILS ON "EAST ABUTMENT DETAILS" SHEET.
- ⓐ15 PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED. SEE SHIELD DETAILS ON "WEST ABUTMENT DETAILS" SHEET.
- ⓐ17 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- ⓐ19 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.

WING 1

WING 2




**PLAN**




**PILE PLAN**

PROPOSED ABUTMENT OVERLAPS EXISTING ABUT. BODY FOOTING. PRE-BORING MAY NEED TO EXTEND THROUGH EXIST. CONC. FOOTING (TYP. PILES 1&6)


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		PLANS CK'D.	ARC
WEST ABUTMENT		SHEET 5	



**WING 1 ELEVATION**  
LOOKING AT FRONT FACE,  
WING 2 SIMILAR



**A501, A509**




**A403**


**BILL OF BARS** NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COY.	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
A501		47	17'-0"	X		BODY-STIRRUPS
A402		12	2'-3"			PILES - 2 PER BODY PILE
A403		6	28'-0"	X		PILES - 1 PER BODY PILE
A604		11	19'-1"			BODY - HORIZ. - F.F., TOP. & BOT. - STAGE 1
A605		7	3'-4"			BODY - HORIZ. - B.F. - STAGE 1
A906		14	18'-8"	X		BODY - HORIZ. - B.F. - STAGE 1 & 2
A407		20	3'-11"	X		BODY - BTWN. BEAM SEATS - VERT.
A408		8	6'-2"			BODY - BTWN. BEAM SEATS - HORIZ.
A509	X	24	17'-8"	X		WINGS 1 & 2 - STIRRUPS
A410	X	6	5'-7"			WINGS 1 & 2 - VERT. F.F. - ABUT. ENDS
A511	X	14	14'-4"			WINGS 1 & 2 - HORIZ. - F.F. - LOWER WINGS
A812	X	18	14'-0"	X		WINGS 1 & 2 - HORIZ. - B.F. - LOWER WINGS
A413	X	8	7'-9"			WINGS 1 & 2 - HORIZ. - UPPER WINGS
A414	X	18	17'-8"			WINGS 1 & 2 - HORIZ. - UPPER WINGS
A615	X	4	17'-8"			WINGS 1 & 2 - HORIZ. - UPPER WINGS - TOP
A516	X	18	10'-8"	X		WINGS 1 & 2 - VERT. - UPPER WINGS
A517	X	32	12'-6"	X		WINGS 1 & 2 - VERT. - UPPER WINGS
A618		11	19'-1"			BODY - HORIZ. - F.F., TOP. & BOT. - STAGE 2
A619		7	3'-4"			BODY - HORIZ. - B.F. - STAGE 2
A420		2	3'-1"			BODY - BTWN. BEAM SEAT - HORIZ. - STAGE 1
A421		2	3'-1"			BODY - BTWN. BEAM SEAT - HORIZ. - STAGE 2


BAR COUPLERS REQUIRED. BAR LENGTHS CALCULATED TO C OF VERTICAL CONSTRUCTION JOINT. MODIFY, IF NECESSARY, TO BAR COUPLER MANUFACTURER'S SPECIFICATION. PAY BASED ON BARS AS DETAILED.




**A906, A812**




**A407**



**A516, A517**



**WING 1 SECTION**  
WING 2 SIMILAR



**RODENT SHIELD DETAIL**

\* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.


THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.

- BAR COUPLERS REQUIRED.
- A03 OPTIONAL CONST. JOINT: KEYWAY FORMED BY BEVELED 2 x 6. (18" RMW @ B.F. & 3/4" "V" GROOVE @ F.F. IF JOINT IS USED).
- A06 ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 STEEL PILING, FIRMLY SEATED IN HOLES PRE-BORED TO AN ELEVATION OF 878.5. PILES ESTIMATED 20'-0" LONG. PILE DRIVING IS NOT REQUIRED. FACTORED AXIAL RESISTANCE, USED FOR DESIGN, IS 180 TONS PER PILE. PILE SPLICE DETAILS ON "EAST ABUTMENT DETAILS" SHEET.
- A15 PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED. SEE SHIELD DETAILS ON THIS SHEET.
- A17 1/2" FILLER (INCLUDED IN WING LENGTH); SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- A19 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- A21 FOR PPT. BARS & DIMENSIONS, SEE "SINGLE SLOPE PARAPET 42SS" SHEET.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		PLANS CK'D.	
M J H		A R C	
<b>WEST ABUTMENT DETAILS</b>			SHEET 6


STEEL TROWEL TOP SURFACE OF ABUTMENT. PLACE MULTIPLE LAYERS OF POLYETHYLENE SHEETS OVER ENTIRE ABUTMENT TOP BEFORE PLACING BEARING PADS. TOTAL THICKNESS OF SHEETS SHALL BE AT LEAST 0.03".




**ELEVATION**  
(LOOKING EAST)

WING 3


WING 4



**PLAN**




**PILE PLAN**



**SECTION THRU BODY**


- BAR COUPLERS REQUIRED
- \* ELEVATIONS GIVEN ARE AT C. BRG. & GIRDER. SEE "SLOPED BEAM SEAT DETAILS"
- 4" X 1/2" PREFORMED JOINT FILLER X ABUTMENT LENGTH
- ★ 3/4" CORK FILLER ON VERTICAL BEAM SEAT FACES.
- (A06) ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 STEEL PILING, FIRMLY SEATED IN HOLE PRE-BORED TO AN ELEVATION OF 878.5. PILES ESTIMATED 20'-0" LONG. PILES DRIVING IS NOT REQUIRED. FACTORED AXIAL RESISTANCE, USED FOR DESIGN, IS 180 TONS PER PILE. PILE SPLICE DETAILS ON "EAST ABUTMENT DETAILS" SHEET.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH), SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED. SEE SHIELD DETAILS ON "WEST ABUTMENT DETAILS" SHEET.
- (A17) 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE), EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.




**SLOPED BEAM SEAT DETAILS**

PROPOSED ABUTMENT OVERLAPS EXISTING ABUT. BODY FOOTING. PRE-BORING MAY NEED TO EXTEND THROUGH EXIST. CONC. FOOTING (TYP. PILES 1&6)


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		PLANS CK'D.	
M J H		A R C	
EAST ABUTMENT			SHEET 7



**WING 3 ELEVATION**  
LOOKING AT FRONT FACE,  
WING 4 SIMILAR



**B501, B509**




**B403**


**BILL OF BARS** NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
B501		47	17'-0"	X		BODY-STIRRUPS
B402		12	2'-3"			PILES - 2 PER BODY PILE
B403		6	28'-0"	X		PILES - 1 PER BODY PILE
B604		11	19'-1"			BODY - HORIZ. - F.F., TOP. & BOT. - STAGE 2
B605		7	3'-4"			BODY - HORIZ. - B.F. - STAGE 2
B906		14	18'-8"	X		BODY - HORIZ. - B.F. - STAGE 1 & 2
B407		20	3'-11"	X		BODY - BTWN. BEAM SEATS - VERT.
B408		8	6'-2"			BODY - BTWN. BEAM SEATS - HORIZ.
B509	X	24	17'-6"	X		WING 3 & 4 - STIRRUPS
B410	X	6	5'-6"			WINGS 3 & 4 - VERT. F.F. - ABUT. ENDS
B511	X	14	14'-4"			WING 3 & 4 - HORIZ. - F.F. - LOWER WINGS
B812	X	18	14'-0"	X		WING 3 & 4 - HORIZ. - B.F. - LOWER WINGS
B413	X	8	7'-9"			WING 3 & 4 - HORIZ. - UPPER WINGS
B414	X	18	17'-8"			WING 3 & 4 - HORIZ. - UPPER WINGS
B615	X	4	17'-8"			WING 3 & 4 - HORIZ. - UPPER WINGS - TOP
B516	X	18	10'-6"	X		WING 3 & 4 - VERT. - UPPER WINGS
B517	X	32	12'-6"	X		WING 3 & 4 - VERT. - UPPER WINGS
B618		11	19'-1"			BODY - HORIZ. - F.F., TOP. & BOT. - STAGE 1
B619		7	3'-4"			BODY - HORIZ. - B.F. - STAGE 1
B420		2	3'-1"			BODY - BTWN. BEAM SEAT - HORIZ. - STAGE 2
B421		2	3'-1"			BODY - BTWN. BEAM SEAT - HORIZ. - STAGE 1
B422	X	38	2'-0"			WING 3 & 4 - HORIZ. - SURFACE DRAIN ANCHORS


BAR COUPLERS REQUIRED. BAR LENGTHS CALCULATED TO C. OF VERTICAL CONSTRUCTION JOINT. MODIFY, IF NECESSARY, TO BAR COUPLER MANUFACTURER'S SPECIFICATION. PAY BASED ON BARS AS DETAILED.




**B906, B812**




**B407**



**B516, B517**



**WING 3 SECTION**  
WING 4 SIMILAR



**PILE DETAILS**

- BAR COUPLERS REQUIRED.
- (A03) OPTIONAL CONST. JOINT: KEYWAY FORMED BY BEVELED 2 x 6. (18" RMW @ B.F. & 3/4" "V" GROOVE @ F.F. IF JOINT IS USED).
- (A06) ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 STEEL PILING, FIRMLY SEATED IN HOLES PRE-BORED TO AN ELEVATION OF 878.5. PILES ESTIMATED 20'-0" LONG. PILE DRIVING IS NOT REQUIRED. FACTORED AXIAL RESISTANCE, USED FOR DESIGN, IS 180 TONS PER PILE. PILE SPLICE DETAILS ON THIS SHEET.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED. SEE SHIELD DETAILS ON "WEST ABUTMENT DETAILS" SHEET.
- (A16) B422 BARS SPACED @ 1'-0" CTRS. EMBED 1'-0" INTO WING CONC. LOCATE 3" DOWN FROM TOP OF WING @ BACKFACE TO 6" DOWN @ WING TIP. (DRILLED IN EPOXY ANCHORED #4 BARS 2'-0" LONG MAY BE USED.) COST INCIDENTAL TO BID ITEM "BAR STEEL REINFORCEMENT HS COATED STRUCTURES".
- (A17) 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (A21) FOR PPT. BARS & DIMENSIONS, SEE "SINGLE SLOPE PARAPET 42SS" SHEET.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		MJH	PLANS CK'D. ARC
<b>EAST ABUTMENT DETAILS</b>		SHEET 8	

**NOTES**

TOP OF GIRDER TO BE ROUGH FLOATED AND BROOMED TRANSVERSELY, EXCEPT THE OUTSIDE 2" OF GIRDER, WHICH SHALL RECEIVE A SMOOTH FINISH. AN APPROVED CONCRETE SEALER SHALL BE APPLIED TO ALL SMOOTH SURFACES INCLUDING THE OUTSIDE 2" OF THE TOP FLANGE.

DO NOT APPLY CONCRETE SEALER OR EPOXY TO SURFACES RECEIVING APPLICATION OF CONCRETE STAINING.

THE GIRDERS SHALL BE PROVIDED WITH A SUITABLE LIFTING DEVICE FOR HANDLING AND ERECTING THE GIRDERS. SEE SECT. 503.3.3 OF STANDARD SPECIFICATIONS FOR GUIDANCE.

STRANDS SHALL BE FLUSH WITH END OF GIRDER. FOR GIRDER ENDS EMBEDDED COMPLETELY IN CONCRETE, END OF STRANDS SHALL BE COATED WITH NON-BITUMINOUS JOINT SEALER. FOR GIRDER ENDS THAT ARE FINALLY EXPOSED, COAT THE GIRDER ENDS, EXPOSED STRAND ENDS AND ALL NON-BONDING SURFACES WITHIN 2 FEET OF THE GIRDER ENDS WITH A NON-PIGMENTED EPOXY CONFORMING TO AASHTO M-235 TYPE III, GRADE 2, CLASS B OR C. THE EPOXY SHALL BE APPLIED AT LEAST 3 DAYS AFTER MOIST CURING HAS CEASED AND PRIOR TO THE APPLICATION OF THE SEALER.

ALL GIRDERS SHALL BE CAST FULL LENGTH AS SHOWN.


SPACING SHOWN FOR #4 STIRRUPS IS FOR GRADE 60 REINFORCEMENT.

AN ALTERNATE EQUIVALENT OF WELDED WIRE FABRIC (WWF) ASTM A1064 MAY BE SUBSTITUTED FOR THE STIRRUP REINFORCEMENT SHOWN, UPON APPROVAL OF THE STRUCTURES DEVELOPMENT SECTION.

PRESTRESSING STRANDS SHALL BE (0.6" DIA.)-7 WIRE LOW-RELAXATION STRANDS WITH AN ULTIMATE STRENGTH OF 270,000 PSI.


BEND EACH END OF #4 STIRRUPS 4 1/2" AND #5 STIRRUPS 6".

FOR DIAPHRAGM INSERT & CONNECTION DETAILS SEE "STEEL DIAPHRAGM" SHEET.




**SIDE VIEW & TYPICAL SECTION IN SPAN** (A) DETAIL TYP. AT EACH END


(B) 2 #5 BARS, FULL LENGTH, MIN. LAP = 2'-5", STD. HOOK AT ENDS




**TYP. STRAND PATTERN**



**TOP VIEW OF GIRDER ENDS**



**DEAD LOAD DEFLECTION DIAGRAM**




**DECK HAUNCH DETAIL**

IF 1/4" MINIMUM HAUNCH HEIGHT AT EDGE OF GIRDER CANNOT BE MAINTAINED, THE GRADE LINE MAY BE REVISED BY THE ENGINEER AT THE OPTION OF THE CONTRACTOR, THE PLAN DECK THICKNESS SHALL BE HELD. NOTIFY THE STRUCTURES SECTION IF THE GRADE LINE IS RAISED FROM THE PLAN PROFILE BY MORE THAN 1/2" OR, \*\* IF 3" MINIMUM DECK EMBEDMENT OF THE BAR CANNOT BE OBTAINED.

TO DETERMINE 'T', ELEV. OF TOP OF GIR'S. AT C. OF SUBSTRUCTURE UNITS & AT 1/10 POINTS OF EACH SPAN SHALL BE TAKEN. THEN FOLLOW THIS PROCESS:

- TOP OF DECK ELEV. AT FINAL GRADE
- TOP OF GIRDER ELEVATION
- + DEAD LOAD DEFLECTION
- DECK THICKNESS
- = HAUNCH HEIGHT 'T'

NOTE: AN AVERAGE HAUNCH ('T') OF 2.9" WAS USED IN THE QUANTITY "CONCRETE MASONRY BRIDGES".



**DRAPED STRAND PROFILE**

\* THE THEORETICAL INITIAL CAMBER VALUE AT THE TIME OF STRAND RELEASE AT MIDSPAN MULTIPLIED BY A FACTOR OF 1.4 TO ACCOUNT FOR CAMBER GROWTH FROM THE TIME OF STRAND RELEASE TO JOBSITE PLACEMENT.


SPAN	CAMBER (IN.) *
1	2.81

THESE VALUES ARE NOT TO BE USED IN DETERMINING 'T'. USE ACTUAL GIRDER SHOTS. THESE VALUES ARE FOR INFORMATIONAL PURPOSES ONLY.

\* MINIMUM CYLINDER STRENGTH OF CONCRETE @ TIME OF TRANSFER OF PRESTRESS FORCE.

**GIRDER DATA**


SPAN	GIRDER	GIRDER LENGTH "L" (FEET)	DEAD LOAD DEFL. (IN.)									CONC. STRGTH. f'c (P.S.I.)	"P" (IN.)			DIA. OF STRAND (IN.)	TOTAL NO. OF STRANDS	f'ci (P.S.I.) *	DRAPED PATTERN (IN.)				
			1/10	2/10	3/10	4/10	5/10	6/10	7/10	8/10	9/10		1ST 1/3 OF GIRDER	MID 1/3 OF GIRDER	END 1/3 OF GIRDER				"A"	"B" MIN.	"B" MAX.	"C"	
1	1-6	71.0	0.4	0.8	1.0	1.2	1.3	1.2	1.0	0.8	0.4	8,000	7	6 1/2"	7	0.6	18	6,400	32	11	14	4	




**DRAPED PATTERN**

0.6" DIA. STRANDS

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		PLANS CHECKED	
M J H		A R C	
<b>36" PRESTRESSED GIRDER DETAILS</b>		SHEET 9	




**INTERMEDIATE STEEL DIAPHRAGM LAYOUT**



**DIAPHRAGM SUPPORT**


\* 2 1/2" FOR ALTERNATE PLATE DIAPHRAGM




C12X20.7

ALTERNATE DIAPHRAGM


**SECTION THRU DIAPHRAGM**



**PART TRANSVERSE SECTION AT DIAPHRAGM**



**DETAIL B**




**SECTION A-A**  
(FOR EXTERIOR ATTACHMENT)


**NOTES**

- ALL DIAPHRAGM MATERIAL NOT EMBEDDED IN THE CONCRETE GIRDER SHALL BE PAID FOR AT THE UNIT PRICE BID FOR "STEEL DIAPHRAGMS B-27-171", EACH.
- EACH DIAPHRAGM BETWEEN GIRDERS SHALL CONSTITUTE ONE UNIT.
- ALL DIAPHRAGM STRUCTURAL STEEL SHALL BE ASTM A709 GRADE 36.
- ALL DIAPHRAGM MATERIAL INCLUDING BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED AFTER FABRICATION.
- STEEL DIAPHRAGM TO CONCRETE WEB CONNECTION SHALL BE SNUG-TIGHT PLUS 1/4 TURN, UNLESS NOTED OTHERWISE. HIGH STRENGTH BOLTS FOR WEB CONNECTION SHALL MEET THE REQUIREMENTS FOR ASTM A325 OR ASTM A449.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		MJH	PLANS CHECKED BY
			ARC
<b>STEEL DIAPHRAGM</b>			SHEET 10




**SECTION S-S**




**DETAIL A**

◆ BARS EQUALLY SPACED AT EACH DIAPH. END FACE




**TYP. EDGE OF DECK SECTION**




**SECTION THRU LONGIT. JOINT**

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY MJH		PLANS CKD. ARC	
<b>SUPERSTRUCTURE DETAILS 1</b>			SHEET 11



**DECK PLAN**

■ FOR PPT. VERTICAL REINF. LOCATIONS & SPACING, SEE "PARTIAL PLAN DETAIL OF PARAPET REINF." & "SECTION THRU PARAPET ON DECK" DETAILS ON NEXT SHEET.



**CROSS SECTION THRU BRIDGE**

(LOOKING EAST UPSTATION)


⊙ 3/4" V-GROOVE REQ'D. EXTEND TO 6" FROM F.F. OF ABUT. DIAPH.

**DETAIL B**  
BAR COUPLERS REQUIRED

8

8






**PART LONGIT. SECTION**

BAR COUPLERS REQUIRED

\* DIMENSION IS TAKEN NORMAL TO  $\phi$  SUBSTRUCTURE UNITS.

\*\* BARS PLACED PARALLEL TO GIRDERS SPACING PERPENDICULAR TO  $\phi$  GIRDERS



**SECTION THRU PARAPET ON DECK**


CONSTRUCTION JOINT. STRIKE OFF AS SHOWN.

**BILL OF BARS**

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE


BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
S401	X	102	36'-11"			DECK-LONGIT.-TOP
S402	X	156	25'-2"			DECK-LONGIT.-BOT.
S403	X	347	20'-9"			DECK-TRANS.-TOP & BOT.-STAGE 1
S404	X	347	19'-6"			DECK-TRANS.-TOP & BOT.-STAGE 2
S505	X	174	4'-6"	X		DECK-TRANS. EDGE OF DECK
S506	X	32	37'-8"			PARAPET-HORIZ.
S507	X	218	4'-5"	X		PARAPET/DECK-VERT.
S508	X	222	6'-8"	X		PARAPET-VERT.
S609	X	4	1'-6"			ABUT. DIAPH.-HORIZ.-END-BOT.-F.F.
S610	X	8	6'-6"	X		ABUT. DIAPH.-HORIZ.-END
S411	X	12	2'-8"			ABUT. DIAPH.-VERT.-ENDS
S512	X	92	11'-8"	X		ABUT. DIAPH.-VERT. STIRRUP
S513	X	92	5'-9"	X		ABUT. DIAPH.-VERT. U-BAR
S414	X	16	3'-10"			ABUT. DIAPH.-HORIZ.-BOT.-BTWN. BEAM SEATS
S415	X	50	3'-3"	X		ABUT. DIAPH.-VERT.-BOT.-BTWN. BEAM SEATS
S616	X	64	3'-10"			ABUT. DAIPH.-HORIZ.-F.F.
S617	X	4	1'-9"			ABUT. DIAPH.-HORIZ.-END-TOP-F.F.
S618	X	12	18'-7"			ABUT. DIAPH.-HORIZ.-BF. & TOP - STAGE 1
S519	X	24	6'-0"			ABUT. DIAPH.-HORIZ. THRU GIR.
S620	X	12	19'-7"			ABUT. DIAPH.-HORIZ.-BF. & TOP - STAGE 2
S521	X	4	5'-10"	X		DECK & PPT. - VERT. - AT PAVING NOTCH
S422	X	4	1'-5"			ABUT. DIAPH.-HORIZ.-BOT.-BTWN. BEAM SEATS - STAGE 1
S423	X	4	2'-5"			ABUT. DIAPH.-HORIZ.-BOT.-BTWN. BEAM SEATS - STAGE 2
S624	X	4	1'-11"			ABUT. DAIPH.-HORIZ.-F.F. - STAGE 1
S625	X	4	2'-11"			ABUT. DAIPH.-HORIZ.-F.F. - STAGE 2
S626	X	4	2'-5"			ABUT. DAIPH.-HORIZ.-F.F. - STAGE 1
S627	X	4	3'-5"			ABUT. DAIPH.-HORIZ.-F.F. - STAGE 2

BAR COUPLERS REQUIRED. BAR LENGTHS CALCULATED TO  $\phi$  OF VERTICAL CONSTRUCTION JOINT. MODIFY, IF NECESSARY, TO BAR COUPLER MANUFACTURER'S SPECIFICATION. PAY BASED ON BARS AS DETAILED.




**PARTIAL PLAN DETAIL OF PARAPET REINF.**


(SHOWING SOUTH CORNERS OF WEST & EAST ABUTMENTS. DETAIL TYP. OF BOTH EDGES OF SUPERSTRUCTURE)




**S505**




**S507**




**S508**




**S512**



**S610, S513, S610**



**S521**



**BEARING PAD DETAIL**

**TOP OF DECK ELEVATIONS**

	W. ABUT.	1/10	2/10	3/10	4/10	5/10	6/10	7/10	8/10	9/10	E. ABUT.	
N. EOD	903.86	903.81	903.77	903.73	903.69	903.65	903.61	903.57	903.52	903.48	903.44	N. EOD
GIRDER 1	903.88	903.84	903.80	903.76	903.72	903.67	903.63	903.59	903.55	903.51	903.47	GIRDER 1
GIRDER 2	904.02	903.97	903.93	903.89	903.85	903.81	903.77	903.73	903.68	903.64	903.60	GIRDER 2
GIRDER 3	904.15	904.11	904.07	904.02	903.98	903.94	903.90	903.86	903.82	903.78	903.74	GIRDER 3
R. STH 95	904.22	904.17	904.13	904.09	904.05	904.01	903.97	903.93	903.88	903.84	903.80	STH 95
GIRDER 4	904.15	904.11	904.07	904.02	903.98	903.94	903.90	903.86	903.82	903.78	903.74	GIRDER 4
GIRDER 5	904.02	903.97	903.93	903.89	903.85	903.81	903.77	903.73	903.68	903.64	903.60	GIRDER 5
GIRDER 6	903.88	903.84	903.80	903.76	903.72	903.67	903.63	903.59	903.55	903.51	903.47	GIRDER 6
S. EOD	903.86	903.81	903.77	903.73	903.69	903.65	903.61	903.57	903.52	903.48	903.44	S. EOD

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY		MJH	PLANS CHECKED BY ARC
<b>SUPERSTRUCTURE DETAILS 2</b>			SHEET 12

**BILL OF BARS**

FOR ABUTMENT PARAPETS



BAR MARK	COU'T	WEST ABUT.	EAST ABUT.	LENGTH	BENT	BAR SERIES	LOCATION
R501	X	28	28	5'-10"	X		PARAPET VERT.
R502	X	28	28	6'-8"	X		PARAPET VERT.
R503	X	24	24	3'-0"	X		PARAPET VERT.
R504	X	34	34	5'-7"	X		PARAPET VERT.
R505	X	10	10	6'-5"	X		PARAPET VERT.
R506	X	12	12	6'-6"	X		PARAPET VERT.
R507	X	2	2	17'-7"	X		PARAPET HORIZ.
R508	X	10	10	17'-7"			PARAPET HORIZ.
R509	X	12	12	5'-5"	X	▲	PARAPET VERT.
R510	X	4	4	17'-7"	X		PARAPET HORIZ.

▲ LENGTH SHOWN FOR BAR IS AN AVERAGE LENGTH AND SHOULD ONLY BE USED FOR BAR WEIGHT CALCULATIONS. SEE BAR SERIES TABLE FOR ACTUAL LENGTHS.

**BAR SERIES TABLE**


BAR MARK	NO. REQ'D	LENGTH
R509	4 SERIES OF 6	4'-9" TO 6'-1"

BUNDLE AND TAG EACH SERIES SEPARATELY.




**PARAPET END TREATMENT DETAIL**  
LOOKING AT INSIDE FACE OF PARAPET


OPTIONAL CONSTRUCTION JOINTS IN THE PARAPETS MAY BE USED, RUN BAR REINF. THRU THE JOINT, LAP LONGIT. BARS A MIN. OF 1'-9". MIN. JOINT SPACING OF 80'-0". DEFINE CONST. JOINT WITH A 3/4" - 1" GROOVE.




PLAN  
NW CORNER SHOWN, OTHERS SIMILAR



**INSIDE ELEVATION**  
NW CORNER SHOWN, OTHERS SIMILAR



■ BENCH MARK CAP (WHEN SUPPLIED). AVOID PLACING A BENCH MARK CAP BELOW A RAIL OR FENCE SYSTEM THAT IS ATTACHED TO THE TOP OF THE PARAPET.




**DETAIL OF ANCHOR ASSEMBLY**


NOTE: HEX HEAD CAP SCREWS & WASHERS TO BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 CLASS C.  
ASSEMBLY SHALL BE BID ITEM "ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD", EACH.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
<b>STRUCTURE B-27-171</b>			
DRAWN BY MJH		PLANS CK'D. ARC	
<b>SINGLE SLOPE PARAPET 42SS</b>		SHEET 13	


**PROJECT I.D. 7520-00-77 EARTHWORK SUMMARY**

STA	EXCAVATION COMMON (1) CY	UNUSABLE PAVEMENT CY	AVAILABLE MATERIAL (2) CY	UNEXPANDED FILL CY	EXPANDED FILL (3) CY	MASS ORDINATE (4) +/-	WASTE CY	BORROW CY
<b>61+37.00</b>	15	1	14	10	13	1	1	-1
<b>61+50.00</b>	32	3	29	53	69	-40	3	40
<b>61+85.60</b>	10	1	9	24	31	-22	1	22
<b>62+00.00</b>	15	2	13	53	69	-56	2	56
<b>62+25.00</b>								
<b>STRUCTURE B-27-0171</b>								
<b>63+36.92</b>	15	0	15	15	20	-5	0	5
<b>63+50.00</b>	32	1	31	33	43	-12	1	12
<b>63+77.05</b>	14	1	13	14	18	-5	1	5
<b>63+88.90</b>	16	1	15	17	22	-7	1	7
<b>64+02.05</b>	29	2	27	41	53	-26	2	26
<b>64+27.05</b>	25	1	24	21	27	-3	1	3
<b>64+50.00</b>								
<b>SUBTOTALS</b>	203	13		281	365	-175	13	175
<b>TOTALS</b>	<b>203</b>			<b>281</b>	<b>365</b>		<b>13</b>	<b>175</b>
(1) COMMON EXCAVATION IS THE SUM OF THE CUT INCLUDING UNSUABLE PAVEMENT MATERIAL. ITEM NUMBER 205.0100 (2) AVAILABLE MATERIAL = CUT - UNUSABLE PAVEMENT MATERIAL (3) - FILL EXPANSION 30% (4) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.								





PROJECT NO: 7520-00-77      HWY: STH 95      COUNTY: JACKSON      CROSS SECTIONS: STH 95      SHEET      E



PROJECT NO: 7520-00-77      HWY: STH 95      COUNTY: JACKSON      CROSS SECTIONS: STH 95      SHEET      E

Notes



## ***Wisconsin Department of Transportation***

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>