



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

January 9, 2023

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #02: 1016-01-61, WISC 2023135**  
**Tomah - Portage**  
**Camp Douglas to Seven Mile Creek**  
**IH 090**  
**Juneau County**

### Letting of January 10, 2023

This is Addendum No. 02, which provides for the following:

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
416.1725	Concrete Pavement Replacement SHES	SY	13,198	-1,700	11,498

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
10-23	Corrected Concrete Repair item on MQ sheets

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**

**1016-01-61**

**January 9, 2023**

**Schedule of Items**

Attached, dated January 9, 2023, are the revised Schedule of Items Page 1.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 10-23

END OF ADDENDUM

CONCRETE REPAIR SUMMARY														CONCRETE REPAIR SUMMARY (CONTINUED)																							
416.0610							416.0620							416.0610							416.0620																
EB MILE MARKER	PLUS	EASTBOUND LOCATION	LENGTH	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	EB MILE MARKER	PLUS	EASTBOUND LOCATION	LENGTH	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS																		
55	350	right	6	-	16	9.33	-	34		56	1130	right	60	24	16	-	93.33	88																			
55	860	right	15	6	16	23.33	-	43		56	1270	right	105	42	16	-	163.33	133																			
55	2220	right	15	6	16	23.33	-	43		56	1400	right	30	12	16	-	46.67	58																			
55	2300	right	30	12	16	-	46.67	58		56	1600	left	6	-	16	8.00	-	30																			
55	2500	left	6	-	16	8.00	-	30		56	1800	right	60	24	16	-	93.33	88																			
55	3090	right	50	20	16	-	77.78	78		56	1890	right	30	12	16	-	46.67	58																			
55	3181	right	20	8	16	-	31.11	48		56	1920	right	12	5	16	18.67	-	40																			
55	3269	right	20	8	16	-	31.11	48		56	1920	left	6	-	16	8.00	-	30																			
55	3420	right	30	12	16	-	46.67	58		56	1950	right	45	18	16	-	70.00	73																			
55	3500	right	60	24	16	-	93.33	88		56	2000	left	6	-	16	8.00	-	30																			
55	3620	right	45	18	16	-	70.00	73		56	2060	right	30	12	16	-	46.67	58																			
55	3700	right	15	6	16	23.33	-	43		56	2088	right	12	5	16	18.67	-	40																			
55	3720	right	30	12	16	-	46.67	58		56	2110	left	6	-	16	8.00	-	30																			
55	3840	right	30	12	16	-	46.67	58		56	2144	right	12	5	16	18.67	-	40																			
55	3940	right	15	6	16	23.33	-	43		56	2200	left	6	-	16	8.00	-	30																			
55	3940	left	6	-	16	8.00	-	30		56	2220	right	45	18	16	-	70.00	73																			
55	3940	right	30	12	16	-	46.67	58		56	2370	right	75	30	16	-	116.67	103																			
55	4200	left	6	-	16	8.00	-	30		56	2430	left	6	-	16	8.00	-	30																			
55	4300	right	6	-	16	9.33	-	34		56	2566	right	30	12	16	-	46.67	58																			
55	4400	left	6	-	16	8.00	-	30		56	2590	left	6	-	16	8.00	-	30																			
55	4500	right	8	4	16	12.44	-	36		56	2640	right	60	24	16	-	93.33	88																			
55	4520	right	8	4	16	12.44	-	36		56	2740	right	45	18	16	-	70.00	73																			
55	4530	right	8	4	16	12.44	-	36		56	2950	right	45	18	16	-	70.00	73																			
55	4550	right	45	18	16	-	70.00	73		56	2980	left	6	-	16	8.00	-	30																			
55	4690	left	6	-	16	8.00	-	30		56	3120	right	30	12	16	-	46.67	58																			
55	4730	right	30	12	16	-	46.67	58		56	3190	right	30	12	16	-	46.67	58																			
55	4999	right	60	24	16	-	93.33	88		56	3500	right	75	30	16	-	116.67	103																			
55	5080	left	6	-	16	8.00	-	30		56	3620	right	45	18	16	-	70.00	73																			
55	5129	right	30	12	16	-	46.67	58		56	3670	left	6	-	16	8.00	-	30																			
55	5200	right	45	18	16	-	70.00	73		56	3730	right	15	6	16	23.33	-	43																			
56	50	right	60	24	16	-	93.33	88		56	3730	left	6	-	16	8.00	-	30																			
56	220	right	60	24	16	-	93.33	88		56	3750	left	6	-	16	8.00	-	30																			
56	430	right	10	4	16	15.56	-	38		56	3800	right	15	6	16	23.33	-	43																			
56	500	right	15	6	16	23.33	-	43		56	3860	right	30	12	16	-	46.67	58																			
56	530	right	15	6	16	23.33	-	43		56	3890	left	6	-	16	8.00	-	30																			
56	570	left	6	-	16	8.00	-	30		56	3950	right	20	8	16	-	31.11	48																			
56	780	right	45	18	16	-	70.00	73		56	4100	right	30	12	16	-	46.67	58																			
56	780	left	6	-	16	8.00	-	30		56	4266	left	6	-	16	8.00	-	30																			
56	900	right	30	12	16	-	46.67	58		56	4280	both	6	-	32	17.33	-	58																			
56	980	right	75	30	16	-	116.67	103		56	4350	left	6	-	16	8.00	-	30																			
SUBTOTAL 1 =														382	640	276	1,283	2,097	SUBTOTAL 2 =														395	656	232	1,431	2,164

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet  
 January 9, 2023

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 11  
January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

EB MILE MARKER	PLUS	EASTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	EB MILE MARKER	PLUS	EASTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	CONCRETE REPAIR SUMMARY (CONTINUED)													
																		416.0610	416.0620	416.1715	690.0250										
56	4444	right	30	12	16	9.33	46.67	58	57	3110	right	30	12	16	9.33	46.67	58		57	3110	right	30	12	16	9.33	46.67	58				
56	4566	right	6	-	16	9.33	-	34	57	3555	right	6	-	16	9.33	-	34		57	3555	right	6	-	16	9.33	-	34				
56	4610	right	6	-	16	9.33	-	34	57	3666	right	30	12	16	9.33	-	34		57	3666	right	30	12	16	9.33	-	34				
56	4655	right	6	-	16	9.33	-	34	57	3699	right	8	4	16	12.44	-	36		57	3699	right	8	4	16	12.44	-	36				
56	4766	right	6	-	16	9.33	-	34	57	3800	right	8	4	16	12.44	-	36		57	3800	right	8	4	16	12.44	-	36				
56	4799	left	6	-	16	8.00	-	30	57	3910	right	45	18	16	8.00	-	73		57	3910	left	6	-	16	8.00	-	30				
56	4830	left	6	-	16	8.00	-	30	57	3910	left	6	-	16	8.00	-	30		57	3910	left	6	-	16	8.00	-	30				
56	4850	right	12	5	16	18.67	-	40	57	3955	left	6	-	16	8.00	-	30		57	3955	left	6	-	16	8.00	-	30				
56	4888	left	6	-	16	8.00	-	30	57	3999	right	6	-	16	9.33	-	34		57	3999	right	6	-	16	9.33	-	34				
56	4900	left	6	-	16	8.00	-	30	57	4030	right	6	-	16	9.33	-	34		57	4030	right	6	-	16	9.33	-	34				
57	100	right	45	18	16	-	70.00	73	57	4040	both	6	-	32	17.33	-	58		57	4040	both	6	-	32	17.33	-	58				
57	200	right	30	12	16	8.00	46.67	58	57	4100	right	6	-	16	9.33	-	34		57	4100	right	6	-	16	9.33	-	34				
57	310	left	6	-	16	8.00	-	30	57	4177	right	8	4	16	12.44	-	36		57	4177	right	8	4	16	12.44	-	36				
57	310	right	15	6	16	23.33	-	43	57	4222	left	6	-	16	8.00	-	30		57	4222	left	6	-	16	8.00	-	30				
57	355	right	15	6	16	23.33	-	43	57	4299	left	6	-	16	8.00	-	30		57	4299	left	6	-	16	8.00	-	30				
57	355	left	6	-	16	8.00	-	30	57	4315	right	6	-	16	9.33	-	34		57	4315	right	6	-	16	9.33	-	34				
57	400	right	15	6	16	23.33	-	43	57	4355	right	45	18	16	18.67	-	73		57	4355	right	45	18	16	18.67	-	73				
57	630	right	135	54	16	-	210.00	163	57	4577	right	12	5	16	8.00	-	40		57	4577	right	12	5	16	8.00	-	40				
57	1010	right	90	36	16	-	140.00	118	57	4630	left	6	-	16	8.00	-	30		57	4630	left	6	-	16	8.00	-	30				
57	1188	right	6	-	16	9.33	-	34	57	4377	right	12	5	16	18.67	-	40		57	4377	right	12	5	16	18.67	-	40				
57	1222	right	75	30	16	-	116.67	103	57	4699	left	6	-	16	8.00	-	30		57	4699	left	6	-	16	8.00	-	30				
57	1400	right	6	-	16	9.33	-	34	57	4780	left	6	-	16	8.00	-	30		57	4780	left	6	-	16	8.00	-	30				
57	1477	right	60	24	16	-	93.33	88	57	4810	left	6	-	16	8.00	-	30		57	4810	left	6	-	16	8.00	-	30				
57	1555	right	6	-	16	9.33	-	34	57	4920	right	6	-	16	9.33	-	34		57	4920	right	6	-	16	9.33	-	34				
57	1720	right	60	24	16	-	93.33	88	57	4930	right	6	-	16	9.33	-	34		57	4930	right	6	-	16	9.33	-	34				
57	1800	left	6	-	16	8.00	-	30	57	5050	right	30	12	16	-	46.67	58		57	5050	right	30	12	16	-	46.67	58				
57	1930	left	6	-	16	8.00	-	30	57	5100	right	45	18	16	8.00	-	73		57	5100	right	45	18	16	8.00	-	73				
57	1940	right	12	5	16	18.67	-	40	57	5100	left	6	-	16	8.00	-	30		57	5100	left	6	-	16	8.00	-	30				
57	1950	right	12	5	16	18.67	-	40	57	5140	right	6	-	16	9.33	-	34		57	5140	right	6	-	16	9.33	-	34				
57	1970	right	6	-	16	9.33	-	34	58	160	right	6	-	16	9.33	-	34		58	160	right	6	-	16	9.33	-	34				
57	2020	right	30	12	16	-	46.67	58	58	300	right	15	6	16	23.33	-	43		58	300	right	15	6	16	23.33	-	43				
57	2090	both	6	-	32	17.33	-	58	58	310	left	6	-	16	8.00	-	30		58	310	left	6	-	16	8.00	-	30				
57	2400	left	6	-	16	8.00	-	30	58	320	left	6	-	16	8.00	-	30		58	320	left	6	-	16	8.00	-	30				
57	2400	right	30	12	16	-	46.67	58	58	330	right	30	12	16	-	46.67	58		58	330	right	30	12	16	-	46.67	58				
57	2700	left	6	-	16	8.00	-	30	58	366	both	6	-	32	17.33	-	58		58	366	both	6	-	32	17.33	-	58				
57	2740	left	6	-	16	8.00	-	30	58	430	left	6	-	16	8.00	-	30		58	430	left	6	-	16	8.00	-	30				
57	2750	right	35	14	16	-	54.44	63	58	750	right	12	5	16	18.67	-	40		58	750	right	12	5	16	18.67	-	40				
57	2788	left	6	-	16	8.00	-	30	58	790	right	15	6	16	23.33	-	43		58	790	right	15	6	16	23.33	-	43				
57	2833	left	6	-	16	8.00	-	30	58	850	right	15	6	16	23.33	-	43		58	850	right	15	6	16	23.33	-	43				
57	2920	left	6	-	16	8.00	-	30	58	960	right	15	6	16	23.33	-	43		58	960	right	15	6	16	23.33	-	43				
SUBTOTAL 3 =										281		656		330		964		1,927		SUBTOTAL 4 =		153		672		401		397		1,633	

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

EB MILE MARKER	PLUS	EASTBOUND LOCATION	SIDE	LENGTH	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR		CONCRETE PAVEMENT REPLACEMENT SHES	SAWING CONCRETE LF	REMARKS	EB MILE MARKER	PLUS	EASTBOUND LOCATION	SIDE	LENGTH	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR		CONCRETE PAVEMENT REPLACEMENT SHES	SAWING CONCRETE LF	REMARKS										
							ST	SY											ST	SY													
58	1000	right	right	6	-	16	9.33	-	34	-	-	58	4375	right	right	6	-	16	9.33	-	46.67	690.0250	690.0250	690.0250									
58	1020	right	right	12	5	16	18.67	-	40	-	-	58	4480	right	right	6	-	16	9.33	-	-	-	34	34									
58	1050	right	right	15	6	16	23.33	-	43	-	-	58	4500	right	right	6	-	16	9.33	-	-	-	34	34									
58	1200	right	right	12	5	16	18.67	-	40	-	-	58	4520	right	right	6	-	16	9.33	-	-	-	34	34									
58	1300	right	right	30	12	16	-	46.67	58	-	-	58	4600	right	right	30	12	16	-	-	-	46.67	58	58									
58	1350	right	right	90	36	16	-	140.00	118	-	-	58	4620	right	right	6	-	16	9.33	-	-	-	34	34									
58	1380	right	right	6	-	16	9.33	-	34	-	-	58	4700	right	right	30	12	16	-	-	46.67	-	58	58									
58	1400	both	both	6	-	32	17.33	-	58	-	-	58	4800	right	right	30	12	16	-	-	46.67	-	58	58									
58	1450	right	right	30	12	16	-	46.67	58	-	-	58	4900	right	right	6	-	16	9.33	-	-	-	34	34									
58	1450	left	left	6	-	16	8.00	-	30	-	-	58	18	right	right	6	-	16	9.33	-	-	-	34	34									
58	1515	left	left	6	-	16	8.00	-	30	-	-	59	30	left	left	6	-	16	8.00	-	-	-	30	30									
58	1515	right	right	35	14	16	-	54.44	63	-	-	59	80	right	right	30	12	16	-	-	46.67	-	58	58									
58	1575	right	right	15	6	16	23.33	-	43	-	-	59	170	right	right	6	-	16	9.33	-	-	-	34	34									
58	1600	right	right	12	5	16	18.67	-	40	-	-	59	222	right	right	6	-	16	9.33	-	-	-	34	34									
58	1699	right	right	45	18	16	-	70.00	73	-	-	59	290	right	right	30	12	16	-	-	46.67	-	58	58									
58	1900	right	right	6	-	16	9.33	-	34	-	-	59	450	right	right	6	-	16	9.33	-	-	-	34	34									
58	2000	right	right	6	-	16	9.33	-	34	-	-	59	460	right	right	6	-	16	9.33	-	-	-	34	34									
58	2050	right	right	30	12	16	-	46.67	58	-	-	59	480	left	left	6	-	16	8.00	-	-	-	30	30									
58	2100	both	both	6	-	32	17.33	-	58	-	-	59	530	right	right	6	-	16	9.33	-	-	-	30	30									
58	2160	right	right	15	6	16	23.33	-	43	-	-	59	588	right	right	30	12	16	-	-	46.67	-	58	58									
58	2300	right	right	75	30	16	-	116.67	103	-	-	59	666	right	right	15	6	16	23.33	-	-	-	43	43									
58	2400	right	right	30	12	16	-	46.67	58	-	-	59	733	right	right	15	6	16	23.33	-	-	-	43	43									
58	2488	right	right	6	-	16	9.33	-	34	-	-	59	733	left	left	6	-	16	8.00	-	-	-	30	30									
58	2600	right	right	6	-	16	9.33	-	34	-	-	59	800	right	right	30	12	16	-	-	46.67	-	58	58									
58	2650	right	right	6	-	16	9.33	-	34	-	-	59	827	right	right	30	12	16	-	-	46.67	-	58	58									
58	2700	both	both	6	-	32	17.33	-	58	-	-	59	827	left	left	6	-	16	8.00	-	-	-	30	30									
58	2850	right	right	30	12	16	-	46.67	58	-	-	59	888	right	right	6	-	16	9.33	-	-	-	34	34									
58	3000	right	right	6	-	16	9.33	-	34	-	-	59	922	right	right	6	-	16	9.33	-	-	-	34	34									
58	3120	right	right	20	8	16	-	31.11	48	-	-	59	1000	both	both	6	-	32	17.33	-	-	-	58	58									
58	3200	right	right	6	-	16	9.33	-	34	-	-	59	1020	right	right	6	-	16	9.33	-	-	-	34	34									
58	3400	right	right	8	4	16	12.44	-	36	-	-	59	1070	right	right	6	-	16	9.33	-	-	-	34	34									
58	3500	right	right	60	24	16	-	93.33	88	-	-	59	1090	left	left	6	-	16	8.00	-	-	-	30	30									
58	3800	right	right	30	12	16	-	46.67	58	-	-	59	1150	right	right	30	12	16	-	-	46.67	-	58	58									
58	3860	right	right	45	18	16	-	70.00	73	-	-	59	1250	right	right	6	-	16	9.33	-	-	-	34	34									
58	3960	right	right	15	6	16	23.33	-	43	-	-	59	1260	left	left	6	-	16	8.00	-	-	-	30	30									
58	4000	right	right	15	6	16	23.33	-	43	-	-	59	1300	right	right	12	5	16	18.67	-	-	-	40	40									
58	4120	right	right	30	12	16	-	46.67	58	-	-	59	1444	left	left	6	-	16	8.00	-	-	-	30	30									
58	4200	right	right	6	-	16	9.33	-	34	-	-	59	1255	right	right	8	4	16	12.44	-	-	-	36	36									
58	4260	right	right	6	-	16	9.33	-	34	-	-	59	1530	right	right	45	16	16	-	-	70.00	-	73	73									
58	4360	right	right	6	-	16	9.33	-	34	-	-	59	1600	right	right	75	30	16	-	-	116.67	-	103	103									
SUBTOTAL 5 =												281	688	365	902	1,985	SUBTOTAL 6 =												177	656	310	607	1,706

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet 12  
 January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

EB MILE MARKER	PLUS	EASTBOUND LOCATION	SIDE	LENGTH	416.0610		416.0620		416.1715		416.1725		REMARKS
					DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	
59	1700	right	30	12	16	16	16	16	16	16	16	16	58
59	1800	right	6	16	16	16	16	16	16	16	16	16	34
59	2100	right	6	16	16	16	16	16	16	16	16	16	34
59	2110	right	6	16	16	16	16	16	16	16	16	16	34
59	2266	right	6	16	16	16	16	16	16	16	16	16	34
59	2330	right	6	16	16	16	16	16	16	16	16	16	34
59	2360	right	6	16	16	16	16	16	16	16	16	16	34
59	2370	left	6	16	16	16	16	16	16	16	16	16	34
59	2610	right	30	12	16	16	16	16	16	16	16	16	58
59	2744	right	6	16	16	16	16	16	16	16	16	16	34
59	3200	right	6	16	16	16	16	16	16	16	16	16	34
59	3555	right	15	6	16	16	16	16	16	16	16	16	43
59	3800	right	30	12	16	16	16	16	16	16	16	16	58
59	3860	left	6	16	16	16	16	16	16	16	16	16	34
59	3888	right	30	12	16	16	16	16	16	16	16	16	58
59	4090	right	6	16	16	16	16	16	16	16	16	16	34
59	4240	right	6	16	16	16	16	16	16	16	16	16	34
59	4370	right	6	16	16	16	16	16	16	16	16	16	34
59	4500	right	30	12	16	16	16	16	16	16	16	16	58
59	4590	right	20	8	16	16	16	16	16	16	16	16	48
59	4620	right	6	16	16	16	16	16	16	16	16	16	34
59	4750	right	90	36	16	16	16	16	16	16	16	16	118
59	5040	right	30	12	16	16	16	16	16	16	16	16	58
60	100	right	60	24	16	16	16	16	16	16	16	16	88
60	188	right	6	16	16	16	16	16	16	16	16	16	34
60	233	right	30	12	16	16	16	16	16	16	16	16	58
60	355	right	15	6	16	16	16	16	16	16	16	16	43
60	500	right	45	18	16	16	16	16	16	16	16	16	73
60	588	right	30	12	16	16	16	16	16	16	16	16	103
60	620	left	6	16	16	16	16	16	16	16	16	16	30
60	920	right	15	6	16	16	16	16	16	16	16	16	43
60	955	right	30	12	16	16	16	16	16	16	16	16	58
60	1044	right	6	16	16	16	16	16	16	16	16	16	34
60	1111	right	30	12	16	16	16	16	16	16	16	16	58
60	1177	right	45	18	16	16	16	16	16	16	16	16	73
60	1200	left	6	16	16	16	16	16	16	16	16	16	30
60	1444	left	6	16	16	16	16	16	16	16	16	16	34
60	1460	left	6	16	16	16	16	16	16	16	16	16	34
60	1490	left	6	16	16	16	16	16	16	16	16	16	28
60	1555	right	12	5	16	16	16	16	16	16	16	16	28
60	1555	right	12	5	16	16	16	16	16	16	16	16	58
SUBTOTAL 7 =													265
SUBTOTAL 8 =													941
SUBTOTAL 8 =													723
SUBTOTAL 8 =													315
SUBTOTAL 8 =													720
SUBTOTAL 8 =													211
SUBTOTAL 8 =													1,880
SUBTOTAL 8 =													1,869

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet 13  
 January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)										CONCRETE REPAIR SUMMARY (CONTINUED)														
EB MILE MARKER	PLUS	SIDE	EASTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	EB MILE MARKER	PLUS	SIDE	EASTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS					
																				416.0610	416.0620	416.1715	416.1725	690.0250
61	2300	right	60	24	16	62	1790	right	75	30	16	-	-	103	-	-	-	-	-					
61	2300	left	6	-	16	62	1860	left	10	4	16	13.33	-	34	-	-	-	-	-					
61	2420	right	30	12	16	62	2060	right	45	18	16	-	70.00	73	-	-	-	-	-					
61	2620	left	6	-	16	62	2160	right	30	12	16	-	46.67	58	-	-	-	-	-					
61	2666	both	6	-	32	62	2260	right	20	8	16	-	31.11	48	-	-	-	-	-					
61	2700	left	6	-	16	62	2400	both	6	-	32	17.33	-	58	-	-	-	-	-					
61	2800	left	6	-	16	62	2440	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	2969	right	15	6	16	62	2480	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	3010	both	6	-	32	62	2699	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	3170	right	20	8	16	62	2800	right	8	4	16	12.44	-	36	-	-	-	-	-					
61	3310	right	6	-	16	62	2800	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	3360	right	6	-	16	62	2820	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	3370	right	6	-	16	62	2930	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	3420	both	6	-	32	62	3000	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	3525	left	6	-	16	62	3028	right	8	4	16	12.44	-	36	-	-	-	-	-					
61	3666	right	45	18	16	62	3028	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	3820	both	6	-	32	62	3035	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	3833	right	6	-	16	62	3092	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	3860	both	6	-	32	62	3230	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	3870	both	6	-	32	62	3266	right	45	18	16	-	70.00	73	-	-	-	-	-					
61	4000	right	30	12	16	62	3310	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	4130	right	15	6	16	62	3333	left	6	-	16	8.00	-	30	-	-	-	-	-					
61	4400	right	6	-	16	62	3400	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	4970	left	6	-	16	62	3510	right	6	-	16	9.33	-	34	-	-	-	-	-					
61	5050	right	10	4	16	62	3555	right	15	6	16	23.33	-	43	-	-	-	-	-					
62	269	right	6	-	16	62	3820	right	8	4	16	10.67	-	32	-	-	-	-	-					
62	280	right	6	-	16	62	3866	right	8	4	16	12.44	-	36	-	-	-	-	-					
62	466	right	10	4	16	62	3899	left	8	4	16	10.67	-	32	-	-	-	-	-					
62	510	right	30	12	16	62	4410	left	6	-	16	8.00	-	30	-	-	-	-	-					
62	650	left	6	-	16	62	4499	right	6	-	16	9.33	-	34	-	-	-	-	-					
62	744	right	8	4	16	62	4600	left	6	-	16	8.00	-	30	-	-	-	-	-					
62	880	right	6	-	16	62	4669	right	6	-	16	9.33	-	34	-	-	-	-	-					
62	910	right	30	12	16	62	4999	right	30	12	16	-	46.67	58	-	-	-	-	-					
62	1000	left	6	-	16	62	5140	right	15	6	16	23.33	-	43	-	-	-	-	-					
62	1130	left	6	-	16	63	500	left	6	-	16	8.00	-	30	-	-	-	-	-					
62	1277	right	6	-	16	63	569	left	8	4	16	10.67	-	32	-	-	-	-	-					
62	1315	right	30	12	16	63	700	left	6	-	16	8.00	-	30	-	-	-	-	-					
62	1380	right	15	6	16	63	840	right	6	-	16	9.33	-	34	-	-	-	-	-					
62	1590	right	45	18	16	63	888	left	6	-	16	8.00	-	30	-	-	-	-	-					
62	1730	right	6	-	16	63	940	right	6	-	16	9.33	-	34	-	-	-	-	-					
SUBTOTAL 9 =										140	704	374	428	1,664	SUBTOTAL 10 =									
										138	656	355	381	1,563										

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 14  
January 9, 2023

3

3

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 15  
January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

EB MILE MARKER	PLUS	SIDE	EASTBOUND LOCATION	LENGTH	416.0610		416.0620		416.1715		416.1725		690.0250	REMARKS
					DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY			
63	1111	left	6	6	-	16	8.00	-	-	9.33	-	-	34	
63	1150	left	6	6	-	16	8.00	-	-	8.00	-	-	30	
63	1177	right	30	58	12	16	-	46.67	-	8.00	-	-	58	
63	1220	left	6	6	-	16	8.00	-	-	9.33	-	-	30	
63	1320	left	6	6	-	16	8.00	-	-	9.33	-	-	30	
63	1400	left	6	6	-	16	8.00	-	-	9.33	-	-	30	
63	1480	right	30	58	12	16	-	46.67	-	9.33	-	-	58	
63	1555	right	15	43	6	16	23.33	-	-	8.00	-	-	43	
63	1944	right	6	34	-	16	9.33	-	-	23.33	-	-	34	
63	2030	left	6	30	-	16	8.00	-	-	-	-	-	30	
63	2069	right	6	34	-	16	9.33	-	-	-	-	-	34	
63	2400	left	6	30	-	16	8.00	-	-	-	-	-	30	
63	2477	right	6	34	-	16	9.33	-	-	12.44	-	-	34	
63	2666	right	6	34	-	16	9.33	-	-	12.44	-	-	34	
63	2850	left	6	30	-	16	8.00	-	-	12.44	-	-	30	
63	2900	left	6	30	-	16	8.00	-	-	15.56	-	-	30	
63	2999	right	6	34	-	16	9.33	-	-	-	-	-	34	
63	3150	right	6	34	-	16	9.33	-	-	9.33	-	-	34	
63	3277	right	6	34	-	16	9.33	-	-	23.33	-	-	34	
63	3333	right	6	34	-	16	9.33	-	-	23.33	-	-	34	
63	3488	right	15	43	6	16	23.33	-	-	-	-	-	43	
63	3630	both	6	58	-	32	17.33	-	-	15.56	-	-	58	
63	3850	left	6	30	-	16	8.00	-	-	9.33	-	-	30	
63	3940	right	45	73	18	16	-	70.00	-	15.56	-	-	73	
SUBTOTAL 11 =				54	400	219	163	905	146	640	419	327	1,571	

PROJECT NO: 1016-01-61

HWY: IH - 90

COUNTY: JUNEAU

MISCELLANEOUS QUANTITIES

SHEET: 15

FILE NAME: N:\PDS\1030200\_mq.ppk

PLOT DATE: February 22, 2022

PLOT BY: A.R.H.

PLOT NAME:

PLOT SCALE: 1:1



CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	WB MILE MARKER	MINUS	SIDE	WESTBOUND LOCATION	LENGTH	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS																
																				416.0610	416.0620	416.1715	416.1725	690.0250	416.0610	416.0620	416.1715	416.1725	690.0250						
71	1260	left	6	16	8.00	-	30		71	4030	right	6	6	-	16	9.33	-	34																	
71	1280	left	6	16	8.00	-	30		71	4200	left	6	6	-	16	8.00	-	34																	
71	1295	right	8	16	12.44	-	36		71	4250	left	6	6	-	16	8.00	-	30																	
71	1310	right	6	16	9.33	-	34		71	4325	left	6	6	-	16	8.00	-	30																	
71	1430	right	6	16	9.33	-	34		71	4390	left	6	6	-	16	8.00	-	30																	
71	1455	right	6	16	9.33	-	34		71	4405	right	15	15	6	16	23.33	-	43																	
71	1540	left	6	16	8.00	-	30		71	4435	right	6	6	-	16	9.33	-	34																	
71	1650	right	6	16	9.33	-	34		71	4625	both	6	6	-	32	17.33	-	58																	
71	1715	right	8	16	12.44	-	36		71	4660	right	6	6	-	16	9.33	-	34																	
71	1715	left	6	16	8.00	-	30		71	4675	left	6	6	-	16	8.00	-	30																	
71	1745	left	6	16	8.00	-	30		71	4685	left	6	6	-	16	8.00	-	30																	
71	1780	right	6	16	9.33	-	34		71	4815	left	6	6	-	16	8.00	-	34																	
71	1810	right	6	16	9.33	-	34		71	4865	right	6	6	-	16	9.33	-	30																	
71	1830	left	6	16	8.00	-	30		71	4885	left	6	6	-	16	8.00	-	30																	
71	1865	right	8	16	12.44	-	36		71	4930	left	6	6	-	16	8.00	-	30																	
71	1980	right	6	16	9.33	-	34		71	5050	right	75	75	30	16	-	116.67	103																	
71	2120	right	6	16	9.33	-	34		71	5225	right	6	6	-	16	9.33	-	34																	
71	2270	left	6	16	8.00	-	30		71	5250	right	6	6	-	16	9.33	-	34																	
71	2320	right	6	16	9.33	-	34		70	2185	right	30	30	12	16	-	46.67	58																	
71	2380	left	6	16	8.00	-	30		70	2270	right	6	6	-	16	9.33	-	34																	
71	2450	left	6	16	8.00	-	30		70	2290	right	6	6	-	16	9.33	-	34																	
71	2490	right	10	16	15.56	-	38		70	2365	right	6	6	-	16	9.33	-	34																	
71	2515	left	6	16	8.00	-	30		70	2430	right	6	6	-	16	9.33	-	30																	
71	2560	right	6	16	9.33	-	34		70	2740	left	6	6	-	16	8.00	-	34																	
71	2660	left	6	16	8.00	-	30		70	2875	right	6	6	-	16	9.33	-	34																	
71	2750	right	6	16	9.33	-	34		70	2960	right	6	6	-	16	9.33	-	34																	
71	2790	left	6	16	8.00	-	30		70	3050	left	6	6	-	16	8.00	-	30																	
71	2820	left	6	16	8.00	-	30		70	3040	left	6	6	-	16	8.00	-	30																	
71	2880	left	6	16	8.00	-	30		70	3180	left	6	6	-	16	8.00	-	30																	
71	2975	left	6	16	8.00	-	30		70	3200	right	6	6	-	16	9.33	-	34																	
71	3050	left	6	16	8.00	-	30		70	3440	right	6	6	-	16	9.33	-	34																	
71	3090	right	8	16	12.44	-	36		70	3460	right	6	6	-	16	9.33	-	34																	
71	3180	left	6	16	8.00	-	30		70	3610	right	6	6	-	16	9.33	-	34																	
71	3230	left	6	16	8.00	-	30		70	3880	right	6	6	-	16	9.33	-	34																	
71	3300	left	6	16	8.00	-	30		70	4330	right	6	6	-	16	9.33	-	34																	
71	3380	left	6	16	8.00	-	30		70	4800	right	6	6	-	16	9.33	-	34																	
71	3410	right	6	16	9.33	-	34		70	4810	right	6	6	-	16	9.33	-	34																	
71	3430	right	8	16	12.44	-	36		70	4960	left	6	6	-	16	9.33	-	34																	
71	3935	right	30	12	-	46.67	58		70	5220	left	6	6	-	16	8.00	-	30																	
71	4000	right	15	6	23.33	-	43		70	5230	right	6	6	-	16	9.33	-	34																	
SUBTOTAL 13 =													42	640	373	47	1327	SUBTOTAL 14 =													48	656	358	163	1430

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet 16  
 January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS							
																		CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY					
69	0	left	-	-	8.00	-	30		69	4550	right	4	16	12.44	-	36								
69	10	left	-	-	8.00	-	30		69	4625	right	4	16	9.33	-	34								
69	185	right	-	-	9.33	-	34		69	4735	right	4	16	12.44	-	36								
69	210	left	-	-	8.00	-	34		69	4925	right	-	16	9.33	-	34								
69	340	right	-	-	9.33	-	34		69	4980	right	-	16	9.33	-	34								
69	370	left	-	-	8.00	-	30		69	5105	right	18	16	-	70.00	73								
69	390	left	-	-	8.00	-	30		69	260	right	6	16	23.33	-	43								
69	640	left	-	-	8.00	-	30		69	370	left	6	16	8.00	-	30								
69	715	right	-	-	9.33	-	34		68	575	right	-	16	9.33	-	34								
69	740	left	-	-	8.00	-	30		68	600	left	-	16	8.00	-	30								
69	815	left	-	-	8.00	-	30		68	715	right	-	16	9.33	-	34								
69	850	left	-	-	8.00	-	30		68	800	left	-	16	8.00	-	30								
69	1110	both	-	-	17.33	-	58		68	880	right	-	16	9.33	-	34								
69	1150	right	-	-	9.33	-	34		68	920	right	-	16	9.33	-	34								
69	1165	right	-	-	9.33	-	34		68	940	right	-	16	9.33	-	34								
69	1185	both	-	-	17.33	-	58		68	960	right	-	16	9.33	-	34								
69	1200	left	-	-	8.00	-	30		68	1225	right	-	16	9.33	-	34								
69	1310	right	-	-	9.33	-	34		68	1490	right	-	16	9.33	-	34								
69	1380	right	-	-	9.33	-	34		68	1810	right	-	16	9.33	-	34								
69	1445	left	-	-	8.00	-	30		68	1855	right	-	16	9.33	-	34								
69	1460	left	-	-	8.00	-	30		68	1925	left	-	16	8.00	-	30								
69	1540	right	-	-	9.33	-	34		68	2115	right	6	16	23.33	-	43								
69	1560	right	-	-	9.33	-	34		68	2160	left	-	16	8.00	-	30								
69	1615	left	-	-	8.00	-	30		68	2240	left	-	16	8.00	-	30								
69	3060	right	20	8	-	31.11	48		68	2850	right	4	16	12.44	-	36								
69	3160	right	-	-	9.33	-	34		68	2875	right	4	16	12.44	-	36								
69	3310	right	-	-	9.33	-	34		68	2890	right	12	16	16	46.67	58								
69	3350	left	-	-	8.00	-	30		68	3590	left	6	16	8.00	-	30								
69	3420	right	20	8	-	31.11	48		68	3620	right	-	16	9.33	-	34								
69	3550	left	-	-	8.00	-	30		68	3715	left	-	16	8.00	-	30								
69	3590	right	-	-	9.33	-	34		68	3840	right	-	16	9.33	-	34								
69	3750	right	-	-	9.33	-	34		68	3880	left	-	16	8.00	-	30								
69	4070	left	-	-	8.00	-	30		68	3930	right	4	16	15.56	-	38								
69	4165	right	-	-	9.33	-	34		68	4190	right	-	16	9.33	-	34								
69	4240	right	-	-	9.33	-	34		68	4250	right	-	16	9.33	-	34								
69	4285	right	-	-	9.33	-	34		68	4360	right	-	16	9.33	-	34								
69	4345	right	-	-	9.33	-	34		68	4380	right	-	16	9.33	-	34								
69	4380	right	-	-	9.33	-	34		68	4460	right	-	16	9.33	-	34								
69	4430	left	4	4	10.67	-	32		68	4480	right	-	16	9.33	-	34								
69	4480	right	-	-	9.33	-	34		68	4650	left	-	16	8.00	-	30								
SUBTOTAL 15 =													20	672	351	62	1,370	SUBTOTAL 16 =		62	640	388	117	1,413

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet 17  
 January 9, 2023

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 18  
January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS					
																		WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH
68	4740	right	8	4	12.44	-	36		67	3930	left	6	16	8.00	-	30						
68	4780	left	6	16	8.00	-	30		67	4180	left	6	16	8.00	-	30						
68	4860	right	8	4	12.44	-	36		67	4290	left	6	16	8.00	-	30						
68	4975	left	6	16	8.00	-	30		67	4345	right	6	16	9.33	-	34						
68	5060	left	6	16	8.00	-	30		67	4375	left	6	16	8.00	-	30						
68	5100	left	6	16	8.00	-	30		67	4415	right	6	16	9.33	-	34						
67	55	right	6	16	9.33	-	34		67	4435	right	6	16	9.33	-	34						
67	175	left	6	16	8.00	-	30		67	4615	right	8	4	12.44	-	36						
67	310	right	6	16	9.33	-	34		67	4645	right	8	4	12.44	-	36						
67	350	left	6	16	8.00	-	30		67	4660	left	6	16	8.00	-	30						
67	575	left	6	16	8.00	-	30		67	4745	left	6	16	8.00	-	30						
67	670	right	8	4	12.44	-	36		67	4770	right	6	16	9.33	-	34						
67	1015	right	8	4	12.44	-	36		67	4790	left	6	16	8.00	-	30						
67	1115	right	6	16	9.33	-	34		67	4970	right	6	16	9.33	-	34						
67	1260	right	6	16	9.33	-	34		67	5080	right	6	16	9.33	-	34						
67	1615	left	6	16	8.00	-	30		66	65	left	6	16	8.00	-	30						
67	1695	right	6	16	8.00	-	30		66	340	left	6	16	8.00	-	30						
67	1795	right	20	8	31.11	-	48		66	485	right	6	16	9.33	-	34						
67	2020	left	8	4	10.67	-	32		66	545	right	6	16	9.33	-	34						
67	2135	right	6	16	9.33	-	34		66	685	right	6	16	9.33	-	34						
67	2210	right	6	16	9.33	-	34		66	760	left	6	16	8.00	-	30						
67	2230	left	6	16	8.00	-	30		66	950	left	6	16	8.00	-	30						
67	2305	right	6	16	9.33	-	34		66	1045	left	6	16	8.00	-	30						
67	2745	right	45	18	70.00	-	73		66	1100	right	6	16	9.33	-	34						
67	2830	right	6	16	9.33	-	34		66	1275	right	6	16	9.33	-	34						
67	2845	left	6	16	8.00	-	30		66	1340	left	6	16	8.00	-	30						
67	2870	left	6	16	8.00	-	30		66	1610	right	6	16	9.33	-	34						
67	3060	left	6	16	8.00	-	30		66	1660	right	6	16	9.33	-	34						
67	3105	right	6	16	9.33	-	34		66	1710	right	6	16	9.33	-	34						
67	3325	left	6	16	8.00	-	30		66	1750	right	6	16	9.33	-	34						
67	3505	left	6	16	8.00	-	30		66	1780	left	6	16	8.00	-	30						
67	3550	right	6	16	9.33	-	34		66	2250	right	8	4	12.44	-	36						
67	3560	both	6	32	17.33	-	58		66	2250	left	6	16	8.00	-	30						
67	3585	left	6	16	8.00	-	30		66	2320	right	6	16	9.33	-	34						
67	3600	left	6	16	8.00	-	30		66	2495	right	6	16	9.33	-	34						
67	3610	right	6	16	9.33	-	34		66	2540	right	6	16	9.33	-	34						
67	3630	right	6	16	9.33	-	34		66	2570	left	6	16	8.00	-	30						
67	3800	left	6	16	8.00	-	30		66	2665	right	6	16	9.33	-	34						
67	3820	right	6	16	9.33	-	34		66	2800	right	6	16	9.33	-	34						
67	3875	right	6	16	9.33	-	34		66	2935	left	6	16	8.00	-	30						
SUBTOTAL 17 =										46	656		352	101	1371	SUBTOTAL 18 =		12	640	360	0	1,298

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 19  
January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	CONCRETE REPAIR SUMMARY (CONTINUED)				REMARKS		
									416.0610	416.0620	416.1715	416.1725			
66	3100	right	6	16	9.33	-	34		416.0610	416.0620	416.1715	416.1725	690.0250		
66	3160	right	6	16	9.33	-	34		-	16	8.00	-	-	30	
66	3230	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
66	3710	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
66	3745	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
66	3870	right	45	16	-	70.00	73		-	16	9.33	-	-	34	
66	3930	both	6	32	17.33	-	58		-	16	9.33	-	-	34	
66	4105	right	6	16	9.33	-	34		-	16	9.33	-	-	34	
66	4190	left	6	16	8.00	-	30		4	16	10.67	-	-	32	
66	4265	right	6	16	9.33	-	34		18	16	-	70.00	-	73	
66	4540	right	6	16	9.33	-	34		-	16	8.00	-	-	30	
66	5175	left	6	16	8.00	-	30		4	16	12.44	-	-	36	
65	10	left	6	16	8.00	-	30		-	16	8.00	-	-	30	
65	295	right	15	6	16	23.33	43		-	16	9.33	-	-	34	
65	395	right	15	6	16	23.33	43		-	32	17.33	-	-	58	
65	650	right	20	8	16	-	48		4	16	12.44	-	-	36	
65	770	left	6	16	8.00	31.11	30		-	16	9.33	-	-	34	
65	950	right	8	4	16	12.44	36		-	16	9.33	-	-	34	
65	1000	left	6	16	8.00	-	30		4	16	15.56	-	-	38	
65	1070	right	10	4	16	15.56	38		4	16	12.44	-	-	36	
65	1145	left	6	16	8.00	-	30		-	16	8.00	-	-	30	
65	1210	right	6	16	9.33	-	34		-	16	8.00	-	-	30	
65	1230	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
65	1265	left	6	16	8.00	-	30		24	16	-	93.33	-	88	
65	1295	right	6	16	9.33	-	34		4	16	12.44	-	-	36	
65	1340	left	6	16	8.00	-	30		4	16	10.67	-	-	32	
65	1365	right	6	16	9.33	-	34		-	16	8.00	-	-	30	
65	1530	right	15	6	16	23.33	43		-	16	9.33	-	-	34	
65	1530	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
65	1735	left	6	16	8.00	-	30		-	16	8.00	-	-	30	
65	1940	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
65	2045	left	6	16	8.00	-	30		4	16	12.44	-	-	36	
65	2120	right	8	4	16	12.44	36		-	16	9.33	-	-	34	
65	2220	right	6	16	9.33	-	34		4	16	12.44	-	-	36	
65	2255	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
65	2555	right	6	16	9.33	-	34		-	16	8.00	-	-	30	
65	2675	left	6	16	8.00	-	30		-	16	9.33	-	-	34	
65	2685	right	6	16	9.33	-	34		-	16	9.33	-	-	34	
65	2860	right	6	16	9.33	-	34		4	16	10.67	-	-	32	
65	3000	right	6	16	9.33	-	34		-	16	9.33	-	-	34	
SUBTOTAL 19 =									56	656	393	101	1,400		
SUBTOTAL 20 =									82	656	382	163	1,459		

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	CONCRETE REPAIR SUMMARY (CONTINUED)					REMARKS
									416.0610	416.0620	416.1715	416.1725	690.0250	
64	2230	both	-	32	17.33	-	58		416.0610	416.0620	416.1715	416.1725	690.0250	
64	2305	both	-	32	17.33	-	58		-	-	17.33	-	-	58
64	2370	left	-	16	8.00	-	30		-	-	17.33	-	-	58
64	2440	left	-	16	8.00	-	30		-	-	8.00	-	-	30
64	2510	both	-	32	17.33	-	58		-	-	9.33	-	-	34
64	2780	right	-	16	9.33	-	34		-	-	-	46.67	-	58
64	2840	left	-	16	8.00	-	30		-	-	8.00	-	-	30
64	3150	right	-	16	9.33	-	34		-	-	12.44	-	-	36
64	3480	right	-	16	9.33	-	34		-	-	23.33	-	-	43
64	3540	left	-	16	8.00	-	30		-	-	9.33	-	-	34
64	3575	right	-	16	9.33	-	34		-	-	9.33	-	-	34
64	3700	left	-	16	8.00	-	30		-	-	8.00	-	-	30
64	3765	right	-	16	9.33	-	34		-	-	8.00	-	-	30
64	3900	left	-	16	8.00	-	30		-	-	9.33	-	-	34
64	3950	right	4	16	12.44	-	36		-	-	9.33	-	-	34
64	4010	left	-	16	8.00	-	30		-	-	-	70.00	-	73
64	4050	left	-	16	8.00	-	30		-	-	8.00	-	-	30
64	4245	right	-	16	9.33	-	34		-	-	9.33	-	-	34
64	4285	left	-	16	8.00	-	30		-	-	9.33	-	-	34
64	4355	left	-	16	8.00	-	30		-	-	23.33	-	-	43
64	4425	left	-	16	8.00	-	30		-	-	12.44	-	-	36
64	4515	right	-	16	9.33	-	34		-	-	8.00	-	-	30
64	4685	right	-	16	9.33	-	34		-	-	9.33	-	-	34
64	4740	left	-	16	8.00	-	30		-	-	8.00	-	-	30
64	5005	left	-	16	8.00	-	30		-	-	-	31.11	-	48
64	5100	left	-	16	8.00	-	30		-	-	9.33	-	-	34
64	5145	left	-	16	8.00	-	30		-	-	8.00	-	-	30
63	280	left	-	16	8.00	-	30		-	-	9.33	-	-	34
63	350	right	-	16	9.33	-	34		-	-	9.33	-	-	34
63	740	left	-	16	8.00	-	30		-	-	-	31.11	-	48
63	1260	left	-	16	8.00	-	30		-	-	9.33	-	-	34
63	1450	right	-	16	9.33	-	34		-	-	23.33	-	-	43
63	1520	right	-	16	9.33	-	34		-	-	8.00	-	-	30
63	1550	right	-	16	9.33	-	34		-	-	9.33	-	-	34
63	1600	right	-	16	9.33	-	34		-	-	12.44	-	-	36
63	1750	right	-	16	9.33	-	34		-	-	8.00	-	-	30
63	1850	left	4	16	10.67	-	32		-	-	9.33	-	-	34
63	2000	left	-	16	8.00	-	30		-	-	8.00	-	-	30
63	2040	left	-	16	8.00	-	30		-	-	8.00	-	-	30
63	2060	left	-	16	8.00	-	30		-	-	8.00	-	-	30
SUBTOTAL 21 =									8	688	374	0	1,348	
SUBTOTAL 22 =									76	672	386	179	1,480	

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet 20  
 January 9, 2023

PROJECT NO: 1016-01-61

HWY: IH - 90

COUNTY: JUNEAU

MISCELLANEOUS QUANTITIES

SHEET: 20

E

FILE NAME: N:\PDS\1030200\_mq.ppk

PLOT DATE: February 22, 2022

PLOT BY: A.R.H.

PLOT NAME: 11

CONCRETE REPAIR SUMMARY (CONTINUED)

CONCRETE REPAIR SUMMARY (CONTINUED)

WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOVCEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	WB MILE MARKER	MINUS	SIDE	WESTBOUND LOCATION	LENGTH	DRILLED TIE BARS EACH	DRILLED DOVCEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS					
																				416.0610	416.0620	416.1715	416.1725	690.0250
62	1580	both	-	32	17.33	-	58		60	2488	right	45	18	16	-	-	70.00	73						
62	1800	left	-	16	8.00	-	30		60	2488	left	6	-	16	8.00	-	-	30						
62	2166	left	-	16	8.00	-	30		60	2515	right	8	4	16	12.44	-	-	36						
62	2269	both	-	32	17.33	-	58		60	2515	left	15	6	16	20.00	-	-	39						
62	2340	right	6	16	23.33	-	43		60	2550	right	45	18	16	-	70.00	-	73						
62	2480	right	4	16	12.44	-	36		60	2588	right	12	5	16	18.67	-	-	40						
62	3950	right	6	16	9.33	-	34		60	2600	right	30	12	16	-	46.67	-	58						
62	4140	right	6	16	9.33	-	34		60	2680	left	6	4	16	8.00	-	-	30						
62	4600	left	-	16	8.00	-	30		60	2700	left	8	4	16	10.67	-	-	32						
62	4900	left	-	16	8.00	-	30		60	2767	left	6	-	16	8.00	-	-	30						
62	5080	left	-	16	8.00	-	30		60	2800	right	15	6	16	23.33	-	-	43						
61	370	left	-	16	8.00	-	30		60	2860	left	6	-	16	8.00	-	-	30						
61	730	left	-	16	8.00	-	30		60	2929	left	6	-	16	8.00	-	-	30						
61	940	right	6	16	23.33	-	43		60	3000	left	6	-	16	8.00	-	-	30						
61	1160	left	-	16	8.00	-	30		60	3100	left	6	-	16	8.00	-	-	30						
61	2900	right	8	16	12.44	-	36		60	3120	left	6	-	16	8.00	-	-	30						
61	3880	left	-	16	8.00	-	30		60	3150	left	6	-	16	8.00	-	-	30						
61	3970	left	-	16	8.00	-	30		60	3190	right	15	6	16	23.33	-	-	43						
61	4030	left	-	16	8.00	-	30		60	3269	right	15	6	16	23.33	-	-	43						
61	4270	right	-	16	9.33	-	34		60	3420	right	75	30	16	-	116.67	-	103						
61	4405	left	-	16	8.00	-	30		60	3520	left	6	-	16	8.00	-	-	30						
61	4777	right	6	16	9.33	-	34		60	3777	right	6	-	16	9.33	-	-	34						
60	69	left	-	16	8.00	-	30		60	3888	right	6	-	16	9.33	-	-	34						
60	160	right	15	6	23.33	-	43		60	3977	right	30	12	16	-	46.67	-	58						
60	330	left	-	16	8.00	-	30		60	4088	right	30	12	16	-	46.67	-	58						
60	530	right	30	12	-	46.67	58		60	4120	left	6	-	16	8.00	-	-	30						
60	666	right	75	30	116.67	103	103		60	4300	right	30	12	16	-	46.67	-	58						
60	820	right	60	24	-	93.33	88		60	4380	left	6	-	16	8.00	-	-	30						
60	969	right	120	48	-	186.67	148		60	4400	left	6	-	16	8.00	-	-	30						
60	1244	left	6	16	8.00	-	30		60	4500	right	15	6	16	23.33	-	-	43						
60	1244	right	30	12	-	46.67	58		60	4570	left	6	-	16	8.00	-	-	30						
60	1300	right	25	10	-	38.89	53		60	4600	right	30	12	16	-	46.67	-	58						
60	1320	right	15	6	23.33	-	43		60	4720	left	6	-	16	8.00	-	-	30						
60	1350	right	25	10	-	38.89	53		60	4810	right	15	6	16	23.33	-	-	43						
60	1388	right	10	4	15.56	-	38		60	4990	right	20	8	16	-	31.11	-	48						
60	1750	right	90	36	-	140.00	118		60	5100	left	6	-	16	8.00	-	-	30						
60	2188	right	6	16	9.33	-	34		60	5120	right	6	-	16	9.33	-	-	34						
60	2269	left	-	16	8.00	-	30		60	5240	right	15	6	16	23.33	-	-	43						
60	2269	right	30	12	-	46.67	58		60	5320	right	15	6	16	23.33	-	-	43						
60	2350	right	12	5	18.67	-	40		60	5320	right	15	6	16	23.33	-	-	43						
SUBTOTAL 23 =										235	672	362	754	1825	SUBTOTAL 24 =					201	640	404	521	1,660

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 21  
January 9, 2023

CONCRETE REPAIR SUMMARY (CONTINUED)													CONCRETE REPAIR SUMMARY (CONTINUED)																														
WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS	WB MILE MARKER	MINUS	WESTBOUND LOCATION	DRILLED TIE BARS EACH	DRILLED DOWEL BARS EACH	CONCRETE PAVEMENT REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	REMARKS																										
58	400	both	6	32	17.33	-	58		57	1560	right	6	16	23.33	-	43																											
58	500	right	15	16	23.33	-	43		57	1650	right	6	16	9.33	-	34																											
58	1080	right	6	16	9.33	-	34		57	1888	right	6	16	9.33	-	34																											
58	1177	right	10	4	15.56	-	38		57	2000	left	6	16	8.00	-	30																											
58	1380	right	6	16	9.33	-	34		57	2260	left	6	16	8.00	-	30																											
58	1577	left	6	16	8.00	-	30		57	2500	right	6	16	9.33	-	34																											
58	1600	left	6	16	8.00	-	30		57	2700	left	6	16	8.00	-	30																											
58	1790	right	6	16	9.33	-	34		57	2940	right	6	16	23.33	-	43																											
58	1810	right	6	16	9.33	-	34		57	3020	left	6	16	8.00	-	30																											
58	2020	right	6	16	9.33	-	34		57	3040	left	6	16	8.00	-	30																											
58	2600	right	6	16	9.33	-	34		57	3390	right	6	16	9.33	-	34																											
58	3050	right	6	16	9.33	-	34		57	3790	right	6	16	9.33	-	34																											
58	3500	right	6	16	9.33	-	34		57	3920	left	6	16	8.00	-	30																											
58	4000	right	15	6	23.33	-	43		57	4190	right	6	16	9.33	-	34																											
58	4100	right	12	5	18.67	-	40		57	4390	right	8	4	12.44	-	36																											
58	4150	right	15	6	23.33	-	43		57	4415	right	15	6	16	23.33	-	43																										
58	4200	right	15	6	23.33	-	43		57	4450	right	8	4	16	12.44	-	36																										
58	4444	right	6	16	9.33	-	34		57	4800	right	15	6	16	23.33	-	43																										
58	4800	right	6	16	9.33	-	34		56	22	left	6	16	8.00	-	30																											
58	4830	right	15	6	23.33	-	43		56	60	left	6	16	8.00	-	30																											
58	4940	left	6	16	8.00	-	30		56	180	right	40	16	62.22	-	68																											
58	4950	right	10	4	15.56	-	38		56	380	right	6	16	9.33	-	34																											
58	5120	right	6	16	9.33	-	34		56	899	left	6	16	8.00	-	30																											
58	5200	right	6	16	9.33	-	34		56	933	right	20	8	31.11	-	48																											
57	10	right	10	4	15.56	-	38		56	1080	left	6	16	8.00	-	30																											
57	20	left	6	16	8.00	-	30		56	1250	right	6	16	9.33	-	34																											
57	50	left	6	16	8.00	-	30		56	1380	right	15	6	23.33	-	43																											
57	120	right	8	4	12.44	-	36		56	1490	right	6	16	9.33	-	34																											
57	450	right	6	16	9.33	-	34		56	1555	right	30	12	46.67	-	58																											
57	500	left	6	16	8.00	-	30		56	1610	left	6	16	8.00	-	30																											
57	570	left	6	16	8.00	-	30		56	1820	both	20	8	57.78	-	72																											
57	669	right	10	4	15.56	-	38																																				
57	860	right	10	4	15.56	-	38																																				
57	940	right	15	6	23.33	-	43																																				
57	990	left	6	16	8.00	-	30																																				
57	1020	right	6	16	9.33	-	34																																				
57	1100	right	8	4	12.44	-	36																																				
57	1220	right	30	12	46.67	-	58																																				
57	1260	right	30	12	46.67	-	58																																				
57	1390	right	6	16	9.33	-	34																																				
SUBTOTAL 25 =																	93	656	483	93	1,484	SUBTOTAL 26 =																	482	832	470	648	3,669

Addendum No. 02  
 ID 1016-01-61  
 Revised Sheet 22  
 January 9, 2023

Addendum No. 02  
ID 1016-01-61  
Revised Sheet 23  
January 9, 2023

CONCRETE REPAIR SUMMARY (TOTALS)		416-0620		416-1715		416-1725		690.0250		REMARKS
DRILLED TIE BARS EACH	DRILLED DOOR BARS EACH	CONCRETE REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	SAWING CONCRETE LF	SAWING CONCRETE LF		
SUBTOTAL 1	382	640	276	1,283	2,097	2,164	2,164	2,164	EASTBOUND	
SUBTOTAL 2	395	656	330	1,431	2,164	1,927	1,927	1,927		
SUBTOTAL 3	281	656	330	964	1,927	1,633	1,633	1,633		
SUBTOTAL 4	153	672	401	397	1,633	1,985	1,985	1,985		
SUBTOTAL 5	281	688	365	902	1,985	1,706	1,706	1,706		
SUBTOTAL 6	177	656	310	607	1,706	1,880	1,880	1,880		
SUBTOTAL 7	265	640	275	941	1,880	1,869	1,869	1,869		
SUBTOTAL 8	211	720	315	723	1,869	1,664	1,664	1,664		
SUBTOTAL 9	140	704	374	428	1,664	1,563	1,563	1,563		
SUBTOTAL 10	138	656	355	381	1,563	905	905	905		
SUBTOTAL 11	54	400	219	163	327	1,571	1,571	1,571		
SUBTOTAL 12	146	640	419	327	1,571	1,327	1,327	1,327		
SUBTOTAL 13	42	640	373	47	1,327	1,430	1,430	1,430		
SUBTOTAL 14	48	656	358	163	1,430	1,370	1,370	1,370		
SUBTOTAL 15	20	672	351	62	1,370	1,413	1,413	1,413		
SUBTOTAL 16	62	640	388	117	1,413	1,371	1,371	1,371		
SUBTOTAL 17	46	656	352	101	1,371	1,298	1,298	1,298		
SUBTOTAL 18	12	640	360	0	1,298	1,400	1,400	1,400		
SUBTOTAL 19	56	656	393	101	1,400	1,459	1,459	1,459		
SUBTOTAL 20	82	656	382	163	1,459	1,348	1,348	1,348		
SUBTOTAL 21	8	688	374	0	1,348	1,480	1,480	1,480		
SUBTOTAL 22	76	672	386	179	1,480	1,825	1,825	1,825		
SUBTOTAL 23	235	640	404	521	1,825	1,660	1,660	1,660		
SUBTOTAL 24	201	640	404	521	1,660	1,484	1,484	1,484		
SUBTOTAL 25	93	656	483	93	1,484	648	648	648		
SUBTOTAL 26	482	832	470	648	648	3,669	3,669	3,669		
TOTAL 0010	4,086	17,104	9,306	11,498	43,498					

ASPHALT AND SHOULDER SUMMARY		204.0120		305.0110		415.6000S		455.0605		460.5224		460.7624		465.0400		624.0100		
REMOVING ASPHALTIC SURFACE MILLING	SY	SEAL	TON	ROUT AND DENSE 3/4-INCH	TON	BASE AGGREGATE	TON	HMA PAVEMENT 4 LT 58-28 S	TON	HMA PAVEMENT 4 HT 58-28 V	TON	SHOULDER RUMBLE STRIPS	LF	ASPHALTIC	LF	WATER	M GAL	
235+11 - EB Inside	30,800	46,249	1,000	46,249	-	4,100	-	4,100	-	-	-	46,249	100	-	46,249	100	-	-
235+11 - EB Outside	41,100	46,249	1,000	46,249	-	8,100	-	8,100	-	-	-	46,249	150	-	46,249	150	-	-
235+01A - WB Inside	58,200	87,263	1,900	87,263	-	7,700	-	7,700	-	-	-	87,263	150	-	87,263	150	-	-
235+01A - WB Outside	77,600	87,263	1,900	87,263	-	15,300	-	15,300	-	-	-	87,263	250	-	87,263	250	-	-
574+00 - EB ON RAMP GORE AREA	400	-	-	200	-	50	-	50	-	-	-	200	-	-	200	-	-	-
588+50 - EB OFF RAMP GORE AREA	570	-	-	300	-	60	-	60	-	-	-	300	-	-	300	-	-	-
570+00A - WB OFF RAMP GORE AREA	1,260	-	-	700	-	130	-	130	-	-	-	700	-	-	700	-	-	-
590+00A - WB ON RAMP GORE AREA	570	-	-	300	-	60	-	60	-	-	-	300	-	-	300	-	-	-
1170+50A - Pavement Repair Section	500	-	-	-	-	-	-	-	-	90	200	-	-	-	200	-	-	-
TOTAL 0010	211,000	268,524	5,800	268,524	32	35,500	90	35,500	90	2,687,24	650							

EROSION CONTROL SUMMARY		628.1910		628.2004		630.0120		630.0130		630.0200		630.0200	
MOBILIZATIONS EMERGENCY	EACH	MOBILIZATIONS EROSION MAT CLASS I TYPE B	SY	EROSION CONTROL CLASS I TYPE B	EACH	FERTILIZER TYPE B NO. 20	LB	SEEDING MIXTURE NO. 30	LB	SEEDING MIXTURE TEMPORARY	LB	SEEDING	LB
UNDISTRIBUTED	2	2	500	2	2	1	1	3	3				
TOTAL 0010	2	2	500	2	2	1	1	3	3				

CONCRETE REPAIR SUMMARY (TOTALS)		416-0620		416-1715		416-1725		690.0250		REMARKS
DRILLED TIE BARS EACH	DRILLED DOOR BARS EACH	CONCRETE REPAIR SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	CONCRETE PAVEMENT REPLACEMENT SHES SY	SAWING CONCRETE LF	SAWING CONCRETE LF	SAWING CONCRETE LF		
SUBTOTAL 1	382	640	276	1,283	2,097	2,164	2,164	2,164	EASTBOUND	
SUBTOTAL 2	395	656	330	1,431	2,164	1,927	1,927	1,927		
SUBTOTAL 3	281	656	330	964	1,927	1,633	1,633	1,633		
SUBTOTAL 4	153	672	401	397	1,633	1,985	1,985	1,985		
SUBTOTAL 5	281	688	365	902	1,985	1,706	1,706	1,706		
SUBTOTAL 6	177	656	310	607	1,706	1,880	1,880	1,880		
SUBTOTAL 7	265	640	275	941	1,880	1,869	1,869	1,869		
SUBTOTAL 8	211	720	315	723	1,869	1,664	1,664	1,664		
SUBTOTAL 9	140	704	374	428	1,664	1,563	1,563	1,563		
SUBTOTAL 10	138	656	355	381	1,563	905	905	905		
SUBTOTAL 11	54	400	219	163	327	1,571	1,571	1,571		
SUBTOTAL 12	146	640	419	327	1,571	1,327	1,327	1,327		
SUBTOTAL 13	42	640	373	47	1,327	1,430	1,430	1,430		
SUBTOTAL 14	48	656	358	163	1,430	1,370	1,370	1,370		
SUBTOTAL 15	20	672	351	62	1,370	1,413	1,413	1,413		
SUBTOTAL 16	62	640	388	117	1,413	1,371	1,371	1,371		
SUBTOTAL 17	46	656	352	101	1,371	1,298	1,298	1,298		
SUBTOTAL 18	12	640	360	0	1,298	1,400	1,400	1,400		
SUBTOTAL 19	56	656	393	101	1,400	1,459	1,459	1,459		
SUBTOTAL 20	82	656	382	163	1,459	1,348	1,348	1,348		
SUBTOTAL 21	8	688	374	0	1,348	1,480	1,480	1,480		
SUBTOTAL 22	76	672	386	179	1,480	1,825	1,825	1,825		
SUBTOTAL 23	235	640	404	521	1,825	1,660	1,660	1,660		
SUBTOTAL 24	201	640	404	521	1,660	1,484	1,484	1,484		
SUBTOTAL 25	93	656	483	93	1,484	648	648	648		
SUBTOTAL 26	482	832	470	648	648	3,669	3,669	3,669		
TOTAL 0010	4,086	17,104	9,306	11,498	43,498					

PROJECT NO: 1016-01-61  
HWY: IH - 90  
COUNTY: JUNEAU  
MISCELLANEOUS QUANTITIES  
SHEET: 23

Plot Name: A.R.H.  
Plot Scale: 1:1  
Plot Date: February 22, 2022  
File Name: N:\PDS\1030200\_mq.ppk





Proposal Schedule of Items

Proposal ID: 20230110002 Project(s): 1016-01-61

Federal ID(s): WISC 2023135

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0120 Removing Asphaltic Surface Milling	211,000.000 SY	_____.	_____.
0004	204.0170 Removing Fence	164,210.000 LF	_____.	_____.
0006	211.0400 Prepare Foundation for Asphaltic Shoulders	2,672.000 STA	_____.	_____.
0008	213.0100 Finishing Roadway (project) 01. 1016-01-61	1.000 EACH	_____.	_____.
0010	305.0110 Base Aggregate Dense 3/4-Inch	5,800.000 TON	_____.	_____.
0012	415.6000.S Rout and Seal	268,524.000 LF	_____.	_____.
0014	416.0610 Drilled Tie Bars	4,086.000 EACH	_____.	_____.
0016	416.0620 Drilled Dowel Bars	17,104.000 EACH	_____.	_____.
0018	416.1715 Concrete Pavement Repair SHES	9,306.000 SY	_____.	_____.
0020	416.1725 Concrete Pavement Replacement SHES	11,498.000 SY	_____.	_____.
0022	455.0605 Tack Coat	32.000 GAL	_____.	_____.
0024	460.2000 Incentive Density HMA Pavement	22,530.000 DOL	1.00000	22,530.00
0026	460.5224 HMA Pavement 4 LT 58-28 S	35,500.000 TON	_____.	_____.
0028	460.7624 HMA Pavement 4 HT 58-28 V	90.000 TON	_____.	_____.
0030	465.0400 Asphaltic Shoulder Rumble Strips	268,724.000 LF	_____.	_____.
0032	616.0100 Fence Woven Wire (height) 01. 4-FT	164,210.000 LF	_____.	_____.

