



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

January 3, 2023

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #35: 7125-00-71
Alma – Mondovi
Branch Trout Creek Bridge B-06-0207
STH 37
Buffalo County

Letting of January 10, 2023

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Excavation Common	CY	2,057	299	2,356

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
208.0100	Borrow	CY	479	-479	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
15	Miscellaneous Quantities revised quantity of Excavation Common and delete Borrow.
86	Earthwork Summary - revised earthwork summary tables

Schedule of Items

Attached, dated January 3, 2023, are the revised Schedule of Items Pages 1 – 6.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 15 & 86.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

CLEARING AND GRUBBING

CLEARING GRUBBING
201.0105 201.0205

CATEGORY	STATION	TO	STATION	LOCATION	STA	STA	REMARKS
0010	543+25	-	546+60	STH 37 LT	3	3	TEMP BYPASS CONSTRUCTION

PROJECT TOTALS = 3 3

REMOVING GUARDRAIL

CATEGORY	STATION	TO	STATION	LOCATION	204.0165 LF	REMARKS
0010	540+05	-	545+00	LT/RT	990	
0010	545+50	-	546+82	LT	132.0	
0010	545+50	-	101+16.5 SL	RT	166.0	

PROJECT TOTALS = 1,288

EXCAVATION SUMMARY

CATEGORY	STATION	TO	STATION	LOCATION	EXCAVATION COMMON 205.0100 CY	BREAKER RUN 311.0110 TON	REMARKS
0010	10+75	-	13+25	TEMP BYPASS	29	2,421	BYPASS CONSTRUCTION
0010	540+00	-	547+75	STH 37	982	-	STH 37 CONSTRUCTION
0010	10+75	-	13+25	TEMP BYPASS	1,345	-	REMOVING BYPASS

PROJECT TOTALS = 2,356 2,421

PREPARE FOUNDATION FOR ASPHALTIC PAVING (PROJECT) 01. 7125-00-71

CATEGORY	LOCATION	211.0101 EACH	REMARKS
0010	PROJECT 7125-00-71	1	

PROJECT TOTALS = 1

FINISHING ROADWAY (PROJECT) 01. 7125-00-71

CATEGORY	LOCATION	213.0100 EACH	REMARKS
0010	PROJECT 7125-00-71	1	

PROJECT TOTALS = 1

Addendum No. 01
ID 7125-00-71
Revised Sheet 15
January 3, 2023

Addendum No. 01
ID 7125-00-71
Revised Sheet 86
January 3, 2023

STATION	REAL STATION	DISTANCE	AREA (SF)				INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)								
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	MARSH ETC	ROCK ETC	ROCK ETC	EB	MARSH ETC	ROCK ETC	EB	EXPANDED MARSH BACKFILL	EXPANDED ROCK BACKFILL	EXPANDED EBS BACKFILL	REDUCED MARSH IN FILL	REDUCED EBS IN FILL	MASS ORDINATE	
			NOTE 1	NOTE 2	NOTE 3	NOTE 4	NOTE 5	NOTE 6	NOTE 7	NOTE 8	NOTE 9	NOTE 10	NOTE 11	NOTE 12	NOTE 13	NOTE 14	NOTE 15	NOTE 16	
10+50	1050.00	0.00	4.18	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11+00	1100.00	50.00	2.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11+50	1150.00	50.00	1.83	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
12+00	1200.00	50.00	2.84	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
12+35	1235.00	35.00	0.06	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
TEMP STRUCTURE																			
12+65	1265.00	30.00	2.47	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
13+00	1300.00	35.00	1.08	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
13+50	1350.00	50.00	4.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
14+00	1400.00	50.00	0.58	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

STATION	REAL STATION	DISTANCE	AREA (SF)				INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)								
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	MARSH ETC	ROCK ETC	ROCK ETC	EB	MARSH ETC	ROCK ETC	EB	EXPANDED MARSH BACKFILL	EXPANDED ROCK BACKFILL	EXPANDED EBS BACKFILL	REDUCED MARSH IN FILL	REDUCED EBS IN FILL	MASS ORDINATE	
			NOTE 1	NOTE 2	NOTE 3	NOTE 4	NOTE 5	NOTE 6	NOTE 7	NOTE 8	NOTE 9	NOTE 10	NOTE 11	NOTE 12	NOTE 13	NOTE 14	NOTE 15	NOTE 16	
5450+01	5450.00	0.00	18.93	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+02	5450.00	50.00	24.71	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+03	5450.00	50.00	19.83	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+04	5450.00	50.00	43.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+05	5450.00	50.00	32.38	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+06	5450.00	50.00	23.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+07	5450.00	50.00	22.22	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+08	5450.00	50.00	19.84	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+09	5450.00	50.00	11.12	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+10	5450.00	50.00	8.13	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5450+11	5450.00	50.00	32.97	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
544485+25	544485.25	35.25	3.97	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
545454+25	545454.25	0.00	15.39	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
54500+00	54500.00	45.75	41.62	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
54500+01	54500.00	50.00	38.64	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
54500+02	54500.00	50.00	15.16	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
54500+03	54500.00	50.00	41.53	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

- 1- CUT (DOES NOT INCLUDE SALVAGED PAVEMENT MATERIAL)
- 2- SALVAGED/UNUSABLE PAVEMENT MATERIAL (THIS DOES NOT SHOW UP IN CROSS SECTIONS)
- 3- FILL
- 4- EXPANDED MARSH BACKFILL
- 5- EXPANDED ROCK BACKFILL
- 6- EXPANDED EBS
- 7- REDUCED MARSH IN FILL
- 8- REDUCED EBS IN FILL
- 9- MASS ORDINATE
- 10- MASS ORDINATE
- 11- MASS ORDINATE
- 12- MASS ORDINATE
- 13- MASS ORDINATE
- 14- MASS ORDINATE
- 15- MASS ORDINATE
- 16- MASS ORDINATE



Proposal Schedule of Items

Proposal ID: 20230110035 Project(s): 7125-00-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	3.000 STA	_____.	_____.
0004	201.0205 Grubbing	3.000 STA	_____.	_____.
0006	203.0211.S Abatement of Asbestos Containing Material (structure) 01. B-06-0896	1.000 EACH	_____.	_____.
0008	203.0260 Removing Structure Over Waterway Minimal Debris (structure) 01. B-06-0896	1.000 EACH	_____.	_____.
0010	204.0165 Removing Guardrail	1,288.000 LF	_____.	_____.
0012	205.0100 Excavation Common	2,356.000 CY	_____.	_____.
0014	206.1001 Excavation for Structures Bridges (structure) 01. B-06-0207	1.000 EACH	_____.	_____.
0018	210.1500 Backfill Structure Type A	292.000 TON	_____.	_____.
0020	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 7125-00-71	1.000 EACH	_____.	_____.
0022	213.0100 Finishing Roadway (project) 01. 7125-00-71	1.000 EACH	_____.	_____.
0024	305.0110 Base Aggregate Dense 3/4-Inch	227.000 TON	_____.	_____.
0026	305.0120 Base Aggregate Dense 1 1/4-Inch	2,928.000 TON	_____.	_____.
0028	311.0110 Breaker Run	2,421.000 TON	_____.	_____.
0030	455.0605 Tack Coat	191.000 GAL	_____.	_____.
0032	460.2000 Incentive Density HMA Pavement	600.000 DOL	1.00000	600.00



Proposal Schedule of Items

Proposal ID: 20230110035 Project(s): 7125-00-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	460.6244 HMA Pavement 4 MT 58-34 S	934.000 TON	_____.	_____.
0036	465.0125 Asphaltic Surface Temporary	131.000 TON	_____.	_____.
0038	465.0315 Asphaltic Flumes	12.000 SY	_____.	_____.
0040	502.0100 Concrete Masonry Bridges	277.000 CY	_____.	_____.
0042	502.3200 Protective Surface Treatment	269.000 SY	_____.	_____.
0044	502.3210 Pigmented Surface Sealer	88.000 SY	_____.	_____.
0046	505.0400 Bar Steel Reinforcement HS Structures	4,460.000 LB	_____.	_____.
0048	505.0600 Bar Steel Reinforcement HS Coated Structures	42,010.000 LB	_____.	_____.
0050	516.0500 Rubberized Membrane Waterproofing	22.000 SY	_____.	_____.
0052	526.0101 Temporary Structure (station) 01. 12+50	1.000 EACH	_____.	_____.
0054	550.1100 Piling Steel HP 10-Inch X 42 Lb	1,995.000 LF	_____.	_____.
0056	606.0300 Riprap Heavy	196.000 CY	_____.	_____.
0058	612.0406 Pipe Underdrain Wrapped 6-Inch	148.000 LF	_____.	_____.
0060	614.0115 Anchorages for Steel Plate Beam Guard Type 2	1.000 EACH	_____.	_____.
0062	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	_____.	_____.
0064	614.0200 Steel Thrie Beam Structure Approach	61.800 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230110035 Project(s): 7125-00-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	614.0305 Steel Plate Beam Guard Class A	1,037.500 LF	_____.	_____.
0068	614.0400 Adjusting Steel Plate Beam Guard	50.000 LF	_____.	_____.
0070	614.2300 MGS Guardrail 3	75.000 LF	_____.	_____.
0072	614.2500 MGS Thrie Beam Transition	39.400 LF	_____.	_____.
0074	614.2610 MGS Guardrail Terminal EAT	1.000 EACH	_____.	_____.
0076	618.0100 Maintenance And Repair of Haul Roads (project) 01. 7125-00-71	1.000 EACH	_____.	_____.
0078	619.1000 Mobilization	1.000 EACH	_____.	_____.
0080	624.0100 Water	48.000 MGAL	_____.	_____.
0082	625.0500 Salvaged Topsoil	5,781.000 SY	_____.	_____.
0084	627.0200 Mulching	1,182.000 SY	_____.	_____.
0086	628.1504 Silt Fence	1,975.000 LF	_____.	_____.
0088	628.1520 Silt Fence Maintenance	1,975.000 LF	_____.	_____.
0090	628.1905 Mobilizations Erosion Control	7.000 EACH	_____.	_____.
0092	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0094	628.2004 Erosion Mat Class I Type B	4,600.000 SY	_____.	_____.
0096	628.6005 Turbidity Barriers	275.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230110035 Project(s): 7125-00-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	628.7504 Temporary Ditch Checks	132.000 LF	_____.	_____.
0100	628.7555 Culvert Pipe Checks	1.000 EACH	_____.	_____.
0102	629.0210 Fertilizer Type B	3.800 CWT	_____.	_____.
0104	630.0130 Seeding Mixture No. 30	56.900 LB	_____.	_____.
0106	630.0160 Seeding Mixture No. 60	45.100 LB	_____.	_____.
0108	630.0200 Seeding Temporary	4.400 LB	_____.	_____.
0110	630.0500 Seed Water	458.000 MGAL	_____.	_____.
0112	633.1100 Delineators Temporary	33.000 EACH	_____.	_____.
0114	638.2102 Moving Signs Type II	5.000 EACH	_____.	_____.
0116	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0118	643.0300 Traffic Control Drums	2,840.000 DAY	_____.	_____.
0120	643.0420 Traffic Control Barricades Type III	1,340.000 DAY	_____.	_____.
0122	643.0705 Traffic Control Warning Lights Type A	2,680.000 DAY	_____.	_____.
0124	643.0715 Traffic Control Warning Lights Type C	1,560.000 DAY	_____.	_____.
0126	643.0900 Traffic Control Signs	2,760.000 DAY	_____.	_____.
0128	643.1050 Traffic Control Signs PCMS	190.000 DAY	_____.	_____.
0130	643.3105 Temporary Marking Line Paint 4-Inch	816.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230110035 Project(s): 7125-00-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0132	643.3850 Temporary Marking Stop Line Removable Tape 18-Inch	36.000 LF	_____.	_____.
0134	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0136	645.0105 Geotextile Type C	2,071.000 SY	_____.	_____.
0138	645.0111 Geotextile Type DF Schedule A	70.000 SY	_____.	_____.
0140	645.0120 Geotextile Type HR	350.000 SY	_____.	_____.
0142	646.1020 Marking Line Epoxy 4-Inch	2,519.000 LF	_____.	_____.
0144	646.9000 Marking Removal Line 4-Inch	94.000 LF	_____.	_____.
0146	648.0100 Locating No-Passing Zones	0.150 MI	_____.	_____.
0148	650.4500 Construction Staking Subgrade	707.000 LF	_____.	_____.
0150	650.5000 Construction Staking Base	707.000 LF	_____.	_____.
0152	650.6501 Construction Staking Structure Layout (structure) 01. B-06-0207	1.000 EACH	_____.	_____.
0154	650.9911 Construction Staking Supplemental Control (project) 01. 7125-00-71	1.000 EACH	_____.	_____.
0156	650.9920 Construction Staking Slope Stakes	707.000 LF	_____.	_____.
0158	661.0101 Temporary Traffic Signals for Bridges (structure) 01. B-06-0207	1.000 EACH	_____.	_____.
0160	690.0150 Sawing Asphalt	913.000 LF	_____.	_____.
0162	715.0502 Incentive Strength Concrete Structures	1,662.000 DOL	1.00000	1,662.00



Proposal Schedule of Items

Proposal ID: 20230110035 Project(s): 7125-00-71

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0164	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. 545+20	1.000 EACH	_____.	_____.
0166	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0168	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0170	SPV.0090 Special 01. Removing Existing Timber Piling	360.000 LF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.