


ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 96



DESIGN DESIGNATION


A.A.D.T.	2025	=	1200
A.A.D.T.	2045	=	1300
D.H.V.		=	6.8%
D.D.		=	
T.		=	8.3%
DESIGN SPEED		=	60 MPH
ESALS		=	197,100

CONVENTIONAL SYMBOLS

PLAN		PROFILE	
CORPORATE LIMITS		GRADE LINE	
PROPERTY LINE		ORIGINAL GROUND	
LOT LINE		MARSH OR ROCK PROFILE (To be noted as such)	
LIMITED HIGHWAY EASEMENT		SPECIAL DITCH	
EXISTING RIGHT OF WAY		GRADE ELEVATION	
PROPOSED OR NEW R/W LINE		CULVERT (Profile View)	
SLOPE INTERCEPT		UTILITIES	
REFERENCE LINE		ELECTRIC	
EXISTING CULVERT		FIBER OPTIC	
PROPOSED CULVERT (Box or Pipe)		GAS	
COMBUSTIBLE FLUIDS		SANITARY SEWER	
MARSH AREA		STORM SEWER	
		TELEPHONE	
		WATER	
		UTILITY PEDESTAL	
		POWER POLE	
		TELEPHONE POLE	
WOODED OR SHRUB AREA			

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION
 PLAN OF PROPOSED IMPROVEMENT
ALMA - MONDOVI
 BRANCH TROUT CREEK BRIDGE B-06-0207
 STH 37
 BUFFALO COUNTY

STATE PROJECT NUMBER
7125-00-71



BEGIN PROJECT
 STA 540+00
 Y=317,662.1007
 X=544,234.5187

STRUCTURE B-06-0207
 STA 544+86.42 - STA 545+53.58

END PROJECT
 STA 547+75
 Y=317,834.0991
 X=544,960.2196

LAYOUT
 SCALE 0 2 MI
 TOTAL NET LENGTH OF CENTERLINE = 0.147 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), BUFFALO COUNTY, NAD83 (1986), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12A.

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
7125-00-71		

ORIGINAL PLANS PREPARED BY
KNIGHT
 831 Critter Court
 Suite 400
 Onalaska, WI 54650
 Engineers & Architects Phone: (608) 519-1455



Ryan B. McKane
 6/26/2020 (Date) _____ (Signature)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

PREPARED BY

Surveyor	KNIGHT E/A
Designer	KNIGHT E/A
Project Manager	ADAM HETRICK
Regional Examiner	JENNIFER OLDENBURG
Regional Supervisor	DAVID KOEPP

APPROVED FOR THE DEPARTMENT
 DATE: 07/01/2020 *Adam Hetrick*
 (Signature)

E

STANDARD ABBREVIATIONS

AC	ACRE	INL	INLET
AGG	AGGREGATE	INV	INVERT
AH	AHEAD	JCT	JUNCTION
AA DT	ANNUAL AVERAGE DAILY TRAFFIC	LT	LEFT
ASPH	ASPHALTIC	L	LENGTH OF CURVE
AVG	AVERAGE	LIN FT or LF	LINEAR FOOT
BK	BACK	LS	LUMP SUM
BAD	BASE AGGREGATE DENSE	NC	NORMAL CROWN
BM	BENCH MARK	N	NORTH
BR	BRIDGE	NB	NORTHBOUND
CL or C/L	CENTER LINE	NO	NUMBER
CE	COMMERCIAL ENTRANCE	PT	POINT
CONC	CONCRETE	PC	POINT OF CURVATURE
CO	COUNTY	PI	POINT OF INTERSECTION
CTH	COUNTY TRUNK HIGHWAY	PT	POINT OF TANGENCY
CR	CREEK	PCC	PORTLAND CEMENT CONCRETE
CABC	CRUSHED AGGREGATE BASE COURSE	LB	POUND
CSD	COMMUNITY SENSITIVE DESIGN	PE	PRIVATE ENTRANCE
CY or CU YD	CUBIC YARD	R	RADIUS
CULV	CULVERT	RL or R/L	REFERENCE LINE
CP	CULVERT PIPE	RT	RIGHT
C & G	CURB AND GUTTER	R/W	RIGHT-OF-WAY
D	DEGREE OF CURVE	RD	ROAD
DIA	DIAMETER	SHLDR	SHOULDER
DISCH	DISCHARGE	SB	SOUTHBOUND
E	EAST	SF or SQ FT	SQUARE FEET
EB	EASTBOUND	SY or SQ YD	SQUARE YARD
EL or ELEV	ELEVATION	SDD	STANDARD DETAIL DRAWINGS
EW	ENDWALL	STH	STATE TRUNK HIGHWAYS
ENT	ENTRANCE	SE	SUPERELEVATION
EXC	EXCAVATION	T	TANGENT
EX	EXISTING	TEMP	TEMPORARY
FERT	FERTILIZER	TWLTL	TWO-WAY LEFT-TURN LANE
FE	FIELD ENTRANCE	UG	UNDERGROUND
FL or F/L	FLOW LINE	USH	UNITED STATES HIGHWAY
FT	FOOT	V	VELOCITY OR DESIGN SPEED
HE	HIGHWAY EASEMENT	VC	VERTICAL CURVE
HMA	HOT MIX ASPHALT	WB	WESTBOUND
CWT	HUNDREDWEIGHT	YD	YARD

GENERAL NOTES

- NO TREES OR SHRUBS SHALL BE REMOVED UNLESS DESIGNATED FOR REMOVAL BY THE ENGINEER.
- DISTURBED AREAS WITHIN THE RIGHT OF WAY ARE TO BE SALVAGED TOPSOILED, FERTILIZED, SEEDED, AND MULCHED AS DIRECTED BY THE ENGINEER.
- MATCH EXISTING DRIVEWAYS WITH IN-KIND MATERIALS.
- PAVING LIMITS ARE TO BE DETERMINED BY THE ENGINEER.
- THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLAN ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.
- HMA PAVEMENT TO BE PLACED IN LIFTS AS FOLLOWS: LOWER- 2 3/4" UPPER-2 1/4".
- PAVEMENT STRUCTURE FOR SECRIST LANE TO MATCH STH 37.
- UNIT WEIGHT FOR HMA PAVEMENT CALCULATIONS ARE BASED ON 112 LB/SY/IN.
- WHEN THE QUANTITY OF BASE AGGREGATE IS MEASURED FOR PAVEMENT BY THE TON OR CUBIC YARD, THE DEPTH OR THICKNESS OF THE LAYER SHOWN ON THE PLANS IS APPROXIMATE AND THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER.

BORING LOG

BORING 1-STA. 543+40, 7' LT	BORING 2-STA. 544+92, 6' LT	BORING 4-STA. 545+55, 7' RT	BORING 5-STA. 546+27, 7' RT
5 INCHES OF BITUMINOUS PAVEMENT	4.25 INCHES OF BITUMINOUS PAVEMENT	5 INCHES OF BITUMINOUS PAVEMENT	4.5 INCHES OF BITUMINOUS PAVEMENT
8 INCHES OF BASE COURSE	1 INCH OF RECYCLED ASPHALT	2 INCHES OF RECYCLED ASPHALT	2 INCHES OF RECYCLED ASPHALT
2 INCHES OF RECYCLED ASPHALT	3.25 INCHES OF BASE COURSE	4.5 INCHES OF BASE COURSE	1 INCHES OF BASE COURSE
11 INCHES OF BASE COURSE	4 INCHES OF RECYCLED ASPHALT	2 INCHES OF RECYCLED ASPHALT	2 INCHES OF RECYCLED ASPHALT
	1.25 INCHES OF BASE COURSE		4 INCHES OF BASE COURSE

AREA CONTACTS

WISDOT PROJECT MANAGER
 ADAM HETRICK, PE
 718 W. CLAIREMONT AVE.
 EAU CLAIRE, WI 54701
 (715) 577-8053
 ADAM.HETRICK@DOT.WI.GOV

DESIGN CONTACT
 KNIGHT E/A, INC.
 RYAN MCKANE, PE
 831 CRITTER COURT
 ONALASKA, WI 54650
 (608) 519-1455
 RMCKANE@KNIGHTEA.COM

WISCONSIN DEPARTMENT OF NATURAL RESOURCES
 AMY LESIK
 1300 W CLAIREMONT AVENUE
 EAU CLAIRE, WI 54701
 (715) 836-6571
 AMYL.LESIK@WISCONSIN.GOV

BUFFALO COUNTY HIGHWAY DEPARTMENT
 HIGHWAY COMMISSIONER
 BOB PLATTETER
 S1672 STATE ROAD 37
 PO BOX 332
 ALMA, WI 54610
 (608) 685-6226
 BOB.PLATTETER@CO.BUFFALO.WI.US

UTILITY CONTACTS

RIVERLAND ENERGY COOPERATIVE
 TIM HOLTAN
 N28988 STATE ROAD 93
 PO BOX 277
 ARCADIA, WI 54612-0277
 (608) 323-3381
 THOLTAN@RIVERLANDENERGY.COM

COCHRANE COOP TEL. CO.
 MATT BIESTERVELD
 103 W 5TH ST
 PO BOX 189
 COCHRANE, WI 54622-0189
 (608) 248-2323
 MBIESTERVELD@CCTCOOP.COM


TDS TELECOM
 JEFF SHAW
 202 ODGEN ST
 MEDFORD, WI 54451
 (715) 748-6970
 JEFF.SHAW@TDSTELECOM.COM



RUNOFF COEFFICIENT TABLE

A	HYDROLOGIC SOIL GROUP											
	B			C			D			E		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
ROW CROPS	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIP-TURF	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPE: TURF			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT	.70 - .95											
CONCRETE	.80 - .95											
BRICK	.70 - .80											
DRIVES, WALKS	.75 - .85											
ROOFS	.75 - .95											
GRAVEL ROADS, SHOULDERS	.40 - .60											


TOTAL PROJECT AREA = 1.91 ACRES
 TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 1.29 ACRES



2

2

PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	TYPICAL SECTIONS	SHEET	E
------------------------	-------------	-----------------	------------------	-------	---



NOTES

DETAILS OF CONSTRUCTION AND EROSION CONTROL DEVICES NOT SHOWN ON THIS DRAWING SHALL CONFORM TO PERTINENT REQUIREMENTS OF THE WISCONSIN DOT STANDARD DETAILS.


BACKFILL ALL HOLES REMAINING DUE TO GUARDRAIL POST REMOVAL WITH BASE AGGREGATE DENSE 3/4-INCH

SPECIAL CONSTRUCTION, EROSION CONTROL AND RESTORATION DETAILS PROVIDED IN THE SITE SPECIFIC BEAM GUARD DETAIL.

*TYPICAL EROSION CONTROL DEVICE INSTALLATION. SEE MISCELLANEOUS QUANTITIES FOR QUANTITIES PER LOCATION. ANY EROSION CONTROL DEVICES NOT SHOWN ON THIS DETAIL WILL BE SHOWN ON THE BEAM GUARD DETAILS. EROSION CONTROL AND CONSTRUCTION REQUIRED AT EACH SITE WILL VARY.



LEGEND

#####	EROSION MAT CLASS I, TYPE B
—●—●—●—	SILT FENCE
△△△	TEMPORARY DITCH CHECK
▨	BASE AGGREGATE DENSE 3/4"
▤	LIMITS OF CONSTRUCTION
- - - - -	SLOPE INTERCEPT



BACKFILL ANY DISTURBED SHOULDER WITH BASE AGGREGATE DENSE 3/4", SHAPE AND COMPACT. PLACE FROM EDGE OF PAVED SHOULDER TO HINGE POINT.

CONSTRUCTION STAKING, EXCAVATION, BORROW, 4" SALVAGED TOPSOIL, FERTILIZER TYPE B, AND SEEDING MIXTURE No. 30 ARE PAID FOR AS INDIVIDUAL CONTRACT ITEMS











TYPICAL DETAIL FOR CONSTRUCTION, EROSION CONTROL & RESTORATION
AT MGS ENERGY ABSORBING TERMINAL INSTALLATIONS


BARRIER SYSTEM GRADING SHAPING FINISHING









NOTES


- * LOCATIONS NOTED AS "MODIFIED GRADING" MAY HAVE A 2.5:1 SLOPE BEYOND THE CLEAR ZONE HINGE POINT.
- ** TAPER MAY BE REDUCED TO 10:1 AS APPROVED BY THE ENGINEER
- *** LOCATIONS NOTED AS "MODIFIED GRADING SECTION" MAY HAVE THE E.A.T. OFFSET REDUCED FROM 2' TO 0' AND THE SHOULDER HINGE POINT AT THE E.A.T. REDUCED FROM 8' TO 3' WITH 2.5:1 GRADING BEYOND THE SHOULDER HINGE POINT

ALL AREAS BEYOND THE AGGREGATE SHOULDER HINGE POINT SHALL BE SEEDED AND FERTILIZED


-  RIPRAP HEAVY & GEOTEXTILE FABRIC TYPE HR
-  SILT FENCE
-  TURBIDITY BARRIER
-  TEMPORARY DITCH CHECKS
-  SALVAGED TOPSOIL, EROSION MAT CLASS I TYPE B FERTILIZER TYPE B, SEEDING MIXTURE NO. 30
-  GEOTEXTILE FABRIC TYPE C, SALVAGED TOPSOIL, FERTILIZER TYPE B, SEEDING MIXTURE NO. 60, AND MULCHING
-  FLOW ARROW
-  CULVERT PIPE DITCH CHECK





-  RIPRAP HEAVY & GEOTEXTILE FABRIC TYPE HR
-  SILT FENCE
-  TURBIDITY BARRIER
-  TEMPORARY DITCH CHECKS
-  SALVAGED TOPSOIL, EROSION MAT CLASS I TYPE B FERTILIZER TYPE B, SEEDING MIXTURE NO. 30
-  GEOTEXTILE FABRIC TYPE C, SALVAGED TOPSOIL, FERTILIZER TYPE B, SEEDING MIXTURE NO. 60, AND MULCHING
-  FLOW ARROW
-  CULVERT PIPE DITCH CHECK




LEGEND

CONSTRUCTION AREA 






TRAFFIC CONTROL SIGNS 

TRAFFIC CONTROL DRUMS 

TYPE III BARRICADE WITH SIGN 

2

2



NOTES:


UTILIZE SDD TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION FOR SIGN LAYOUT AND LOCATION FOR CONSTRUCTION OF TEMP. BYPASS


PROVIDE MIN. 12-FT DRIVING WIDTH


THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.




LEGEND

CONSTRUCTION AREA 


TRAFFIC CONTROL SIGNS 

TRAFFIC CONTROL DRUMS 

TYPE III BARRICADE WITH SIGN 

2


2





NOTES:
 THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.
 SEE MISC. QUANTITIES FOR TEMPORARY TRAFFIC SIGNAL TIMINGS.






LEGEND

CONSTRUCTION AREA 



TRAFFIC CONTROL SIGNS 

TRAFFIC CONTROL DRUMS 

TYPE III BARRICADE WITH SIGN 



END ROAD WORK
G20-2A
48"X24"



END ROAD WORK
G20-2A
48"X24"



END ROAD WORK
G20-2A
48"X24"

NOTES:

UTILIZE SDD TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION FOR SIGN LAYOUT AND LOCATION FOR CONSTRUCTION OF APPROACHES.

PROVIDE MIN. 12-FT DRIVING WIDTH

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.






LEGEND	
CONSTRUCTION AREA	
TRAFFIC CONTROL SIGNS	
TRAFFIC CONTROL DRUMS	
TYPE III BARRICADE WITH SIGN	

2

2



END ROAD WORK
G20-2A
48"X24"




END ROAD WORK
G20-2A
48"X24"



END ROAD WORK
G20-2A
48"X24"

NOTES:
 UTILIZE SDD TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION FOR SIGN LAYOUT AND LOCATION FOR CONSTRUCTION OF APPROACHES.
 PROVIDE MIN. 12-FT DRIVING WIDTH
 THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.






CURVE 1
 PI STA = 10+24.17
 Y = 317675.900
 X = 544538.058
 DELTA = 18°55'40"
 D = 39°30'52"
 T = 24.17'
 L = 47.90'
 R = 145.00'
 PC STA = 10+00.00
 Y = 317667.390
 X = 544515.435
 PT STA = 10+47.90
 Y = 317691.289
 X = 544556.697
 BK = N69°23'07.0"E
 AH = N50°27'27.4"E
 SE=R.C.

CURVE 2
 PI STA = 11+34.13
 Y = 317746.185
 X = 544623.192
 DELTA = 18°59'46"
 D = 39°30'52"
 T = 24.26'
 L = 48.07'
 R = 145.00'
 PC STA = 11+09.87
 Y = 317730.740
 X = 544604.484
 PT STA = 11+57.94
 Y = 317754.699
 X = 544645.908
 BK = N50°27'27.4"E
 AH = N69°27'13.0"E
 SE=R.C.

CURVE 3
 PI STA = 12+94.23
 Y = 317802.530
 X = 544773.522
 DELTA = 25°30'55"
 D = 39°30'52"
 T = 32.83'
 L = 64.57'
 R = 145.00'
 PC STA = 12+61.39
 Y = 317791.008
 X = 544742.780
 PT STA = 13+25.97
 Y = 317799.686
 X = 544806.229
 BK = N69°27'13.0"E
 AH = S85°01'51.7"E
 SE=R.C.

CURVE 4
 PI STA = 13+76.71
 Y = 317795.291
 X = 544856.782
 DELTA = 25°30'55"
 D = 39°30'52"
 T = 32.83'
 L = 64.57'
 R = 145.00'
 PC STA = 13+43.88
 Y = 317798.135
 X = 544824.075
 PT STA = 14+08.45
 Y = 317806.814
 X = 544887.525
 BK = S85°01'51.7"E
 AH = N69°27'13.0"E
 SE=R.C.



BEGIN PROJECT
 STA 540+00
 Y=317562.1007
 X=544234.5187

BEGIN CONSTRUCTION
 STA 10+00 TEMP. BYPASS
 =STA 543+00 STH 37
 Y=317666.4154
 X=544512.7300

END CONSTRUCTION
 STA 14+08.45 TEMP. BYPASS
 =STA 546+94.48 STH 37
 Y = 317805.838
 X = 544884.819

END PROJECT
 STA 547+75
 Y=317834.0991
 X=544960.2196
 239'

CONTROL POINTS					
NO.	DESCRIPTION	STATION	OFFSET	Y	X
1	IRON PIPE	539+54	20.03 LT	317564.49	544184.00
2	PK NAIL	544+00	21.21 RT	317682.63	544616.52
3	IRON PIPE	546+75	118.18 RT	317688.41	544908.49
4	IRON PIPE	-	-	317852.26	545247.55

BENCHMARKS				
NO.	DESCRIPTION	STATION	OFFSET	ELEV.
1	3" DIA. BRASS CAP	544+99	16.09 LT	678.453

Estimate Of Quantities

7125-00-71

Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	3.000	3.000
0004	201.0205	Grubbing	STA	3.000	3.000
0006	203.0211.S	Abatement of Asbestos Containing Material (structure) 01. B-06-0896	EACH	1.000	1.000
0008	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 01. B-06-0896	EACH	1.000	1.000
0010	204.0165	Removing Guardrail	LF	1,288.000	1,288.000
0012	205.0100	Excavation Common	CY	2,057.000	2,057.000
0014	206.1001	Excavation for Structures Bridges (structure) 01. B-06-0207	EACH	1.000	1.000
0016	208.0100	Borrow	CY	479.000	479.000
0018	210.1500	Backfill Structure Type A	TON	292.000	292.000
0020	211.0101	Prepare Foundation for Asphaltic Paving (project) 01. 7125-00-71	EACH	1.000	1.000
0022	213.0100	Finishing Roadway (project) 01. 7125-00-71	EACH	1.000	1.000
0024	305.0110	Base Aggregate Dense 3/4-Inch	TON	227.000	227.000
0026	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	2,928.000	2,928.000
0028	311.0110	Breaker Run	TON	2,421.000	2,421.000
0030	455.0605	Tack Coat	GAL	191.000	191.000
0032	460.2000	Incentive Density HMA Pavement	DOL	600.000	600.000
0034	460.6244	HMA Pavement 4 MT 58-34 S	TON	934.000	934.000
0036	465.0125	Asphaltic Surface Temporary	TON	131.000	131.000
0038	465.0315	Asphaltic Flumes	SY	12.000	12.000
0040	502.0100	Concrete Masonry Bridges	CY	277.000	277.000
0042	502.3200	Protective Surface Treatment	SY	269.000	269.000
0044	502.3210	Pigmented Surface Sealer	SY	88.000	88.000
0046	505.0400	Bar Steel Reinforcement HS Structures	LB	4,460.000	4,460.000
0048	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	42,010.000	42,010.000
0050	516.0500	Rubberized Membrane Waterproofing	SY	22.000	22.000
0052	526.0101	Temporary Structure (station) 01. 12+50	EACH	1.000	1.000
0054	550.1100	Piling Steel HP 10-Inch X 42 Lb	LF	1,995.000	1,995.000
0056	606.0300	Riprap Heavy	CY	196.000	196.000
0058	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	148.000	148.000
0060	614.0115	Anchorage for Steel Plate Beam Guard Type 2	EACH	1.000	1.000
0062	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0064	614.0200	Steel Thrie Beam Structure Approach	LF	61.800	61.800
0066	614.0305	Steel Plate Beam Guard Class A	LF	1,037.500	1,037.500
0068	614.0400	Adjusting Steel Plate Beam Guard	LF	50.000	50.000
0070	614.2300	MGS Guardrail 3	LF	75.000	75.000
0072	614.2500	MGS Thrie Beam Transition	LF	39.400	39.400
0074	614.2610	MGS Guardrail Terminal EAT	EACH	1.000	1.000
0076	618.0100	Maintenance And Repair of Haul Roads (project) 01. 7125-00-71	EACH	1.000	1.000
0078	619.1000	Mobilization	EACH	1.000	1.000
0080	624.0100	Water	MGAL	48.000	48.000
0082	625.0500	Salvaged Topsoil	SY	5,781.000	5,781.000
0084	627.0200	Mulching	SY	1,182.000	1,182.000
0086	628.1504	Silt Fence	LF	1,975.000	1,975.000
0088	628.1520	Silt Fence Maintenance	LF	1,975.000	1,975.000
0090	628.1905	Mobilizations Erosion Control	EACH	7.000	7.000
0092	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0094	628.2004	Erosion Mat Class I Type B	SY	4,600.000	4,600.000
0096	628.6005	Turbidity Barriers	SY	275.000	275.000
0098	628.7504	Temporary Ditch Checks	LF	132.000	132.000

Estimate Of Quantities

7125-00-71

Line	Item	Item Description	Unit	Total	Qty
0100	628.7555	Culvert Pipe Checks	EACH	1.000	1.000
0102	629.0210	Fertilizer Type B	CWT	3.800	3.800
0104	630.0130	Seeding Mixture No. 30	LB	56.900	56.900
0106	630.0160	Seeding Mixture No. 60	LB	45.100	45.100
0108	630.0200	Seeding Temporary	LB	4.400	4.400
0110	630.0500	Seed Water	MGAL	458.000	458.000
0112	633.1100	Delineators Temporary	EACH	33.000	33.000
0114	638.2102	Moving Signs Type II	EACH	5.000	5.000
0116	642.5001	Field Office Type B	EACH	1.000	1.000
0118	643.0300	Traffic Control Drums	DAY	2,840.000	2,840.000
0120	643.0420	Traffic Control Barricades Type III	DAY	1,340.000	1,340.000
0122	643.0705	Traffic Control Warning Lights Type A	DAY	2,680.000	2,680.000
0124	643.0715	Traffic Control Warning Lights Type C	DAY	1,560.000	1,560.000
0126	643.0900	Traffic Control Signs	DAY	2,760.000	2,760.000
0128	643.1050	Traffic Control Signs PCMS	DAY	190.000	190.000
0130	643.3105	Temporary Marking Line Paint 4-Inch	LF	816.000	816.000
0132	643.3850	Temporary Marking Stop Line Removable Tape 18-Inch	LF	36.000	36.000
0134	643.5000	Traffic Control	EACH	1.000	1.000
0136	645.0105	Geotextile Type C	SY	2,071.000	2,071.000
0138	645.0111	Geotextile Type DF Schedule A	SY	70.000	70.000
0140	645.0120	Geotextile Type HR	SY	350.000	350.000
0142	646.1020	Marking Line Epoxy 4-Inch	LF	2,519.000	2,519.000
0144	646.9000	Marking Removal Line 4-Inch	LF	94.000	94.000
0146	648.0100	Locating No-Passing Zones	MI	0.150	0.150
0148	650.4500	Construction Staking Subgrade	LF	707.000	707.000
0150	650.5000	Construction Staking Base	LF	707.000	707.000
0152	650.6501	Construction Staking Structure Layout (structure) 01. B-06-0207	EACH	1.000	1.000
0154	650.9911	Construction Staking Supplemental Control (project) 01. 7125-00-71	EACH	1.000	1.000
0156	650.9920	Construction Staking Slope Stakes	LF	707.000	707.000
0158	661.0101	Temporary Traffic Signals for Bridges (structure) 01. B-06-0207	EACH	1.000	1.000
0160	690.0150	Sawing Asphalt	LF	913.000	913.000
0162	715.0502	Incentive Strength Concrete Structures	DOL	1,662.000	1,662.000
0164	999.2000.S	Installing and Maintaining Bird Deterrent System (station) 01. 545+20	EACH	1.000	1.000
0166	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	1,200.000	1,200.000
0168	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	600.000	600.000
0170	SPV.0090	Special 01. Removing Existing Timber Piling	LF	360.000	360.000

CLEARING AND GRUBBING

CATEGORY	STATION	TO	STATION	LOCATION	CLEARING GRUBBING		REMARKS
					201.0105 STA	201.0205 STA	
0010	543+25	-	546+60	STH 37 LT	3	3	TEMP BYPASS CONSTRUCTION
PROJECT TOTALS =					3	3	

REMOVING GUARDRAIL

CATEGORY	STATION	TO	STATION	LOCATION	204.0165
					LF
0010	540+05	-	545+00	LT/RT	990
0010	545+50	-	546+82	LT	132.0
0010	545+50	-	101+16.5	SL RT	166.0
PROJECT TOTALS =					1,288

EXCAVATION SUMMARY

CATEGORY	STATION	TO	STATION	LOCATION	EXCAVATION			REMARKS
					205.0100 COMMON CY	208.0100 BORROW CY	311.0110 BREAKER RUN TON	
0010	10+75	-	13+25	TEMP BYPASS	29	-	2,421	BYPASS CONSTRUCTION
0010	540+00	-	547+75	STH 37	683	479	-	STH 37 CONSTRUCTION
0010	10+75	-	13+25	TEMP BYPASS	1,345	-	-	REMOVING BYPASS
PROJECT TOTALS =					2,057	479	2,421	

PREPARE FOUNDATION FOR ASPHALTIC PAVING (PROJECT) 01. 7125-00-71

CATEGORY	LOCATION	211.0101	REMARKS
		EACH	
0010	PROJECT 7125-00-71	1	
PROJECT TOTALS =		1	

FINISHING ROADWAY (PROJECT) 01. 7125-00-71

CATEGORY	LOCATION	213.0100	REMARKS
		EACH	
0010	PROJECT 7125-00-71	1	
PROJECT TOTALS =		1	

BASE AGGREGATE DENSE 3/4-INCH

CATEGORY	STATION	TO	STATION	LOCATION	305.0110 TON
0010	540+00	-	544+86	LT/RT	156
0010	545+54	-	547+75	LT/RT	71
PROJECT TOTAL=					<u>227</u>

ASPHALT ITEMS SUMMARY

CATEGORY	STATION	TO	STATION	LOCATION	TACK COAT 455.0605 GAL	HMA PAVEMENT 4 MT 58-34 S 460.6244 TON	ASPHALTIC SURFACE TEMPORARY 465.0125 TON
0010	540+00	-	547+75	STH 37	-	514	-
0010	540+00	-	547+75	STH 37	167	420	-
0010	10+00	-	14+08	TEMP BYPASS	24	-	131
PROJECT TOTALS =					<u>191</u>	<u>934</u>	<u>131</u>

BASE AGGREGATE DENSE 1 1/4-INCH

CATEGORY	STATION	TO	STATION	LOCATION	305.0120 TON
0010	540+00	-	544+86	STH 37	1,503
0010	545+54	-	547+75	STH 37	684
0010				SECRI ST LN	278
0010	10+75	-	13+25	TEMP BYPASS	463
PROJECT TOTALS =					<u>2,928</u>

ASPHALTIC FLUMES

CATEGORY	STATION	LOCATION	465.0315 SY
0010	544+75	STH 37 LT	3.0
0010	544+75	STH 37 RT	3.0
0010	545+70	STH 37 LT	3.0
0010	545+70	STH 37 RT	3.0
PROJECT TOTALS =			<u>12.0</u>

TEMPORARY STRUCTURE (STATION) 01. 12+50

CATEGORY	LOCATION	526.0101 EACH	COMMENTS
0010	STH 37	1	
PROJECT TOTALS =		<u>1</u>	

BEAM GUARD SUMMARY

CATEGORY	STATION	TO	STATION	LOCATION	ANCHORAGES FOR STEEL PLATE BEAM GUARD TYPE 2 614.0115 EACH	STEEL THRI E BEAM STRUCTURE APPROACH 614.0200 LF	STEEL PLATE BEAM GUARD CLASS A 614.0305 LF	ADJUSTING STEEL PLATE BEAM GUARD 614.0400 LF	MGS GUARDRAI L 3 614.2300 LF	MGS THRI E BEAM TRANSI TION 614.2500 LF	MGS GUARDRAI L TERMI NAL EAT 614.2610 EACH	REMARKS
0010	539+75	-	540+00	LT/RT	-	-	-	50	-	-	-	
0010	540+05	-	544+75	LT	-	20.6	450.0	-	-	-	-	
0010	540+05	-	544+75	RT	-	20.6	450.0	-	-	-	-	
0010	545+64	-	546+82	LT	-	-	-	-	75	39.4	1.0	
0010	545+64	-	101+16.5 SL	RT	1.0	20.6	137.5	-	-	-	-	60' R BEND REQ' D
PROJECT TOTALS =					<u>1.0</u>	<u>61.8</u>	<u>1,037.5</u>	<u>50.0</u>	<u>75.0</u>	<u>39.4</u>	<u>1.0</u>	

**MAINTENANCE AND REPAIR OF HAUL ROADS
(PROJECT) 01. 7125-00-71**

CATEGORY	LOCATION	618. 0100 EACH
0010	PROJECT 7125-00-71	1
PROJECT TOTALS =		1

WATER

CATEGORY	LOCATION	624. 0100 MGAL	COMMENTS
0010	STH 37	48	BASE AGG.
PROJECT TOTALS =		48	

EROSION CONTROL SUMMARY

CATEGORY	STATION TO STATION	LOCATION	SALVAGED TOPSOIL 625. 0500 SY	MULCHING 627. 0200 SY	EROSION MAT CLASS I TYPE B 628. 2004 SY	TURBIDITY BARRIERS 628. 6005 SY	TEMPORARY DITCH CHECKS 628. 7504 LF	CULVERT PIPE CHECK 628. 7555 EACH	FERTILIZER TYPE B 629. 0210 CWT	SEEDING MIXTURE NO. 30 630. 0130 LB	SEEDING MIXTURE NO. 60 630. 0160 LB	SEEDING TEMPORARY 630. 0200 LB	SEED WATER 630. 0500 MGAL	REMARKS
0010	540+00 - 544+70	LT	1,109	-	1,109	-	40	-	0.7	20.0	-	-	88	
0010	540+00 - 544+70	RT	887	-	887	-	40	-	0.6	16.0	-	-	70	
0010	545+70 - 545+75	LT	457	-	457	-	20	-	0.3	8.3	-	-	36	
0010	545+70 - 546+50	RT	408	-	408	-	20	1	0.3	7.4	-	-	33	
0010	545+00 -	LT/RT	-	-	-	250	-	-	-	-	-	-	-	
0010	540+00 - 547+75	LT	1,320	-	1,320	-	-	-	0.9	-	23.80	4.0	104	TEMP BYPASS
0010	540+00 - 547+75	LT	1,074	1,074	-	-	-	-	0.7	-	19.4	-	85	TEMP BYPASS REMOVAL
0010	540+00 - 547+75	UNDISTRIBUTED	526	107	418	25	12	-	0.3	5.2	1.9	0.4	42	
PROJECT TOTALS =			5,781	1,182	4,600	275	132	1	3.80	56.9	45.1	4.4	458	

SILT FENCE SUMMARY

CATEGORY	STATION TO STATION	LOCATION	SILT FENCE 628. 1504 LF	SILT FENCE MAINTENANCE 628. 1520 LF	REMARKS
0010	540+00 - 547+75	LT	790	790	TEMP BYPASS
0010	540+00 - 546+50	RT	690	690	
0010	546+75 - 547+92	RT	145	145	
0010	543+00 - 546+50	LT	350	350	BYPASS REMOVAL
PROJECT TOTALS =			1,975	1,975	

MOBILIZATION EROSION CONTROL

CATEGORY	LOCATION	MOBILIZATION EROSION CONTROL 628. 1905 EACH	MOBILIZATION EROSION CONTROL 628. 1910 EACH	REMARKS
0010	PROJECT 7125-00-71	7	3	ENTIRE PROJECT
PROJECT TOTALS =		7	3	

FIELD OFFICE TYPE B

CATEGORY	LOCATION	642.5001 EACH
0010	PROJECT 7125-00-71	<u>1</u>
PROJECT TOTALS =		1

TRAFFIC CONTROL

CATEGORY	STATION	STATION	STAGE	LOCATION	DAYS	DELINEATORS TEMPORARY 633.1100 EACH	TRAFFIC CONTROL DRUMS 643.0300 DAY	TRAFFIC CONTROL BARICADES TYPE III 643.0420 DAY	TRAFFIC CONTROL WARNING LIGHTS TYPE A 643.0705 DAY	TRAFFIC CONTROL WARNING LIGHTS TYPE C 643.0715 DAY	TRAFFIC CONTROL SIGNS 643.0900 DAY	TRAFFIC CONTROL SIGNS PCMS 643.1050 DAY	REMARKS
0010	542+00	- 547+92	1	STH 37	15	-	180	60	120	-	-	30	FLAGGING
0010	10+00	- 14+08	2	TEMP BYPASS	60	33	2280	1200	2400	1560	2760	120	TEMP BYPASS W/SIGNALS
0010	538+75	- 547+92	3	STH 37	10	-	190	40	80	-	-	20	FLAGGING
0010	538+75	- 547+92	4	STH 37	10	-	190	40	80	-	-	20	FLAGGING
PROJECT TOTALS =						33	2840	1340	2680	1560	2760	190	

MOVING SIGNS TYPE II

CATEGORY	STATION	LOCATION	638.2102 EACH
0010	544+60	RT	1
0010	544+87	RT	1
0010	544+91	LT	1
0010	545+59	RT	1
0010	545+59	LT	<u>1</u>
PROJECT TOTALS =			5

PAVEMENT MARKING SUMMARY

CATEGORY	STATION TO	STATION	LOCATION	MARKING EPOXY 4-INCH 646.1020 LF	MARKING REMOVAL LINE 4-INCH 646.9000 LF	TEMPORARY MARKING LINE PAINT 4-INCH 643.3105 LF	TEMPORARY MARKING STOP LINE REMOVABLE TAPE 18-INCH 643.3850 LF	REMARKS
0010	539+00	-	-	-	-	-	12	WEST STH 37 PROJECT LIMIT
0010	547+92	-	-	-	-	-	12	EAST STH 37 PROJECT LIMIT
0010	100+50	-	-	-	-	-	12	SECRIST LN STOP
0010	540+00	- 547+75	LT/RT	1,550	-	-	-	LANE EDGE, WHITE
0010	540+00	- 547+75	CL	775	-	-	-	CENTERLINE, SOLID YELLOW
0010	540+00	- 547+75	CL	194	-	-	-	CENTERLINE, DASHED YELLOW
0010	10+00	- 14+08	TEMP BYPASS	-	94	816	-	LT LANE EDGE, WHITE
PROJECT TOTALS =				2,519	94	816	36	

GEOTEXTILE TYPE C

CATEGORY	STATION TO	STATION	LOCATION	645.0105 SY
0010	10+75	- 13+25	TEMP BYPASS	<u>2,071</u>
PROJECT TOTALS =				2,071

LOCATING NO-PASSING ZONES

CATEGORY	STATION	TO	STATION	LOCATION	648.0100 MI
0010	540+00	-	547+75	STH 37	<u>0.15</u>
PROJECT TOTALS =					0.15

CONSTRUCTION STAKING SUMMARY

CATEGORY	STATION	TO	STATION	LOCATION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	CONSTRUCTION	REMARKS
					STAKING SUBGRADE	CONSTRUCTION STAKING BASE	STAKING LAYOUT	STRUCTURE (STRUCTURE)	SUPPLEMENTAL CONTROL (PROJECT)	
					650.4500	650.5000	650.6501	650.9911	650.9920	
					LF	LF	EACH	EACH	LF	
0010	540+00	-	544+86	LT/RT	486	486	-	-	486	
0010	545+54	-	547+75	LT/RT	221	221	-	-	221	
0010	540+00	-	547+75	LT/RT	-	-	1	1	-	
PROJECT TOTALS =					707	707	1	1	707	

TEMPORARY TRAFFIC SIGNALS FOR BRIDGES
(STRUCTURE) 01. B-06-0207

CATEGORY	LOCATION	661.0101
		EACH
0010	STH 37	1
PROJECT TOTALS =		1

PROPOSED SIGNAL TIMINGS (SEC.)			
PHASE 1 STH 37 EB	PHASE 2 Secrist Lane	PHASE 3 STH 37 WB	PROGRAM TYPE
10	5	10	MINIMUM GREEN TIME
8	3	8	MAXIMUM PASSAGE TIME DURING GREEN PHASE
3	-	3	MINIMUM PASSAGE TIME DURING GREEN PHASE
10	-	10	START OF REDUCTION OF PASSAGE FROM MAX. TO MIN. DURING GREEN PHASE
10	-	10	TIME TO REDUCE PASSAGE FROM MAX. TO MIN. DURING GREEN PHASE
25	10	25	MAXIMUM GREEN TIME
4	4	4	YELLOW
23	2	23	ALL-RED
NONE	NONE	MIN	RECALL MODE
<u>NOTES:</u>			
PHASE 3 SHALL TIME AFTER PHASE 1 OR PHASE 2			
PHASE 1 SHALL TIME AFTER PHASE 3			
MIN RECALL SET FOR PHASE 1 AND PHASE 3 TO ENSURE CLEARANCE TIME FOR EB AND WB DIRECTIONS TIME EACH CYCLE.			
SIGNAL SHALL NOT REST IN GREEN OR RED.			
PHASE 2 MAY BE SKIPPED.			

SAWING ASPHALT

CATEGORY	STATION	TO	STATION	690.0150	LOCATION
				LF	
0010	540+00	-	-	30	STH 37 PROJECT START
0010	547+75	-	-	40	STH 37 PROJECT END
0010	540+00	-	547+75	94	TEMP BYPASS
0010	101+00	-	-	24	SECRI ST LANE
0010	540+00	-	545+00	500	CENTERLINE JOINT FOR CONSTRUCTION HALF AT A TIME
0010	545+50	-	547+75	225	CENTERLINE JOINT FOR CONSTRUCTION HALF AT A TIME
PROJECT TOTALS =				913	

NOTES:

POSITIONS SHOWN ON THIS PLAT ARE WISCONSIN REFERENCE SYSTEM COORDINATES (WISCRS), BUFFALO COUNTY, NAD83 (1986), IN U.S. SURVEY FEET. VALUES SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES MAY BE USED AS GROUND DISTANCES. ALL NEW RIGHT-OF-WAY MONUMENTS WILL BE TYPE 2 (TYPICALLY 3/4" X 24" IRON REBARS), UNLESS OTHERWISE NOTED, AND WILL BE PLACED PRIOR TO THE COMPLETION OF THE PROJECT.

ALL RIGHT-OF-WAY LINES DEPICTED IN THE NON-ACQUISITION AREAS ARE INTENDED TO RE-ESTABLISH EXISTING RIGHT-OF-WAY LINES AS DETERMINED FROM PREVIOUS PROJECTS, OTHER RECORDED DOCUMENTS, OR FROM CENTERLINE OF EXISTING PAVEMENTS.

RIGHT-OF-WAY BOUNDARIES ARE DEFINED WITH COURSES OF THE PERIMETER OF THE HIGHWAY LANDS REFERENCED TO THE U.S. PUBLIC LAND SURVEY SYSTEM OR OTHER "SURVEYS" OF PUBLIC RECORD.

DIMENSIONING FOR THE NEW RIGHT-OF-WAY IS MEASURED ALONG AND PERPENDICULAR TO THE NEW REFERENCE LINES.

A TEMPORARY LIMITED EASEMENT (TLE) IS A RIGHT FOR CONSTRUCTION PURPOSES, AS DEFINED HEREIN, INCLUDING THE RIGHT TO OPERATE NECESSARY EQUIPMENT THEREON, THE RIGHT OF INGRESS AND EGRESS, AS LONG AS REQUIRED FOR SUCH PUBLIC PURPOSE, INCLUDING THE RIGHT TO PRESERVE, PROTECT, REMOVE, OR PLANT THEREON ANY VEGETATION THAT THE HIGHWAY AUTHORITIES MAY DEEM DESIRABLE. ALL (TLE)S ON THIS PLAT EXPIRE AT THE COMPLETION OF THE CONSTRUCTION PROJECT FOR WHICH THIS INSTRUMENT IS GIVEN.

PROPERTY LINES SHOWN ON THIS PLAT ARE DRAWN FROM DATA DERIVED FROM MAPS AND DOCUMENTS OF PUBLIC RECORD AND/OR EXISTING OCCUPATIONAL LINES. THIS PLAT MAY NOT BE A TRUE REPRESENTATION OF EXISTING PROPERTY LINES, EXCLUDING RIGHT-OF-WAY, AND SHOULD NOT BE USED AS A SUBSTITUTE FOR AN ACCURATE FIELD SURVEY.

PARCEL IDENTIFICATION NUMBERS MAY NOT POINT TO ALL AREAS OF ACQUISITION, AS NOTED ON THE SCHEDULE OF LANDS & INTERESTS REQUIRED.

EXISTING HIGHWAY RIGHT-OF-WAY SHOWN HEREIN IS BASED ON THE FOLLOWING POINTS OF REFERENCE:

EXISTING HIGHWAY RIGHT-OF-WAY FOR STH 37 ESTABLISHED FROM PREVIOUS PROJECTS DJ5459 AND 7125-05-21.

FOR CURRENT ACCESS/DRIVEWAY INFORMATION, CONTACT THE PLANNING UNIT OF THE WISCONSIN DEPARTMENT OF TRANSPORTATION OFFICE IN EAU CLAIRE.

TRANSPORTATION PROJECT PLAT NO: 7125-00-21 - 4.01

THAT PART OF GOVERNMENT LOT 8 OF THE SOUTHEAST 1/4 OF SECTION 26, CITY OF ALMA AND THAT PART OF GOVERNMENT LOT 7 OF THE SOUTHWEST 1/4 OF SECTION 25, TOWNSHIP 22 NORTH, RANGE 13 WEST OF THE 4TH PRINCIPAL MERIDIAN, TOWN OF ALMA, BUFFALO COUNTY, WISCONSIN.

RELOCATION ORDER STH 37 ALMA - MONDOVI (BRANCH TROUT CREEK BRIDGE B-06-0207), BUFFALO COUNTY

TO PROPERLY ESTABLISH, LAY OUT, WIDEN, ENLARGE, EXTEND, CONSTRUCT, RECONSTRUCT, IMPROVE, OR MAINTAIN A PORTION OF THE HIGHWAY DESIGNATED ABOVE, THE STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION DEEMS IT NECESSARY TO RELOCATE OR CHANGE SAID HIGHWAY AND ACQUIRE CERTAIN LANDS AND INTERESTS OR RIGHTS IN LANDS FOR THE ABOVE PROJECT.

TO EFFECT THIS CHANGE, PURSUANT TO AUTHORITY GRANTED UNDER SECTION 84.02 (3), 84.09, AND 84.30, WISCONSIN STATUTES, THE DEPARTMENT OF TRANSPORTATION HEREBY ORDERS THAT: 1. THAT PORTION OF SAID HIGHWAY AS SHOWN ON THIS PLAT IS Laid OUT AND ESTABLISHED TO THE LINES AND WIDTHS AS SO SHOWN FOR THE ABOVE PROJECT. 2. THE LANDS OR INTERESTS OR RIGHTS IN LANDS AS SHOWN ON THIS PLAT ARE REQUIRED BY THE DEPARTMENT FOR THE ABOVE PROJECT AND SHALL BE ACQUIRED IN THE NAME OF THE STATE OF WISCONSIN, PURSUANT TO THE PROVISIONS OF SECTION 84.09 (1) OR (2), WISCONSIN STATUTES.

STATION & OFFSET TABLE with columns: POINT, STATION, OFFSET, Y COORDS, X COORDS. Rows include T201, T200, 100, 101, 102, 103, 104.

COURSE TABLE with columns: POINT - POINT, COURSE, DISTANCE. Rows include 100-101, 101-102, 102-103, 103-104, 104-100.



UTILITY INTERESTS REQUIRED table with columns: UTILITY #, OWNER, INTEREST REQ'D. Includes TDS TELECOM and TEMPORARY RELEASE OF RIGHTS.

SCHEDULE OF LANDS & INTERESTS REQUIRED table with columns: PARCEL NUMBER, OWNER(S), INTEREST REQUIRED, R/W NEW ACRES, R/W TOTAL ACRES, TLE ACRES. Includes UNITED STATES OF AMERICA and UNKNOWN OWNER.

271935 CAROL J BURMEISTER REGISTER OF DEEDS BUFFALO COUNTY, WI RECORDED ON 04/09/2020 12:21 PM REC FEE: 25.00 PAGES: 1 **The above recording information verifies that this document has been electronically recorded and returned to the submitter.**

RESERVED FOR REGISTER OF DEEDS PROJECT NUMBER: 7125-00-21-4.01 AMENDMENT NO. _____

PROJECT LOCATION MAP



CONVENTIONAL ABBREVIATIONS

Table of conventional abbreviations for survey terms such as ACCESS RIGHTS, ACRES, AHEAD, ALUMINUM, etc., and their corresponding symbols.



CONVENTIONAL UTILITY SYMBOLS

Table of conventional utility symbols for WATER, GAS, TELEPHONE, OVERHEAD TRANSMISSION LINES, etc.

CONVENTIONAL SYMBOLS


Table of conventional symbols for SECTION LINE, QUARTER LINE, SIXTEENTH LINE, NEW REFERENCE LINE, etc., and their corresponding symbols.

SCALE, FEET 0 50 100

KNIGHT



831 Critter Court Suite 400 Onalaska, WI 54650 Engineers & Architects Phone: (608) 519-1455

I, STEVEN BARCZAK, PROFESSIONAL LAND SURVEYOR, HEREBY CERTIFY THAT IN FULL COMPLIANCE WITH THE PROVISIONS OF SECTION 84.095 OF THE WISCONSIN STATUTES AND UNDER THE DIRECTION OF THE DEPARTMENT, I HAVE SURVEYED AND MAPPED THIS TRANSPORTATION PROJECT PLAT AND SUCH PLAT CORRECTLY REPRESENTS ALL EXTERIOR BOUNDARIES OF THE SURVEYED LAND.




SIGNATURE: [Signature] DATE: 4/7/2020 PRINT NAME: STEVEN BARCZAK REGISTRATION NUMBER: 2990-008

THIS PLAT AND RELOCATION ORDER ARE APPROVED FOR THE WISCONSIN DEPARTMENT OF TRANSPORTATION SIGNATURE: [Signature] DATE: 4/7/2020 PRINT NAME: DEBRA B. STENSLAND



PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	PLAN AND PROFILE: STH 37	SHEET	E
------------------------	-------------	-----------------	--------------------------	-------	----------



NOTES:
 UTILITY LOCATIONS ARE APPROXIMATE.
 ACTUAL LOCATIONS MUST BE FIELD VERIFIED.
 SEE TRAFFIC CONTROL OVERVIEW FOR
 TRAFFIC CONTROL SETUP

REMOVING GUARDRAIL - (STA. 545+50 - STA. 546+82) LT
 MGS THRIE BEAM TRANSITION REQ'D,
 MGS GUARDRAIL 3 REQ'D - 75 LF,
 MGS GUARDRAIL TERMINAL EAT REQ'D


END PROJECT 7125-00-71
 STA 547+75
 Y=317,834.0991
 X=544,960.2196
 MATCH EXISTING
 SAWCUT REQ'D

5

5


BENCHMARKS

NO.	DESCRIPTION	STATION	OFFSET	ELEV.
1	3" DIA. BRASS CAP	544+99	16.09 LT	678.453




STA. 545+25
 REMOVE EXISTING STRUCTURE B-06-896
 51.2' OVERALL LENGTH AND
 32.5' CLEAR ROADWAY WIDTH
 DOUBLE SPAN STEEL GIRDER BRIDGE

STA. 545+20
 STRUCTURE B-06-0207 REQ'D
 68.5' OVERALL LENGTH AND
 36' CLEAR ROADWAY WIDTH
 2-SPAN SLAB BRIDGE
 0° SKEW



5

5




TEMPORARY STRUCTURE REQ'D
 MINIMUM BRIDGE OPENING AREA=87.92 SF
 $Q_s = 185$ C.F.S.
 $VEL_s = 1.99$ F.P.S.
 $HW_s = EL. 675.88$

PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	PLAN AND PROFILE: TEMPORARY BYPASS	SHEET E
------------------------	-------------	-----------------	------------------------------------	---------

Standard Detail Drawing List

08E08-03	TYPICAL INSTALLATIONS OF EROSION BALES / TEMPORARY DITCH CHECKS
08E09-06	SILT FENCE
08E11-02	TURBIDITY BARRIER
08E15-01	CULVERT PIPE CHECK
09G02-05A	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
09G02-05B	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
09G02-05C	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
12A03-10	NAME PLATE (STRUCTURES)
13A10-02A	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A10-02B	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A10-02C	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
13A10-02D	2-LANE RURAL SHOULDER RUMBLE STRIP, MILLING
14B15-11A	STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS
14B15-11B	STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS
14B15-11C	STEEL PLATE BEAM GUARD, CLASS "A", INSTALLATION & ELEMENTS
14B16-04A	ANCHORAGE FOR STEEL PLATE BEAM GUARD TYPE 2
14B16-04B	ANCHORAGE FOR STEEL PLATE BEAM GUARD TYPE 2
14B18-06A	STEEL PLATE BEAM GUARD, CLASS "A" (AT BRIDGES, OBSTACLES AND SIDEROADS/DRI VEWAYS)
14B18-06B	STEEL PLATE BEAM GUARD, CLASS "A" AT MEDIAN APPROACH TO BRIDGES
14B20-11A	STEEL THREE BEAM STRUCTURE APPROACH
14B20-11B	STEEL THREE BEAM STRUCTURE APPROACH, CONNECTION TO SQUARE END PARAPETS
14B42-07A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05A	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05E	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05F	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05G	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05H	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05I	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05J	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05K	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
14B45-05L	MIDWEST GUARDRAIL SYSTEM THREE BEAM TRANSITION (MGS)
15A04-07C	DELINEATOR BRACKET WITH REFLECTIVE SHEETING
15C08-21A	LONGITUDINAL MARKING (MAINLINE)
15C11-09B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15C12-09A	TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION
15C33-04	STOP LINE AND CROSSWALK PAVEMENT MARKING
15D31-04	TRAFFIC CONTROL, TEMPORARY BYPASS ROADWAY
15D33-07	TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS
15D39-02	TRAFFIC CONTROL, DROP-OFF SIGNING
15D44-02	TRAFFIC CONTROL, SIGNING ON ROADWAYS WITH MILLED SURFACES


WOOD STAKES (2 PER BALE)
NOMINAL 2" X 2" X 30" MIN.
LENGTH OR EQUIVALENT



NOTE:
ALL DIMENSIONS
ARE APPROXIMATE

EMBED BALES

SECTION A-A




FOR SCOUR PROTECTION USE:
EROSION MAT FOR CHANNEL LINING.
LAP MAT UNDER UPSTREAM BALES
AND SECURE FABRIC WITH WOOD STAKES,
AT 3-FOOT INTERVALS.

STAGGER JOINTS BETWEEN ADJACENT
ROWS OF BALES.

PLAN VIEW

BOTTOM ELEVATION OF END BALE SHALL
BE EQUAL TO OR GREATER THAN TOP OF
LOWEST MIDDLE BALE.




FRONT ELEVATION

TEMPORARY DITCH CHECK USING EROSION BALES ①

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

- ① TEMPORARY DITCH CHECKS EITHER EROSION BALES OR MANUFACTURED SHALL BE PAID FOR UNDER THE BID ITEM OF TEMPORARY DITCH CHECK. THE DEPARTMENT WILL NOT PAY FOR TEMPORARY DITCH CHECKS CONSTRUCTED OF A SINGLE ROW OF EROSION BALES.




PLAN VIEW

WHEN ALTERING THE DIRECTION OF FLOW



PLAN VIEW



FRONT ELEVATION


WHEN EXISTING GROUND SLOPES AWAY FROM FILL SLOPE

EROSION BALES FOR SHEET FLOW


TYPICAL INSTALLATIONS OF
EROSION BALES / TEMPORARY
DITCH CHECKS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
 6/04/02 /S/ Beth Canestra
 DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
 FHWA



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL

NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS




SILT FENCE

* NOTE: 8'-0" POST SPACING ALLOWED IF A WOVEN GEOTEXTILE FABRIC IS USED.



JOINING TWO LENGTHS OF SILT FENCE ⑤




SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)

SILT FENCE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
4-29-05 /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA




SECTION B - B

**TURBIDITY BARRIER - FLOAT ALTERNATIVE
CAUTION - SEE NOTE 6**




PLAN VIEW



SECTION A - A

TURBIDITY BARRIER - STANDARD POST INSTALLATION



PLAN VIEW


TURBIDITY BARRIER PLACEMENT DETAILS

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- ① DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- ② SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- ③ WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- ④ IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- ⑤ ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- ⑥ FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- ⑦ ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- ⑧ USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



PLAN VIEW



SECTION C - C


**TURBIDITY BARRIER DETAIL SHOWING
TYPICAL PLACEMENT AT STRUCTURES**

TURBIDITY BARRIER


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
6/4/02 DATE /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT
ENGINEER

FHWA



END VIEW



SIDE VIEW


CULVERT PIPE CHECK
(INSTALL ON INLET END ONLY)

CULVERT PIPE CHECK

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2019 /S/ Daniel Schave
DATE EROSION CONTROL ENGINEER

FHWA



TYPICAL BRIDGE TEMPORARY TRAFFIC SIGNAL LOCATION

LEGEND


- WOOD POLE (NON-BREAKAWAY)
- WOOD POST (BREAKAWAY)
- - - SIGNAL CABLE
- SIGNAL CABLE W/MESSENGER

➔ DIRECTION OF TRAFFIC


LED TRAFFIC SIGNAL WITH BACKPLATE
3-12"

GENERAL NOTES


- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.
- POLE MOUNTED TRAFFIC SIGNAL CONTROL CABINET MAY BE MOUNTED ON THE SERVICE POLE IF THE ELECTRICAL UTILITY ALLOWS THE INSTALLATION.
- WHEN UTILITY POLES ARE USED TO SPAN THE TEMPORARY OVERHEAD CABLE, WRITTEN PERMISSION MUST BE OBTAINED FROM THE OWNER OF THE POLES AND GIVEN TO THE PROJECT MANAGER. ALL PERTINENT UTILITY AND CODE CLEARANCES SHALL BE MAINTAINED.
- WOOD POLES (NON-BREAKAWAY) SHALL BE NO CLOSER TO EDGE OF PAVEMENT THAN OFFSET DISTANCE CHART ALLOWS OR 4 FEET BEHIND PROTECTIVE BARRIER (BEAM GUARD, ETC.).
- WOOD POSTS (BREAKAWAY) SHALL BE NO CLOSER THAN 2 FEET OUTSIDE OF SHOULDER.
- VERTICAL CLEARANCE ETC. PER NEC.
- TRAFFIC SIGNAL FACES SHALL BE TYPICALLY PLACED 12 FEET FROM EDGE OF PAVEMENT.
- EACH TRAFFIC SIGNAL SHALL HAVE A BACKPLATE.
- SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.



TYPICAL DROP TO TRAFFIC SIGNAL FACE



POLE MOUNT CABINET INSTALLATION



GROUND MOUNT CABINET INSTALLATION

MINIMUM POLE LENGTHS	CLASS	POLE BURIAL DEPTHS
25'	V	5'
30'	V	6'
35'	IV	7'
40'	IV	8'
45'	IV	9'

OFFSET DISTANCES FOR TEMPORARY NON-BREAKAWAY POLES	
SPEED LIMIT	OFFSET DISTANCE*
GREATER THAN 45 MPH	18 FT
45 MPH OR LESS	12 FT
45 MPH OR LESS W/CURBS	2 FT

* NOTE: OFFSET MEASURED FROM OUTER EDGE OF OUTSIDE THRU LANE.

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018 /S/ Ahmet Demirelek
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA

6


6

SDD09G02 - 05a

SDD09G02 - 05a

GENERAL NOTES

USE 3/4" DRILL IN WOOD POLE TO PROVIDE FOR 5/8" BOLTS.



SPAN WIRE POLE

GUY POLE


TYPICAL DEAD-ENDINGS OR GUYING

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2015 DATE /S/ Ahmet Demerbilek
ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA




TRAILER MOUNTED TRAFFIC SIGNAL

GENERAL NOTES

DETAIL OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.



TYPICAL TRAILER MOUNTED TRAFFIC SIGNAL LOCATION

LEGEND

- POST MOUNTED SIGN
- TEMPORARY PRECAST CONCRETE BARRIER
- TRAILER MOUNTED TRAFFIC SIGNAL
- REMOVE PAVEMENT MARKINGS
- DIRECTION OF TRAFFIC

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
June 2015 /S/ Ahmet Demerbilek
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER
FHWA

6

6

SDD09G02 - 05c

SDD09G02 - 05c




TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.



SECTION A-A



SPREAD OPEN SO THE TOP OF LUG IS 1 1/4" WIDE

ALTERNATE LUG


6

6

FOR MULTI-UNIT STRUCTURES
LINE 3 ABOVE SHALL READ


B = BRIDGE
C = CULVERT
R = RETAINING WALL

UNIT NO. FOR MULTIPLE
UNIT BRIDGE



**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.




ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)

S.D.D. 12 A 3-10

S.D.D. 12 A 3-10

NAME PLATE (STRUCTURES)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE 3/26/10	/S/ Scot Becker CHIEF STRUCTURAL DEVELOPMENT ENGINEER
FHWA	




PLACEMENT DETAIL FOR TYPE 1 MILLED RUMBLE STRIP

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

DO NOT MILL SHOULDER GROOVES THROUGH ANY INTERSECTION, MARKED CROSSWALK, NON-MOTORIZED PATH CROSSING, OR SNOWMOBILE CROSSING.


- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.



ISOMETRIC




TYPE 1
2 - LANE SHOULDER RUMBLE STRIP



SECTION A - A

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



6

6


PLACEMENT DETAIL FOR TYPE 2 MILLED RUMBLE STRIP

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

DO NOT MILL SHOULDER GROOVES THROUGH ANY INTERSECTION, MARKED CROSSWALK, NON-MOTORIZED PATH CROSSING, OR SNOWMOBILE CROSSING.


- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.



ISOMETRIC




TYPE 2
2 - LANE SHOULDER RUMBLE STRIP




SECTION A - A

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




SHOULDER GROOVES AT MISCELLANEOUS CROSSINGS




SHOULDER GROOVES AT RIGHT TURN LANE



SHOULDER GROOVES AT BRIDGES



SHOULDER GROOVES AT INTERSECTIONS WITH APPROACH TAPER




SHOULDER GROOVES AT DRIVEWAYS^①

GENERAL NOTES


- ① SHOULDER GROOVES MAY BE OMITTED IN AREAS WITH HIGH CONCENTRATIONS OF DRIVEWAYS. WHEN DIRECTED BY THE ENGINEER.

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



SHOULDER GROOVES AT RAILROADS



SHOULDER GROOVES AT PASSING AND CLIMBING LANES



SHOULDER GROOVES AT BYPASS LANES

**2-LANE RURAL SHOULDER
RUMBLE STRIP, MILLING**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
ENGINEER


GENERAL NOTES

- ① W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POSTS WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS. APPROVED PLASTIC BLOCKOUT DESIGNS MAY VARY FROM THIS TYPICAL DETAIL WHEN USED IN CONJUNCTION WITH STEEL POSTS. DO NOT MIX STEEL POSTS AND WOOD POSTS IN A SINGLE INSTALLATION.
- ② USE STRUCTURAL STEEL POSTS CONFORMING TO ASTM A 36. GALVANIZED POSTS ACCORDING TO AASHTO M 111. EITHER SET THE POSTS IN DRILLED HOLES OR DRIVE TO GRADE. REMOVE MUSHROOMING CAUSED BY DRIVING AND REPAIR DAMAGED SPELTER COATING ON GALVANIZED POSTS.
- ③ INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
- ④ USE EITHER WOOD OR APPROVED PLASTIC BLOCKOUTS ON WOOD POSTS.
- ⑤ IF THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING, W BEAM (LHW).
- ⑥ IF ROCK IS ENCOUNTERED DURING EXCAVATION, THE ENGINEER MAY APPROVE USING A 12 INCH DIAMETER POST HOLE EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE APPROXIMATELY 2 1/2 INCHES DEEP. CUT THE POSTS TO LENGTH AND PLACE IN THE HOLE. BACKFILL WITH MATERIAL EXCAVATED FROM THE HOLE AND COMPACT ADEQUATELY.
- ⑦ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.


INSTALL BEAM GUARD SECTIONS AND ALL NECESSARY HARDWARE ACCORDING TO THE APPLICABLE PLAN AND CURRENT STANDARD AND SUPPLEMENTAL SPECIFICATIONS. ALL DIMENSIONS ARE SUBJECT TO MANUFACTURER'S TOLERANCES EXCEPT WHERE ALLOWABLE TOLERANCES ARE SHOWN.




END VIEW SETTING STEEL OR WOOD POST IN ROCK ⑥




END VIEW LOCATED ALONG A CURBED ROADWAY



END VIEW LOCATED ALONG A ROADWAY SHOULDER STANDARD INSTALLATION




END VIEW STEEL POST & NOTCHED PLASTIC BLOCKOUT ALTERNATIVE STANDARD INSTALLATION




END VIEW LONGER POST AT HALF POST SPACING W BEAM (LHW)


TYPICAL INSTALLATION OF STEEL PLATE BEAM GUARD




STEEL POST & HOLE PUNCHING DETAIL (W6 X 9) ①
ALL HOLES 3/8" DIAMETER EXCEPT AS NOTED




WOOD POST (6" X 8") NOMINAL




WOOD OR PLASTIC BLOCKOUT FOR WOOD POSTS



TYPICAL NOTCHED PLASTIC BLOCKOUT FOR STEEL POSTS ①




PLAN VIEW WOOD POST, BLOCKOUT & BEAM




PLAN VIEW STEEL POST, NOTCHED PLASTIC BLOCKOUT & BEAM

STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATION & ELEMENTS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




SECTION THRU W BEAM




**FRONT VIEW
BEAM SPLICE AT WOOD POST
AND POST MOUNTING DETAIL**

GENERAL NOTES


- FURNISH GUARDRAIL DEFLECTORS FROM APPROVED PRODUCTS LIST.
- ⑨ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINA. START REFLECTORS AT POST #9 AND SPACE EVENLY EVERY 100 FEET (MAX.) TO THE END OF GUARDRAIL RUN, USING A MINIMUM OF 3 REFLECTORS.
 - ⑫ 8 - 5/8" ϕ X 2" BUTTON HEAD BOLTS WITH OVAL SHOULDERS & RECESS NUTS.
 - ⑬ 5/8" DIA. BUTTON HEAD BOLT AND RECESS NUT WITH 5/8" DIA. F844 FLAT WASHER UNDER NUT.



**FRONT VIEW
POST SPACING FOR LONGER POST
AT HALF POST SPACING W BEAM (LHW)**




**FRONT VIEW
BEAM SPLICE AT STEEL POST
TYPICAL SPlicing DETAILS
OF STEEL PLATE BEAM GUARD**




NESTED W BEAM (NW)
USE ALL OTHER STANDARD BEAM GUARD DETAILS FOR
CONSTRUCTING NESTED W BEAM (NW)

* USE DOUBLE SIDED WHITE GUARDRAIL REFLECTORS ON ROADWAYS WITH BI-DIRECTIONAL TRAFFIC (NO MEDIAN). USE SINGLE SIDED WHITE (RIGHT SIDE) AND SINGLE SIDED YELLOW (LEFT SIDE) ON ROADWAYS WITH MEDIAN SEPARATION.




**4" X 12" GUARDRAIL REFLECTOR DETAIL
AND TYPICAL INSTALLATION ***



4" x 12" GUARDRAIL REFLECTOR


**STEEL PLATE BEAM GUARD,
CLASS "A",
INSTALLATION & ELEMENTS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



DETAIL FOR DOUBLE BLOCKS

THE NUMBER OF DOUBLE BLOCK POSTS WITHIN A BARRIER RUN IS UNLIMITED




DETAIL FOR TRIPLE BLOCKS


TRIPLE BLOCK DETAIL IS LIMITED TO ONE LOCATION WITHIN A BEAM GUARD RUN.

NOTES: USE DOUBLE OR TRIPLE BLOCKS WHEN UNDERGROUND OBSTACLES PREVENT THE POST FROM BEING INSTALLED.

DO NOT USE EXTRA BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.




**PLAN VIEW
BEAM LAPPING DETAIL**




**POST DRIVING FOR CONTINUOUS
UNDERGROUND OBSTRUCTION**

STEEL PLATE BEAM GUARD, CLASS "A", INSTALLATION & ELEMENTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED June 2017	/s/ Rodney Taylor
DATE	ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	




PLAN VIEW




FRONT VIEW

END TREATMENT WITH TYPE 2 ANCHORAGE
(USE ON ONE-WAY ROADWAYS ONLY - DEPARTING END)



DETAIL "A"

POST NO. 1



STEEL BEARING PLATE

**ANCHORAGE FOR STEEL
PLATE BEAM GUARD
TYPE 2**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

S.D.D. 14 B 16-4a

S.D.D. 14 B 16-4a




FRONT VIEW




END VIEW

ANCHOR PLATE DETAIL



END VIEW OF BRACKET



CABLE ASSEMBLY

CABLE, SWAGE FITTING, STUD AND NUT SHALL DEVELOP A MINIMUM BREAKING STRENGTH OF 40,000 LB (TIGHTEN UNTIL TAUT)


GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


STRUCTURAL TUBING SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-500 GRADE B OR ASTM A-501.

POST NO. 1 SHALL BE WOOD BREAKAWAY POST INSERTED AND BOLTED INTO STEEL TUBE.


TYPE 2 ANCHORAGE SHALL CONSIST OF A STEEL TUBE, SOIL PLATE, WOOD BREAKAWAY POST, BEARING PLATE, ANCHOR PLATE, CABLE ASSEMBLY AND ALL ASSOCIATED HARDWARE, ALL STEEL PARTS SHALL BE GALVANIZED.




PLAN VIEW



**FRONT VIEW
W BEAM END SECTION ROUNDED**




WOOD BREAKAWAY POST




STEEL TUBE

STEEL TUBE SHALL CONFORM TO REQUIREMENTS OF ASTM A500



BREAKAWAY TERMINAL POST SLEEVE

GALVANIZED STANDARD STRENGTH STEEL PIPE, ASTM 53 GRADE "B"




SOIL PLATE

**ANCHORAGE FOR STEEL
PLATE BEAM GUARD
TYPE 2**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
8/21/2007 DATE /S/ Jerry H. Zogg
ROADWAY STANDARDS DEVELOPMENT
ENGINEER
FHWA



BEAM GUARD AT SIDEROADS OR DRIVEWAYS

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE PERTINENT STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

W6 X 9 OR W6 X 8.5 STEEL POSTS WITH NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POSTS WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.


THE LOCATIONS AND LENGTHS OF BEAM GUARD ARE SHOWN ELSEWHERE IN THE PLAN.

- ① STEEL THRIE BEAM STRUCTURAL APPROACH (STBSA) - SEE CURRENT SDD 14B20.
- ② USE AN APPROVED END TREATMENT FOR THE TRAFFIC APPROACH SIDE OF BRIDGE/OBSTACLES. USE TYPE 2 ANCHORAGE ONLY AT THE DOWNSTREAM ENDS OF BEAM GUARD LOCATED ALONG ROADWAYS WITH ONE WAY TRAFFIC.


MINIMUM LATERAL DISTANCE FROM FACE OF BEAM GUARD TO FIXED OBJECT	POST SPACING
3'-6"	3' - 1 1/2"
4'-6"	6' - 3"



**BEAM GUARD AT OBSTACLES
EXIT END - ONE WAY TRAFFIC**



BEAM GUARD AT FULL WIDTH BRIDGES




BEAM GUARD AT OBSTACLES - TWO WAY TRAFFIC

(RAIL TO OBSTACLE CLEARANCE 3'-6" TO 4'-6")

**TABLE 1
FLARE RATES FOR BEAM
GUARD AT NARROW BRIDGES**

POSTED SPEED (MPH)	FLARE RATE
25	13:1
30	15:1
35	16:1
40	18:1
45	21:1
50	24:1
55	26:1
65	30:1



**BEAM GUARD AT NARROW BRIDGES
(FLARED TO SHOULDER EDGE, THEN PARALLEL TO ROADWAY)**


**STEEL PLATE BEAM GUARD
CLASS "A"
AT BRIDGES, OBSTACLES
AND SIDEROADS/DRIVEWAYS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
8-21-07 DATE /s/ Jerry H. Zogg
ROADWAY STANDARDS DEVELOPMENT ENGINEER
FHWA

GENERAL NOTES

- ① STEEL THRIE BEAM STRUCTURAL APPROACH (STBSA) - SEE CURRENT SDD 14B20.
- ② LOCATIONS AND LENGTHS OF BEAM GUARD ARE SHOWN ELSEWHERE IN THE PLAN.



BEAM GUARD AT MEDIAN APPROACH TO BRIDGES



6

6

S.D.D. 14 B 18-6b


S.D.D. 14 B 18-6b

STEEL PLATE BEAM GUARD CLASS "A" AT MEDIAN APPROACH TO BRIDGES	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED	/S/ Jerry H. Zogg
8-21-07 DATE	ROADWAY STANDARDS DEVELOPMENT ENGINEER
FHWA	




GENERAL NOTES


- BOLT THE THRIE BEAM TO ALL POSTS AND BLOCKOUTS, DRILL OR PUNCH BOLT HOLES IN THE BEAM IF THE POST SPACING IS LESS THAN 6'-3".
- DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.
- IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B15 FOR MORE DETAILS.
- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② MINIMUM EMBEDMENT SHALL BE 4'-0". WHERE EXISTING CONDITIONS DO NOT PERMIT THE APPROPRIATE EARTHWORK SHOWN ON THE PLAN TYPICAL SECTIONS OR DETAILS, THE ENGINEER MAY ALLOW THE REDUCTION OR ELIMINATION OF THE 2 FOOT DISTANCE TO THE HINGE POINT. OTHERWISE BUILD AS THE PLAN SHOWS OR AS THE ENGINEER DIRECTS. IF THE 2 FOOT DISTANCE TO THE HINGE POINT IS REDUCED OR ELIMINATED, INCREASE THE POST EMBEDMENT DEPTH TO 4'-6" OR MORE.
- ③ POST BOLTS ARE 5/8" DIAMETER ASTM A307 BUTTON HEAD BOLT. A POST BOLT REQUIRES A 5/8" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX AND A 5/8" DIAMETER F844 FLAT WASHER. LENGTH OF POST BOLT MAY VARY.
- ④ ALL WOOD POSTS MUST BE 6" X 8" AND AT LEAST 7'-0" LONG.




TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE




THRIE BEAM TERMINAL CONNECTOR



THRIE BEAM SPLICE




SECTION THRU THRIE BEAM RAIL ELEMENT



SECTION A-A

STEEL THRIE BEAM STRUCTURE APPROACH	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 8/31/2012 DATE	/S/ Jerry H. Zogg ROADWAY STANDARDS DEVELOPMENT ENGINEER
FHWA	

① ② 7/8" DIA. HEX HEAD CAP SCREWS INTO THREADED INSERTS (FURNISHED WITH THE BRIDGE) WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER 7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED 1" DIA. HOLES DRILLED THRU PARAPET (5 REQ'D.)



FRONT VIEW

SECTION B-B



**THRIE BEAM CONNECTION TO BRIDGE
PARAPET WITH SQUARE ENDS**

GENERAL NOTES


THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

BOLTS, NUTS AND WASHERS SHALL CONFORM TO ASTM A325, A449 AND GALVANIZED PER STANDARD SPECIFICATIONS 614.

- ① DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ② BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM TERMINAL CONNECTOR. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/8" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ③ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ④ W6 X 9 OR W6 X 8.5 STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS ARE ACCEPTABLE ALTERNATIVES FOR 6" X 8" WOOD POST WITH WOOD OR PLASTIC BLOCKOUTS. USE APPROVED NOTCHED PLASTIC BLOCKOUTS WITH STEEL POSTS.
DO NOT USE STEEL POSTS AND NOTCHED PLASTIC BLOCKOUTS IN THE STEEL THRIE BEAM STRUCTURAL APPROACH AND THE TRANSITION SECTION OF STEEL PLATE BEAM GUARD, CLASS "A" INSTALLATIONS.



SECTION C-C



① ② 7/8" DIA. HEX HEAD CAP SCREWS INTO THREADED INSERTS (FURNISHED WITH THE BRIDGE) WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER 7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED 1" DIA. HOLES DRILLED THRU PARAPET (5 REQ'D.)

FRONT VIEW










**W BEAM TRANSITION AND CONNECTION TO
BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)**

**STEEL THRIE BEAM STRUCTURE
APPROACH, CONNECTION TO
SQUARE END PARAPETS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
8/31/2012 /S/ Jerry H. Zogg
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER
FHWA

- ① WOOD OR STEEL POSTS (w6X9 OR w6X8.5) MAY BE USED. DO NOT INTERMIX WOOD AND STEEL POSTS. INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
- ② USE WOOD OR APPROVED PLASTIC BLOCKOUTS. WOOD BLOCKOUTS MAY BE CONSTRUCTED OUT OF TWO OR MORE WOOD BLOCKOUTS. SEE ALTERNATE WOOD BLOCKOUT DETAIL. DIMENSIONS OF APPROVED PLASTIC BLOCKOUTS MAY VARY.
- ③ IF ROCK IS ENCOUNTERED DURING EXCAVATION, PROVIDE A HOLE 12 INCHES IN DIAMETER EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE APPROXIMATELY 2 1/2" INCHES OF GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE. CUT THE POSTS THE TO LENGTH AND INSTALL. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT. BACKFILL IS TO BE FREE OF LARGE ROCKS.
- ④ WHEN THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING (K).
- ⑤ FOR NEW MGS INSTALLATION TOP OF W-BEAM RAIL TOLERANCE IS ±1". FOR EXISTING MGS INSTALLATION TOP OF W-BEAM IS BETWEEN 27 3/4" TO 32".
- ⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ⑦ TOTAL POST LENGTH FOR TYPE K IS 7' - 0". TOTAL POST LENGTH FOR OTHER MGS TYPES IS 6' - 0".




**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




**FRONT VIEW
MID-SPAN BEAM SPLICE**

GENERAL NOTES


- ⑧ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.
 - ⑨ 25 FEET OF HALF POST SPACING IS REQUIRED ON APPROACH AND DEPARTURE ENDS OF QUARTER POST SPACING.
- POST BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND 3/8" DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS ARE BEING USED.
- GUARD RAIL SPLICE BOLTS ARE A 3/8" DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES 3/8" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.




**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**




FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



SECTION THRU W-BEAM RAIL



**FRONT VIEW
QUARTER POST SPACING (QS)**



**ONE SIDED REFLECTOR DETAIL
AND TYPICAL INSTALLATION**

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

SDD 14B42 - 07b

SDD 14B42 - 07b




DETAIL FOR 16" BLOCKOUT DEPTH

IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.

NOTE:



1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF 3/16".
2. IF THE BOLT EXTENDS MORE THAN 1/4" FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.




ALTERNATE BOLT HEAD

POST BOLT TABLE


L	T (MIN.)
1 1/4"	1 1/8"
2"	1 3/4"
10"	4"
14"	4 1/16"
18"	4"
21"	4 1/16"
25"	4"



**PLAN VIEW
BEAM LAPPING DETAIL**




**POST DRIVING FOR CONTINUOUS
UNDERGROUND OBSTRUCTION**




DETAIL FOR 36" BLOCKOUT DEPTH


NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL.
DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.



**POST BOLT, SPLICE BOLT
AND RECESS NUT**



SIDE VIEW




PLAN VIEW

**ALTERNATE WOOD
BLOCKOUT DETAIL**


⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS, INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN MGS GUARDRAIL




MISSING POST IN MGS GUARDRAIL NEAR EAT




MISSING POST IN MGS GUARDRAIL NEAR AN APPROACH TRANSITION



MISSING POST IN MGS GUARDRAIL NEAR FLARED BEAM GUARD




MISSING POST IN MGS GUARDRAIL NEAR A TYPE 2 END TERMINAL




MISSING POST IN SHORT SPAN MGS GUARDRAIL NEAR CURB (SL)

- 400 MAX SPAN 12' - 6"
- 401 2' MIN.
- 402 MGS GUARDRAIL 3
- 403 NESTING BEAM GUARD
- 404 ASYMMETRIC TRANSITION
- 405 SOIL WELL DRAINED AND COMPACTED
- 406 SEE OTHER DRAWINGS IN THIS SDD
- 407 SEE OTHER DRAWINGS FOR MIN. SPACING BETWEEN SPANS
- 408 SEE SDD 14B44
- 409 SEE SDD 14B45
- 410 SEE SDD 14B47
- 411 MINIMUM DISTANCE BETWEEN MISSING POST SPANS.



SECTION A - A



SECTION B - B

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2021 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
<small>FHWA</small>	

GENERAL NOTES

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
 - (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED
 - (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W - BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
 - (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF - TAPPING SCREWS. ONE SCREW PER CORNER.
 - (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.
- DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.


SEE SDD 14B42 FOR MORE INFORMATION.

* DO NOT ATTACH BLOCKOUTS TO POST 1 AND 2.


DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.

SEE MANUFACTURER'S DRAWING FOR SPLICE LOCATION, HARDWARE DIMENSIONS AND INSTALLATION INSTRUCTIONS.


THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.




PLAN




ELEVATION




DETAIL "A"




**SECTION C - C
TYPICAL AT POST NOS. 3 - 9**



**SECTION B - B
TYPICAL AT POST NO. 2***



**SECTION A - A
TYPICAL AT POST NO. 1***



DETAIL "B"

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

SDD 14B44 - 04a


SDD 14B44 - 04a

BILL OF MATERIALS


PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2



GENERIC GROUND STRUT ⑨ ⑤



GENERIC ANCHOR CABLE BOX ⑨ ⑤



BEARING PLATE ⑥ ⑤

6


6

SDD 14B44 - 04b


SDD 14B44 - 04b

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




UPPER POST NO. 1 ⁽¹⁾ (E)




LOWER POST NO. 1 ⁽²⁾ (E)




WOOD CRT POST ⁽³⁾ (E)
POSTS NUMBER 3-9



UPPER POST NO. 2 ⁽¹⁵⁾ (E)




LOWER POST NO. 2 ⁽¹⁶⁾ (E)



WOOD BLOCKOUT ⁽⁴⁾
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2


6




REFLECTIVE SHEETING DETAIL ^(E)

TYPE H
YELLOW REFLECTIVE
SHEETING 3" X 9".
SEE STANDARD
SPECIFICATION 637.


E.A.T. MARKER
POST (YELLOW)



FRONT VIEW SIDE VIEW
E.A.T. MARKER POST ⁽¹³⁾



SIDE VIEW



TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL

6

SDD 14B44 - 04c


SDD 14B44 - 04c

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR

FHWA



TWO WAY TRAFFIC



ONE WAY TRAFFIC

(T) THRIE BEAM CONNECTION

(W) W-BEAM CONNECTION WHEN REQUIRED

TYPICAL LOCATIONS OF THRIE BEAM AND W-BEAM CONNECTIONS TO BRIDGE

GENERAL NOTES


IF ROCK IS ENCOUNTERED, REMOVE ROCK TO FULL DEPTH OF POST PLUS 2 1/2", AND 12" DIAMETER AROUND POST. SEE 14B42 FOR MORE DETAILS.

TRANSITION USES STEEL POSTS ONLY.


SEE STANDARD DETAIL DRAWING 14 B 42 FOR MORE INFORMATION.

POST 2 THROUGH 17 USES STEEL POST ONLY

- ① BRIDGE RAILING TYPE "W" DOES NOT REQUIRE A TERMINAL CONNECTOR.
- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD14B42



PLAN VIEW



ELEVATION VIEW

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

S.D.D. 14 B 45-5a


S.D.D. 14 B 45-5a

GENERAL NOTES


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ③ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ④ TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42



**SECTION A-A
POSTS 1-5**



**SECTION B-B
POST 6**



**SECTION C-C
POSTS 7-11**







PLATE WASHER DETAIL



SPLICE DETAIL



**THRIE BEAM
TERMINAL CONNECTOR**




**SECTION THRU THRIE
BEAM RAIL ELEMENT**


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


**SECTION D-D
POSTS 12-17**




W-BEAM TO THRIE BEAM TRANSITION SECTION




6'-3\"/>




12'-6\"/>




ALTERNATE WOOD BLOCKOUT DETAIL




STEEL POSTS 1-5




STEEL POSTS 6-17




TOP VIEW



**FRONT VIEW
BLOCKOUT
POSTS 1-5**



TOP VIEW



**FRONT VIEW
BLOCKOUT
POSTS 6-17**

GENERAL NOTES

- STEEL POSTS ARE W6X9 OR W6X8.5.
- BOLT HOLES FOR POST ARE ON FRONT AND OF SIDE OF POST.
- (3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- (5) WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.
- (13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

S.D.D. 14 B 45-5c

S.D.D. 14 B 45-5c




FRONT VIEW

THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS


SECTION E-E

GENERAL NOTES

- THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.
- (2) OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
 - (4) TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
 - (6) DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
 - (7) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
 - (8) THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".




SECTION F-F



FRONT VIEW

W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



DRILL HOLE LOCATION

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

GENERAL NOTES

THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ⑨ BOLT, NUT AND WASHERS NOT REQUIRED FOR THIS LOCATION WHEN RETROFITTING AN EXISTING PAPAPET AND THE HOLE IS EITHER ABOVE PARAPET OR WITHIN 4 INCHES OF THE EDGE OF PARAPET.




FRONT VIEW

W BEAM CONNECTION TO VERTICAL FACE PARAPET

(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



SECTION G-G



FRONT VIEW


THRIE BEAM CONNECTION TO VERTICAL FACED PARAPETS

MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

ONE WAY
TRAFFIC



W-BEAM
TERMINAL
CONNECTOR

FRONT VIEW

**W BEAM CONNECTION TO
PARAPETS WITH SLOPED ENDS**


(USE ONLY AT TRAFFIC EXIT END OF ONE WAY BRIDGE)

WHEN RETROFITTING A TRANSITION
TO AN EXISTING RIGID BARRIER,
INSTALL PLATE WASHERS ON
BACKSIDE OF RIGID BARRIER.


⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO
THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(4 REQ'D.)

GENERAL NOTES

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



DRILL HOLE LOCATION AND PATTERN
FOR THRIE BEAM CONNECTION




FRONT VIEW

**THRIE BEAM CONNECTION TO BRIDGE
PARAPETS WITH SLOPED ENDS**

WHEN RETROFITTING A TRANSITION
TO AN EXISTING RIGID BARRIER,
INSTALL PLATE WASHERS ON
BACKSIDE OF RIGID BARRIER.

⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO
THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(5 REQ'D.)



SECTION I-I

PLATE
WASHER (TYP.)

NUT (TYP.)
WASHER
(TYP.)

1/2"

BACKSIDE OF
RIGID BARRIER

THRIE BEAM
TERMINAL
CONNECTOR


BOLT HEAD
WASHER
(TYP.)

TRAFFIC SIDE OF
RIGID BARRIER


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



BACK-UP PLATE DETAIL




SECTION J-J




BACK-UP PLATE MOUNTING ONTO BRIDGE RAILING

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1'$.
- ⑥ DRILLING HOLES THROUGH THE PAPER, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.




**FRONT VIEW
THRIE BEAM CONNECTION TO
STEEL RAILING TYPE "W"**



FRONT VIEW

**THRIE BEAM CONNECTION TO
TUBULAR RAILING TYPE "F"**



SECTION K-K


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


(4) TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".




FRONT VIEW




**PLAN VIEW
BACK-UP PLATE DETAIL, TYPE "M"**



**FRONT VIEW
ANCHOR PLATE DETAIL, TYPE "M"**




SECTION M-M



SECTION L-L


FRONT VIEW

ANCHOR AND BACK-UP PLATE MOUNTING TO BRIDGE RAILING, TYPE "M"



FRONT VIEW

M



PLAN VIEW

THRIE BEAM CONNECTION TO TUBULAR RAILING, TYPE "M"

6

6

S.D.D. 14 B 45-5h


S.D.D. 14 B 45-5h

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE FHWA	/s/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR

GENERAL NOTES

- COVER PLATE PANELS ARE 3/16" THICK.
- ALL STIFFENERS ARE 1/4" THICK.
- CONNECTOR PLATE SHALL BE FABRICATED FROM ASTM GRADE A36 STEEL AND GALVANIZED.
- FOR GALVANIZED REQUIREMENTS, SEE SECTION 614 OF THE STANDARD SPECIFICATIONS.
- ALL HOLE DIAMETERS SHALL BE 1".
- FOR OPPOSITE SIDE INSTALLATION MIRROR DRAWINGS.

- (10) STIFFENERS LOCATED AT THE OUTSIDE EDGES OF THE COVER PLATES SHALL BE WELDED AS FOLLOWS:
SINGLE BEVEL GROOVE WELD ON EXTERNAL SIDES AND 3/16" FILLET WELD BY 1" LONG SPACED AT 2" ON INTERNAL SIDES.
- (11) STIFFENERS LOCATED ON THE INSIDE OF THE COVER PLATE SHALL BE WELDED AS FOLLOWS:
3/16" FILLET WELD BY 1" LONG SPACED AT 2".



WELDING INSTRUCTION
(VIEWED FROM BACK SIDE OF PLATE)




PLATE AND STIFFENER IDENTIFICATION
(VIEWED FROM BACK SIDE OF PLATE)

CONNECTOR PLATE DIMENSION (PER ASSEMBLY)				
PLATE	QUANTITY	SHAPE	SIZE (A x B x C x D)	THICKNESS
P1	1		20" x 20"	3/16"
P2	1		20" x 20" x 28 3/16"	3/16"
P3	1		39" x 3 5/8" x 20" x 19 5/16"	3/16"
S1	4		18 7/16" x 3 5/8" x 18 3/4"	1/4"
S2	1		10 1/4" x 2 1/16" x 10 3/8" x 1/2"	1/4"
S3	1		3" x 1 1/16" x 3 3/8" x 1/2"	1/4"
S4	1		6 1/8" x 2 1/16"	1/4"
S5	1		6 1/8" x 1 1/16"	1/4"
S6	1		7 3/4" x 1 3/4"	1/4"
S7	1		2 3/16" x 6" x 3 5/8" x 5 1/8"	1/4"
S8	1		1 5/32" x 7 1/2" x 2 1/2" x 7 3/8"	1/4"
S9	1		6 1/16" x 6 3/16" x 1 3/32"	1/4"
S10	1		1 7/8" x 9 7/8" x 3 3/8" x 9 11/16"	1/4"
S11	1		8 1/2" x 8 3/4" x 1 3/16"	1/4"

SINGLE SLOPE CONNECTION PLATE

**MIDWEST GUARDRAIL SYSTEM
THREE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018
DATE

/S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR


FHWA

GENERAL NOTES


CONNECTOR PLATE, DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.



⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTION PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



THRIE BEAM CONNECTION TO SINGLE SLOPE BARRIER



SECTION N-N




SINGLE SLOPE CONNECTION PLATE PLACEMENT


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA



**ELEVATION OF DETAIL AT NY3 END POST
THRIE BEAM RAIL ATTACHMENT**



**ELEVATION OF DETAIL AT NY4 END POST
THRIE BEAM RAIL ATTACHMENT**

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS ± 1".
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND 1/2-INCH BEYOND NUT.


6

6

S.D.D. 14 B 45-5k

S.D.D. 14 B 45-5k


MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	



FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY3"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS ± 1".
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND 1/2-INCH BEYOND NUT.




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY4"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)


MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION


APPROVED
 DATE 7/2018 /S/ Rodney Taylor
 ROADWAY STANDARDS DEVELOPMENT
 UNIT SUPERVISOR
 FHWA




MOUNTING DETAIL FOR DELINEATOR REFLECTOR



DETAIL "A" 3" X 6" DELINEATOR REFLECTOR



DELINEATOR POST



SECTION A - A
WEIGHT 1.12 LBS PER FT. \ 0.1 LB.

REFLECTOR SPACING TABLE


REFLECTOR SPACING	LOCATION
* 100' C-C	RAMPS
400' C-C	MAINLINE

* START AT BEGINNING OF RAMP TAPER AND END AT END OF RAMP TAPER



GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


- ① DELINEATORS SHALL BE PLACED AT A CONSTANT DISTANCE FROM THE EDGE OF THE SHOULDER FOR THE LENGTH OF THE INSTALLATION.
- ② FURNISH TYPE H SHEETING FROM THE APPROVED PRODUCTS LIST.



TYPICAL INSTALLATIONS OF DELINEATOR POSTS



TYPICAL INSTALLATIONS OF FLEXIBLE DELINEATOR POSTS



DELINEATOR POST WITH REFLECTIVE SHEETING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2021 /S/ Matthew Rauch
DATE STATE SIGNING AND MARKING ENGINEER




FHWA


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.


- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.

LEGEND

-  "T" MARKING
-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC




TWO WAY TRAFFIC



ONE WAY TRAFFIC


PERMANENT PAVEMENT MARKING




PERMANENT LONGITUDINAL PAVEMENT MARKINGS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE: May 2022 /S/ Jeannie Silver
STATEWIDE SIGNING AND MARKING ENGINEER




DRUM



42" CONE

DO NOT USE IN TAPERS
½ SPACING OF DRUMS




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.






**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2021 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

LEGEND

-  SIGN ON PORTABLE OR PERMANENT SUPPORT
-  TEMPORARY PORTABLE RUMBLE STRIP ARRAY
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLAGGER, EQUIPPED WITH STOP/SLOW PADDLE FASTENED ON SUPPORT STAFF

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP OR QUEUE.

WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.

FLAGGING

FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING.

- ① FOR MOVING WORK OPERATIONS, POST ADDITIONAL W20-7A FLAGGER SIGNS AT APPROXIMATELY 3,500' INTERVALS IN THE MOVING WORK OPERATION OR AS APPROVED BY THE ENGINEER.
- ② SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA.

WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED.

TEMPORARY PORTABLE RUMBLE STRIPS

UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS.


- ③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSE ACROSS THE LANE AT THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER

ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST.

INSTALL TEMPORARY RUMBLE STRIPS PER MANUFACTURER'S RECOMMENDATIONS.

PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS.

DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS.




STOP/SLOW PADDLE ON SUPPORT STAFF

SIGN AND TEMPORARY RUMBLE STRIP ARRAY SPACING TABLE

SPEED LIMIT	SPACING "A"
25-30 MPH	200'
35-40 MPH	350'
45-55 MPH	500'



USE OF W03-4 SIGN IS OPTIONAL. WHEN USED, THIS SIGN SHALL BE LOCATED BETWEEN THE W20-7A AND W20-4A SIGNS, USING SPACING "A".



TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE: May 2022 /S/ Andrew Heidtke
WORK ZONE ENGINEER

FHWA


GENERAL NOTES

STOP SIGN SHALL BE PLACED A MINIMUM OF 6 FEET TO A MAXIMUM OF 50 FEET FROM THE EDGELINE LOCATION.


- ① 18-INCH STOP LINES MAY BE DELETED OR ADDED BY THE REGION MARKING ENGINEER BASED ON VISIBILITY AND SIGHT LINES.
- ② NO STOP LINE IS REQUIRED IF STOP SIGN IS LESS THAN OR EQUAL TO 40 FEET FROM THE EDGELINE.
- ③ NO STOP LINE IS REQUIRED IF STOP SIGN IS LESS THAN OR EQUAL TO 30 FEET FROM THE FLANGELINE EXTENSION.
- ④ MOVE CLOSER TO THE EDGE OF TRAVEL LINE AS NEEDED FOR VISIBILITY AND SIGHT LINES (NO CLOSER THAN 4 FEET).
- ⑤ LADDER BAR CROSSWALKS SHOULD ONLY BE USED FOR MID BLOCK CROSSINGS. USE 2 - 6" TRANSVERSE LINES INSTEAD.




TYPICAL STOP LINE PAVEMENT MARKING WITH CURB AND GUTTER



TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH RIGHT TURN LANE



TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH CROSSWALK MARKING



TYPICAL STOP LINE PAVEMENT MARKING WITHOUT CURB AND GUTTER

STOP LINE AND CROSSWALK PAVEMENT MARKING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2019 /S/ Matthew Rauch
DATE STATE SIGNING AND MARKING ENGINEER

FHWA

LEGEND

- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TEMPORARY DELINEATOR (WHITE, SINGLE DELINEATOR)
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- TEMPORARY RAISED PAVEMENT MARKERS (TWO WAY YELLOW)
- TEMPORARY STEEL PLATE BEAM GUARD AND END TREATMENT
- DIRECTION OF TRAFFIC
- REMOVE PAVEMENT MARKINGS
- WORK AREA


GENERAL NOTES

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED.
 "WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.
 ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.
 THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.
 THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500' DESIRABLE) DISTANCE TO EXISTING SIGNS.
 SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE FHWA'S MANUAL ON STANDARD HIGHWAY SIGNS OR THE WISCONSIN STANDARD SIGN PLATES.
 EQUIPMENT, VEHICLES, OR MATERIAL SHOULD NOT BE STORED IN BUFFER SPACE.

- ① IF ADVISORY SPEED IS GREATER THAN 30 MPH, USE THE WO1-4 SIGN. IF ADVISORY SPEED IS 30 MPH OR LESS, USE THE WO1-3 SIGN.
- ② WHEN THE DISTANCE TO / FROM THE NEXT CLOSEST NO-PASSING ZONE IS LESS THAN THE MINIMUM DISTANCE BETWEEN ZONES AS INDICATED IN THE SPECIFICATIONS, THE TWO ZONES SHALL BE CONNECTED.
- ③ OMIT THESE WO1-6 SIGNS IF THE ADVISORY SPEED OF THE CURVE IS GREATER THAN 30 MPH.
- ④ TEMPORARY STEEL PLATE BEAM GUARD AND END TREATMENT WHEN INCLUDED IN THE CONTRACT. FOR LAYOUT, SEE DETAILS ELSEWHERE IN THE PLAN.

S (MPH)	BUFFER SPACE (DESIRABLE)
25	55'
30	85'
35	120'
40	170'
45	220'
50	280'
55	335'

S = NON-CONSTRUCTION SPEED LIMIT (MPH)



**TRAFFIC CONTROL,
TEMPORARY BYPASS
ROADWAY**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED _____
 February 2022 DATE /S/ Andrew Heidtke
 WORK ZONE ENGINEER

FHWA

SDD 15D31 - 04

SDD 15D31 - 04

LEGEND

- TYPE III BARRICADE WITH ATTACHED SIGN
- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TRAFFIC CONTROL DRUM
- FLAGS, 16" X 16" MIN. (ORANGE)
- REMOVING PAVEMENT MARKING
- DIRECTION OF TRAFFIC
- ASPHALTIC PAVEMENT WIDENING
- CONCRETE BARRIER TEMPORARY PRECAST
- TEMPORARY SIGNAL. SEE SDD 09G02 FOR EXACT PLACEMENT

WIDTH ON SIGN TO BE APPROX. 1-FOOT LESS THAN AVAILABLE WIDTH. (OMIT IF AVAILABLE WIDTH IS MORE THAN 16 FEET)

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE..

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.


ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.


ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.

REMOVE PAVEMENT MARKING AND PLACE TEMPORARY PAVEMENT MARKING LINES IF THE CLOSURE IS TO BE IN PLACE FOR 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

- ① 500 FOOT SPACING SHOWN IS FOR ROADWAYS WITH A PRE-CONSTRUCTION REGULATORY SPEED LIMIT OF 45 MPH OR MORE. FOR 35 - 40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25 - 30 MPH, USE 200 FOOT TYPICAL SPACING.
- ② USE 300 FOOT SPACING IF THE PRE - CONSTRUCTION REGULATORY SPEED IS 35 MPH OR LESS.
- ③ DIMENSION DETERMINED BY CBTP TAPER FROM EDGE LINE TO TANGENT SECTION OF THE ROAD.
- ④ TEMPORARY PAVEMENT MARKING LINE, 18 INCH WHITE STOP LINE.
- ⑤ 700 FOOT TEMPORARY PAVEMENT MARKING LINE, 4 INCH DOUBLE YELLOW . WHEN THE DISTANCE FOR THE PRECEDING NO - PASSING ZONE IS LESS THAN THE MINIMUM DISTANCE BETWEEN ZONES AS INDICATED IN THE SPECIFICATIONS, THE TWO ZONES SHALL BE CONNECTED.
- ⑥ SEE SDD 15C02 - SHEET "F" FOR ADVANCED WIDTH RESTRICTION SIGNING.



TEMPORARY PAVEMENT MARKING LINE, 4 INCH WHITE (STOPLINE TO STOPLINE). REMOVE EXISTING EDGELINE AND OFFSET THE TEMPORARY EDGELINE IF THE DISTANCE FROM THE EDGELINE TO CONCRETE BARRIER WALL IS LESS THAN 9 FEET.




**TRAFFIC CONTROL,
ONE LANE ROAD
WITH TEMPORARY SIGNALS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2022 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER


FHWA



MULTI-LANE




TWO-WAY TWO LANE



SECTION A - A

OR

SECTION A - A



MULTI-LANE BASE PATCHING

ADJACENT LANE DROP-OFFS

GENERAL NOTES


- FOR SPOT LOCATIONS USE ENGINEERING JUDGEMENT WHEN PLACING ADDITIONAL SIGNS.
- ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.
- "WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.
- WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.
- * IF THE DROP-OFF IS CONTINUOUS ALONG THE PROJECT, PLACE ADDITIONAL SIGNS EVERY 1 MILE AND AFTER EVERY ENTRANCE RAMP.
- ① USE CLOSER SPACING WHEN DELINEATING DROP-OFF.

LEGEND


- SIGN ON TEMPORARY SUPPORT
- TRAFFIC CONTROL DRUM
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- DIRECTION OF TRAFFIC
- WORK AREA WITH DROP-OFF
- MILLED SURFACE

6

6



SHOULDER DROP-OFFS



SECTION B - B

D	SIGN (C)
< 2" WITH A SLOPE STEEPER THAN 3:1	LOW SHOULDER WO8-9
2" < 6" WITH A SLOPE STEEPER THAN 3:1	SHOULDER DROP - OFF W8-9A PROVIDE A 3:1 OR FLATTER SLOPE OF MATERIAL ADJACENT TO THE PAVEMENT

SDD 15D39 - 02

SDD 15D39 - 02

**TRAFFIC CONTROL,
DROP-OFF SIGNING**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018 /S/ Andrew Heidtke
DATE DATE WORK ZONE ENGINEER

FHWA

GENERAL NOTES

DRAWING NOT TO SCALE. ALL SIGNS AND POSTS ON THIS SHEET SHALL BE PAID FOR WITH 'TRAFFIC CONTROL SIGNS' BID ITEM. ALL SIDE ROADS WHICH ARE UNDER CONSTRUCTION OF CURB AND GUTTER AND/OR GRADING SHALL BE ADEQUATELY SIGNED.

ALL SIGNS AND DEVICES SHALL BE IN CONFORMANCE WITH THE WISCONSIN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (WMUTCD). SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE WISDOT STANDARD SIGN PLATES.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THAT THE BACKGROUND IS ORANGE.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.



THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.


ALL SIGNS INAPPROPRIATE TO THE STATUS OF THE CONTROL ZONE, INCLUDING PRE-EXISTING SIGNS IN THE VICINITY, SHALL BE COVERED OR REMOVED AS DIRECTED BY THE ENGINEER.

SEE 15C34 FOR ADDITIONAL TRAFFIC CONTROL SIGNING WHEN CENTERLINE PAVEMENT MAKINGS ARE MISSING. 'DO NOT PASS' SIGNS MUST BE INSTALLED ON THE SAME DAY AS MILLING OPERATIONS.


- ① PLACE SIGNS 350' IN ADVANCE OF MILLED SURFACES AND AT 1 MILE INTERVALS, OR AS DIRECTED BY THE ENGINEER.
- ② PLACE SIGN 200' MIN. FROM INTERSECTION AND 200' MIN. AFTER ADVANCE WARNING SIGN SHOWN IN SDD 15C04.

LEGEND

-  SIGN ON TEMPORARY SUPPORT
-  DIRECTION OF TRAFFIC



TYPICAL SIDE ROAD APPROACH SIGN DETAIL



SEE SDD15C04 FOR ADVANCE WARNING SIGNS

SEE SDD15C04 FOR ADVANCE WARNING SIGNS

DETAIL FOR SIGNING ON MILLED SURFACES

TRAFFIC CONTROL, SIGNING ON ROADWAYS WITH MILLED SURFACES

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

DESIGN DATA

LIVE LOAD:
 DESIGN LOADING: HL-93
 INVENTORY RATING FACTOR: RF = 1.08
 OPERATING RATING FACTOR: RF = 1.40
 WISCONSIN STANDARD PERMIT VEHICLE (WIS.-SPV): 250 (KIPS)

STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 POUNDS PER SQUARE FOOT.

MATERIAL PROPERTIES:

CONCRETE MASONRY:
 SUPERSTRUCTURE $f'_c = 4,000$ P.S.I.
 ALL OTHER $f'_c = 3,500$ P.S.I.

BAR STEEL REINFORCEMENT:
 GRADE 60 $f_y = 60,000$ P.S.I.

FOUNDATION DATA

ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 STEEL PILING DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 125 TONS ** PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC FORMULA, ESTIMATED 105' LONG.

PIER TO BE SUPPORTED ON HP 10 X 42 STEEL PILING DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 180 TONS ** PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC FORMULA, ESTIMATED 105' LONG.

** THE FACTORED AXIAL RESISTANCE OF PILES IN COMPRESSION USED FOR DESIGN IS THE REQUIRED DRIVING RESISTANCE MULTIPLIED BY A RESISTANCE FACTOR OF 0.5 USING MODIFIED GATES TO DETERMINE DRIVEN PILE CAPACITY.

HYDRAULIC DATA

100 YEAR FREQUENCY

$Q_{100} = 800$ C.F.S.
 $VEL_{100} = 4.95$ F.P.S.
 $HW_{100} = EL. 677.14$
 WATERWAY AREA = 161.62 SQ. FT.
 DRAINAGE AREA = 1.6 SQ. MI.
 ROADWAY OVERTOPPING = N/A
 SCOUR CRITICAL CODE = 8

TRAFFIC VOLUME

STH 37
 ADT = 1,300 (2045)
 R.D.S. = 60 M.P.H.

2 YEAR FREQUENCY

$Q_2 = 100$ C.F.S.
 $VEL_2 = 2.01$ F.P.S.
 $HW_2 = EL. 675.53$

LIST OF DRAWINGS

1. GENERAL PLAN
2. CROSS SECTION & QUANTITIES
3. SUBSURFACE EXPLORATION
4. WEST ABUTMENT
5. WEST ABUTMENT DETAILS
6. EAST ABUTMENT
7. EAST ABUTMENT DETAILS
8. PIER
9. SUPERSTRUCTURE
10. CAMBER DETAILS
11. SUPERSTRUCTURE DETAILS
12. SINGLE SLOPE PAPARPET 42SS

STRUCTURE DESIGN CONTACTS:
 JOHN SENDOR (608) 266-5163
 DOMINIQUE BECHLE (608) 261-8205

NO.	DATE	REVISION	BY

ACCEPTED *[Signature]* **DMB** 08/08/22
 CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-06-207

STH 37 OVER BRANCH TROUT CREEK







COUNTY BUFFALO TOWN ALMA

DESIGN SPEC. AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

DESIGNED BY JJS DESIGNED CK'D. EJV DRAWN BY DDS PLANS CK'D. JJS

GENERAL PLAN SHEET 1 OF 12

- * PROVIDE FOR THREE BEAM GUARD RAIL ATTACHMENT, AT UNUSED ANCHOR ASSEMBLIES CAULK HOLES SHUT WITH "100% SILICONE CAULK".
- Ⓜ INDICATES WING NUMBER
- ▲ BENCH MARK AND NAME PLATE FOR LOCATIONS SEE 'SINGLE SLOPE PARAPET 42SS' SHEET.




8

8


SCALE = 6.00

GENERAL NOTES


- DRAWINGS SHALL NOT BE SCALED.
- BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
- THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.
- BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS OTHERWISE NOTED.
- THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES B-06-207" SHALL BE THE EXISTING GROUNDLINE.
- AT THE BACK FACE OF ABUTMENT ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL TYPE A.
- EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.
- THE QUANTITY FOR BACKFILL STRUCTURE IS CALCULATED BASED ON THE DETAIL SHOWN IN THE PLANS.
- PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO THE ENTIRE EXPOSED TOP OF DECK AND TO THE VERTICAL AND HORIZONTAL SURFACES OF THE PAVING NOTCHES AT ABUTMENT DIAPHRAGMS.
- PIGMENTED SURFACE SEALER TO BE APPLIED TO THE FRONT FACE AND THE TOP OF THE PARAPETS, INCLUDING PARAPETS ON WINGS.
- THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH HEAVY RIPRAP AND GEOTEXTILE TYPE "HR" TO THE EXTENT SHOWN ON SHEET I AND THE ABUTMENT DETAILS.
- SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE, UNLESS AN ALTERNATE METHOD IS APPROVED BY THE ENGINEER.
- AT ABUTMENTS, HP 12 X 53 STEEL PILING MAY BE USED IN LIEU OF HP 10 X 42 STEEL PILING, PAYMENT SHALL BE BASED ON BID PRICE FOR HP 10 X 42 STEEL PILING.
- THE EXISTING STREAM BED SHALL BE USED AS THE UPPER LIMITS OF EXCAVATION AT THE PIER.
- AT ABUTMENTS AND PIER, CONCRETE POURED UNDER WATER WILL BE ALLOWED AND SHALL BE DONE IN ACCORDANCE WITH SECTION 502.3.5.3 OF THE STANDARD SPECIFICATIONS. CONCRETE POURED UNDERWATER SHALL NOT EXCEED 10'-0" IN DEPTH, UNLESS APPROVED OTHERWISE.



CROSS SECTION THROUGH ROADWAY
(LOOKING EAST)




PROFILE GRADE LINE - STH 37



ABUTMENT BACKFILL DIAGRAM FOR WINGS PARALLEL TO ROADWAY

- L = OUT TO OUT OF ABUTMENT, INCLUDING WINGS (FT)
- H = AVERAGE ABUTMENT FILL HEIGHT (FT)
- EF = EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)
- $V_{CF} = (L)(3.0)(H) + (L)(0.5)(1.5H)(H)$
- $V_{CY} = V_{CF} / 27$
- $V_{TON} = V_{CY} (2.0)$



TYPICAL SECTION THRU ABUTMENT

- ▲ BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- PIPE UNDERDRAIN WRAPPED (6 INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN.


TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	SUPER.	WEST ABUT.	PIER	EAST ABUT.	TOTALS
203.0260	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS B-06-896	EACH	---	---	---	---	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGE B-06-207	EACH	---	---	---	---	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	---	146	---	146	292
502.0100	CONCRETE MASONRY BRIDGES	CY	171	36	34	36	277
502.3200	PROTECTIVE SURFACE TREATMENT	SY	269	---	---	---	269
502.3210	PIGMENTED SURFACE SEALER	SY	68	10	---	10	88
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	---	2,230	---	2,230	4,460
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	36,470	1,990	1,560	1,990	42,010
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	---	11	---	11	22
550.1100	PILING STEEL HP 10-INCH X 42 LB	LF	---	630	735	630	1,995
606.0300	RIPRAP HEAVY	CY	---	98	---	98	196
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	---	74	---	74	148
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	4	---	---	---	4
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	---	35	---	35	70
645.0120	GEOTEXTILE TYPE HR	SY	---	175	---	175	350
SPV.0090	REMOVING EXISTING TIMBER PILING	LF	---	---	360	---	360
NON-BID ITEMS							
	FILLER	SIZE	---	---	---	---	1/2", 3/4"

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
CROSS SECTION & QUANTITIES			SHEET 2

BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
1	3/30/2018	317697	544578
2	3/28/2018	317740	544692
3	3/29/2018	317737	544728
4	3/30/2018	317750	544756
5	3/30/2018	317774	544822
6	3/27/2018	317810	544784

BORINGS COMPLETED BY: AET
 REPORT COMPLETED BY: AET
 ALL COORDINATES REFERENCED TO WCCS NAD 83(9) BUFFALO COUNTY
 COORDINATES COLLECTED USING NON-SURVEY GRADE EQUIPMENT



STATE PROJECT NUMBER
7125-00-71

MATERIAL SYMBOLS

ASPHALT	TOPSOIL	PEAT
CONCRETE	FILL	GRAVEL
SAND	CLAY	SILT
BOULDERS OR COBBLES	LIMESTONE	BEDROCK (UNKNOWN)
SHALE	SANDSTONE	IGNEOUS/META

LEGEND OF BORING

ST (1) 0.25 (2) 17

F-C COBBLE OR BOULDER
 WEATHERED LIMESTONE
 CORE RUN #1 - 24'-29'
 REC=80%, ROD=72%

GROUND WATER ELEVATION
 ▽ AT TIME OF DRILLING
 ▽ END OF DRILLING
 ▽ AFTER DRILLING

ABBREVIATIONS
 F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION


BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY TLP/DD		PLANS CK'D. JJS	
SUBSURFACE EXPLORATION		SHEET 3	


8

8


SCALE = 15.00




ELEVATION
(LOOKING WEST) ◀ = MOVE STIRRUPS BARS TO MISS PILES




PLAN



PILE PLAN



SECTION THRU BODY



RODENT SHIELD DETAIL


* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.


- (A01) CONST. JOINT: KEYWAY FORMED BY A BEVELED 2" X 6".
- (A06) SUPPORT ABUTMENT ON HP 10 X 42 STEEL PILING. ESTIMATED 105 FEET LONG WITH A REQUIRED DRIVING RESISTANCE OF 125 TONS PER PILE.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A17) 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING, GRAY, NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (A22) A510 BARS @ 1'-0" CTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
WEST ABUTMENT		SHEET 4	




OUTSIDE WING ELEVATION

WING 1 SHOWN, WING 2 SIMILAR




SECTION THRU WING


WING 1 SHOWN, WING 2 SIMILAR




A501, A512



A403



A507, A511




A805

BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	LOCATION
A501		47	14'-0"	X	BODY - STIRRUP
A402		12	2'-3"		BODY - 2 PER BODY PILE - VERT.
A403		6	28'-0"	X	BODY - 1 PER BODY PILE - VERT.
A604		11	38'-2"		BODY - HORIZ.
A805		14	11'-2"	X	BODY - HORIZ. - B.F. - AT BOTH ENDS
A606		7	24'-0"		BODY - HORIZ. - B.F.
A507		12	4'-11"	X	BODY - TOP - VERT.
A408		3	12'-0"		BODY - TOP - HORIZ.
A409		8	4'-7"		BODY - VERT. - AT BODY ENDS ONLY
A22	A510	X	37	2'-0"	DOWEL BARS
A511	X	28	9'-0"	X	WINGS 1&2 - VERT.
A512	X	22	15'-8"	X	WINGS 1&2 - STIRRUP
A513	X	12	12'-2"		WINGS 1&2 - HORIZ. - F.F.
A614	X	16	11'-11"		WINGS 1&2 - HORIZ.
A415	X	12	9'-8"		WINGS 1&2 - HORIZ. - F.F. & B.F
A616	X	4	9'-8"		WINGS 1&2 - HORIZ. - F.F. & B.F
A417	X	20	2'-0"		WINGS 1&2 - HORIZ.



PILE DETAILS

- (A03) OPTIONAL CONST. JOINT: KEYWAY FORMED BY BEVELED 2 x 6. (18" RMW @ B.F. & 3/4" "V" GROOVE @ F.F. IF JOINT IS USED).
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A16) A417 BARS SPACED @ 1'-0" CTRS. EMBED 1'-0" INTO WING CONC. LOCATE 3" DOWN FROM TOP OF WING @ BACKFACE TO 6" DOWN @ WING TIP.
- (A17) 1/2" FILLER (INCLUDED IN WING LENGTH); SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (A21) FOR PPT. BARS & DIMENSIONS SEE "SINGLE SLOPE PARAPET 42SS" SHEET.
- (A22) A510 BARS @ 1'-0" CTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)

NO.	DATE	REVISION	BY


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-06-207


DRAWN BY DDS PLANS CK'D. JJS

**WEST ABUTMENT
DETAILS**


SHEET 5




ELEVATION
(LOOKING EAST) ◀ = MOVE STIRRUPS BARS TO MISS PILES




PLAN



PILE PLAN



SECTION THRU BODY



RODENT SHIELD DETAIL


* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIAALLY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.


- (A01) CONST. JOINT: KEYWAY FORMED BY A BEVELED 2" X 6".
- (A06) SUPPORT ABUTMENT ON HP 10 X 42 STEEL PILING, ESTIMATED 105 FEET LONG WITH A REQUIRED DRIVING RESISTANCE OF 125 TONS PER PILE.
- (A15) PIPE UNDERDRAIN WRAPPED (6-INCH), SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- (A17) 1/2" FILLER (INCLUDED IN WING LENGTH); SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING, GRAY, NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- (A19) 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- (A22) B510 BARS @ 1'-0" CTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
EAST ABUTMENT		SHEET 6	




OUTSIDE WING ELEVATION

WING 3 SHOWN, WING 4 SIMILAR




SECTION THRU WING

WING 3 SHOWN, WING 4 SIMILAR




B501, B512




B403

5 WRAP SPIRAL



B507, B511




B805

BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFY THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	LOCATION
B501		47	14'-0"	X	BODY - STIRRUP
B402		12	2'-3"		BODY - 2 PER BODY PILE - VERT.
B403		6	28'-0"	X	BODY - 1 PER BODY PILE - VERT.
B604		11	38'-2"		BODY - HORIZ.
B805		14	11'-2"	X	BODY - HORIZ. - B.F. - AT BOTH ENDS
B606		7	24'-0"		BODY - HORIZ. - B.F.
B507		12	4'-11"	X	BODY - TOP - VERT.
B408		3	12'-0"		BODY - TOP - HORIZ.
B409		8	4'-7"		BODY - VERT. - AT BODY ENDS ONLY
A22	X	37	2'-0"		DOWEL BARS
B511	X	28	9'-4"	X	WINGS 3&4 - VERT.
B512	X	22	15'-8"	X	WINGS 3&4 - STIRRUP
B513	X	12	12'-2"		WINGS 3&4 - HORIZ. - F.F.
B614	X	16	11'-11"		WINGS 3&4 - HORIZ.
B415	X	12	9'-8"		WINGS 3&4 - HORIZ - F.F. & B.F.
B616	X	4	9'-8"		WINGS 3&4 - HORIZ - F.F. & B.F.
A16	X	20	2'-0"		WINGS 3&4 - HORIZ.



PILE DETAILS

A03 OPTIONAL CONST. JOINT: KEYWAY FORMED BY BEVELLED 2 x 6. (18" RMW @ B.F. & 3/4" "V" GROOVE @ F.F. IF JOINT IS USED).

A15 PIPE UNDERDRAIN WRAPPED (6-INCH), SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.

A16 B417 BARS SPACED @ 1'-0" CTRS. EMBED 1'-0" INTO WING CONC. LOCATE 3" DOWN FROM TOP OF WING @ BACKFACE TO 6" DOWN @ WING TIP.

A17 1/2" FILLER (INCLUDED IN WING LENGTH): SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.

A19 18" (RMW) RUBBERIZED MEMBRANE WATERPROOFING SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.

A21 FOR PPT. BARS & DIMENSIONS SEE "SINGLE SLOPE PARAPET 42SS" SHEET.

A22 B510 BARS @ 1'-0" CTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)

NO.	DATE	REVISION	BY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-06-207

DRAWN BY DDS PLANS CK'D. JJS









**EAST ABUTMENT
DETAILS**

SHEET 7

BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
P401	X	20	35'-0"			PIER - HORIZ.
P402	X	18	6'-4"	X		PIER - HORIZ.
P503	X	80	8'-7"			PIER - VERT.
P504	X	19	3'-10"	X		PIER - VERT. - TOP
P405	X	49	3'-0"	X		PIER - TIE BARS
P506	X	6	4'-10"	X		PIER - VERT. - TOP
P407	X	4	5'-7"			PIER - HORIZ. - TOP
P508	X	37	2'-0"			PIER - DOWEL BARS




- (P02) SUPPORT PIER ON HP 10 X 42 STEEL PILING, ESTIMATED 105'-0" LONG WITH A REQUIRED DRIVING RESISTANCE OF 180 TONS PER PILE.
- (P08) P508 BARS @ 1'-0" CTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)
- (P09) KEYED CONST. JOINT-FORMED BY BEVELED 2 X 6.


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
PIER		SHEET 8	

8


8



SECTION THRU SLAB




PLAN



SECTION THRU BRIDGE IN SPAN (SHOWING SLAB REINFORCEMENT)

(P09) KEYED CONST. JOINT-FORMED BY BEVELED 2" X 6" BETWEEN BEAM SEATS.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
SUPERSTRUCTURE		SHEET 9	



SURVEY TOP OF SLAB ELEVATIONS

	W. ABUTMENT	5/10 PT.	PIER	5/10 PT.	E. ABUTMENT
N. GUTTER					
CROWN OR \bar{R}					
S. GUTTER					

PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF DECK ELEVATIONS AT THE \bar{C} OF ABUTMENTS, THE \bar{C} OF PIERS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR \bar{C} . RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.

CAMBER AND SLAB THICKNESS DIAGRAM

CAMBER SHOWN IS BASED ON 3 TIMES DEAD LOAD DEFLECTIONS. CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION AND FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT. PARAPETS, SIDEWALKS AND MEDIANS PLACED ON TOP OF THE SLAB SHALL BE POURED AFTER FALSEWORK HAS BEEN RELEASED, EXCEPT FOR STAGED CONSTRUCTION.

TO DETERMINE FALSEWORK ELEVATION AT EDGE OF SLAB, CROWN OR REFERENCE LINE FOLLOW THIS PROCEDURE:

TOP OF SLAB ELEVATION AT FINAL GRADE
 LESS SLAB THICKNESS
 PLUS CAMBER
 PLUS FORM SETTLEMENT/DEFLECTION DUE TO PLACEMENT OF SLAB CONCRETE (TO BE COMPUTED BY THE CONTRACTOR)
 EQUALS TOP OF SLAB FALSEWORK ELEVATION.

TOP OF SLAB ELEVATIONS

	\bar{C} BRG. W. ABUT.	1/10	2/10	3/10	4/10	5/10	6/10	7/10	8/10	9/10	\bar{C} PIER	1/10	2/10	3/10	4/10	5/10	6/10	7/10	8/10	9/10	\bar{C} BRG. E. ABUT.
N. EDGE OF DECK	679.46	679.44	679.43	679.41	679.39	679.38	679.36	679.35	679.33	679.31	679.30	679.28	679.26	679.25	679.23	679.21	679.20	679.18	679.16	679.15	679.13
CROWN OR \bar{R}	679.82	679.80	679.79	679.77	679.75	679.74	679.72	679.71	679.69	679.67	679.66	679.64	679.62	679.61	679.59	679.57	679.56	679.54	679.52	679.51	679.49
S. EDGE OF DECK	679.46	679.44	679.43	679.41	679.39	679.38	679.36	679.35	679.33	679.31	679.30	679.28	679.26	679.25	679.23	679.21	679.20	679.18	679.16	679.15	679.13

NOTES

TOP TRANSVERSE BARS IN SLAB SHALL BE SUPPORTED BY INDIVIDUAL BAR CHAIRS AT APPROXIMATELY 3'-0" CENTERS EACH WAY. BOTTOM LONGITUDINAL BARS SHALL BE SUPPORTED BY CONTINUOUS BAR CHAIRS AT APPROXIMATELY 4'-0" CENTERS.


ALL SLAB THICKNESS DIMENSIONS ARE MINIMUM. ANY TOLERANCES NECESSARY TO CORRECT CONSTRUCTION DISCREPANCIES ARE TO BE PLUS (+).

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
CAMBER DETAILS		SHEET 10	


BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE


BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
S1001	X	77	19'-6"			SLAB - LONGITUDINAL - TOP
S802	X	77	29'-5"			SLAB - LONGITUDINAL - TOP
S803	X	77	60'-0"			SLAB - LONGITUDINAL - BOTTOM
S604	X	77	7'-6"			SLAB - LONGITUDINAL - BOTTOM
S505	X	136	38'-2"			SLAB - TRANSVERSE - TOP & BOTTOM
S506	X	134	5'-0"			SLAB - TRANSVERSE - EDGES OF SLAB
S507	X	78	3'-4"	X		ABUT. DIAPH. - VERT.
S508	X	78	7'-0"	X		ABUT. DIAPH. - VERT.
S509	X	6	38'-2"			ABUT. DIAPH. - TRANSVERSE
S510	X	198	4'-5"	X		PARAPET - VERT.
S511	X	206	6'-8"	X		PARAPET - VERT.
S512	X	8	5'-10"	X		PARAPET - VERT.
S513	X	32	35'-0"			PARAPET - HORIZ.




S507




S508




S510



S511



S512



SECTION THRU PARAPET ON SLAB

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-06-207			
DRAWN BY		DDS	PLANS CK'D. JJS
SUPERSTRUCTURE DETAILS		SHEET 11	

BILL OF BARS

FOR ABUTMENT PARAPETS


BAR MARK	COAT	WEST ABUT.	EAST ABUT.	LENGTH	BENT	BAR SERIES	LOCATION
R501	X	3	3	5'-10"	X		PARAPET VERT.
R502	X	3	3	6'-8"	X		PARAPET VERT.
R503	X	22	22	3'-0"	X		PARAPET VERT.
R504	X	34	34	5'-7"	X		PARAPET VERT.
R505	X	10	10	6'-5"	X		PARAPET VERT.
R506	X	12	12	6'-6"	X		PARAPET VERT.
R507	X	2	2	9'-7"	X		PARAPET HORIZ.
R508	X	10	10	9'-7"			PARAPET HORIZ.
R509	X	12	12	5'-5"	X	▲	PARAPET VERT.
R510	X	4	4	9'-7"	X		PARAPET HORIZ.

▲ LENGTH SHOWN FOR BAR IS AN AVERAGE LENGTH AND SHOULD ONLY BE USED FOR BAR WEIGHT CALCULATIONS. SEE BAR SERIES TABLE FOR ACTUAL LENGTHS.

BAR SERIES TABLE


BAR MARK	NO. REQ'D	LENGTH
R509	4 SERIES OF 6	4'-9" TO 6'-1"

BUNDLE AND TAG EACH SERIES SEPARATELY.



PARAPET END TREATMENT DETAIL


LOOKING AT INSIDE FACE OF PARAPET



SECTION A-A


SECTION B-B

SECTION C-C






PLAN

NW CORNER SHOWN, OTHERS SIMILAR




INSIDE ELEVATION

NW CORNER SHOWN, OTHERS SIMILAR



■ BENCH MARK CAP



DETAIL OF ANCHOR ASSEMBLY

NOTE: HEX HEAD CAP SCREWS & WASHERS TO BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 CLASS C.

ASSEMBLY SHALL BE BID ITEM "ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD", EACH.

- CONST. JOINT - STRIKE OFF AS SHOWN
- R503 BARS MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. USE CARE TO PLACE R503 BARS CORRECTLY ALONG TRANSITION OF PARAPET.
- ▽ R501 AND R504 BARS TO BE TIED TO WING STEEL BEFORE WING IS POURED.

NO.	DATE	REVISION	BY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-06-207

DRAWN BY: DDS PLANS CK'D: JJS

SINGLE SLOPE PARAPET 42SS SHEET 12


DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION (1)		SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	205.0500 MARSH EXCAVATION (6)	205.0200 ROCK EXCAVATION (7)	REDUCED MARSH IN FILL (8)	REDUCED EBS IN FILL (9)	EXPANDED MARSH BACKFILL (10)	EXPANDED EBS BACKFILL (11)	EXPANDED ROCK (12)	UNEXPANDED FILL	EXPANDED FILL (13)	MASS ORDINATE +/- (14)	WASTE	208.0100 BORROW	COMMENT:
			FACTOR 0.6	FACTOR 0.8					FACTOR 1.5	FACTOR 1.3	FACTOR 1.1	FACTOR 1.25							
DIVISION 1																			
TEMP BYPASS	10+00 - 14+00		29	0	0	29	0	0	0	0	0	0	0	1,345	0	0	0	0	BREAKER RUN TO BE USED IN PLACE OF BORROW
DIVISION 1 SUBTOTAL			29	0	0	29	0	0	0	0	0	0	0	1,345	0	0	0	0	
DIVISION 2																			
STH 37	540+00 - 545+00		452	0	367	85	0	0	0	0	0	0	0	337	421	-337	0	337	
	545+50-547+75		231	0	259	-28	0	0	0	0	0	0	0	92	115	-143	0	143	
DIVISION 2 SUBTOTAL			683	0	626	57	0	0	0	0	0	0	0	429	536	-479	0	479	
DIVISION 3																			
BYPASS REMOVAL	10+00 - 14+00		1,345	0	0	1,345	0	0	0	0	0	0	0	0	0	1,345	1,345	0	
DIVISION 3 SUBTOTAL			1,345	0	0	1,345	0	0	0	0	0	0	0	0	0	1,345	1,345	0	
GRAND TOTAL			2,057	0	626	1,431	0	0	0	0	0	0	0	1,774	536	866	1,345	479	
TOTAL COMMON EXC			2,057																

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
 - (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
 - (3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNERS CHOICE, CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL.
 - (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL.
 - (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL.
 - (6) MARSH EXCAVATION - TO BE BACKFILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNERS CHOICE, CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL. ITEM NUMBER 205.0500
 - (7) ROCK EXCAVATION ITEM NUMBER 205.0200
 - (8) REDUCED MARSH IN FILL - EXCAVATED MARSH MATERIAL IS USUABLE IN FILLS OUTSIDE THE 1:1 SLOPE. MARSH IN FILL REDUCTION FACTOR = 0.60
 - (9) REDUCED EBS IN FILL - EXCAVATED EBS MATERIAL IS USUABLE IN FILLS OUTSIDE THE 1:1 SLOPE. EBS IN FILL REDUCTION FACTOR = 0.8
 - (10) EXPANDED MARSH BACKFILL - THIS IS TO BE FILLED WITH SELECT BORROW MATERIAL. MARSH BACKFILL FACTOR = 1.5. ITEM NUMBER 208.1100
 - (11) EXPANDED EBS BACKFILL - THIS IS TO BE FILLED WITH SELECT BORROW MATERIAL. EBS BACKFILL FACTOR = 1.30. ITEM NUMBER 208.1100
 - (12) EXPANDED ROCK FACTOR = 1.10
 - (13) EXPANDED FILL FACTOR = 1.25
- DEPENDENT ON SELECTIONS:
- EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH - REDUCED EBS) * FILL FACTOR
 - OR EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED EBS) * FILL FACTOR
 - OR EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH) * FILL FACTOR
 - OR EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK) * FILL FACTOR
- (14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

9

9




9

9

PROJECT NO: 7125-00-71 HWY: STH 37 COUNTY: BUFFALO CROSS SECTIONS: STH 37 SHEET E


FILE NAME: W:\7390_03\CAD\7125-00-01\SHEETSPLAN\090201_XS.DWG PLOT DATE: 6/29/2020 3:03 PM PLOT BY: MARZOLF, ROBBIE PLOT NAME: PLOT SCALE: 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 1



9





9



PROJECT NO: 7125-00-71 HWY: STH 37 COUNTY: BUFFALO CROSS SECTIONS: STH 37 SHEET E

FILE NAME: W:\7390_03\CAD\17125-00-01\SHEETSPLAN\090201_XS.DWG PLOT DATE: 6/29/2020 3:03 PM PLOT BY: MARZOLF, ROBBY PLOT NAME: PLOT SCALE: 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

LAYOUT NAME - 2




9


9

PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	CROSS SECTIONS: STH 37	SHEET	E
------------------------	-------------	-----------------	------------------------	-------	---

STRUCTURE B-06-0207
 STA. 544+86 - 545+54




PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	CROSS SECTIONS: STH 37	SHEET	E
------------------------	-------------	-----------------	------------------------	-------	---



PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	CROSS SECTIONS: STH 37	SHEET 9
------------------------	-------------	-----------------	------------------------	---------

FILE NAME : W:\7390_03\CAD\17125-00-01\SHEETSPLAN\090201_XS.DWG PLOT DATE : 6/29/2020 3:03 PM PLOT BY : MARZOLF, ROBBI PLOT NAME : PLOT SCALE : 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49




LAYOUT NAME - 5




PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	CROSS SECTIONS: TEMP BYPASS	SHEET
------------------------	-------------	-----------------	-----------------------------	-------

9

9





PROJECT NO: 7125-00-71	HWY: STH 37	COUNTY: BUFFALO	CROSS SECTIONS: TEMP BYPASS	SHEET
------------------------	-------------	-----------------	-----------------------------	-------

FILE NAME : W:\7390_03\CAD\1 7125-00-01\SHEETSPLAN\090202_XS.DWG PLOT DATE : 6/29/2020 2:47 PM PLOT BY : MARZOLF, ROBBY PLOT NAME : PLOT SCALE : 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

9

9

Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>