



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

January 26, 2023

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #29: 4160-06-71, WISC 2023231**  
**V Kimberly – CTH N**  
**S Railroad St Intersection**  
**CTH CE**  
**Outagamie County**

### Letting of February 14, 2023

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Added Special Provisions	
Article No.	Description
33	Pipe Grates, 42-Inch, Item 611.9800.S.01

Deleted Special Provisions	
Article No.	Description
15	Pipe Grates

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
611.9800.S.01	Pipe Grates, 42-Inch	Each	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
611.9800.S	Pipe Grates	Each	1	-1	0

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
84	Miscellaneous Quantities (updated Pipe Grates bid item)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**4160-06-71**

**January 26, 2023**

**Special Provisions**

**15. DELETED**

**33. Pipe Grates, 42-Inch, Item 611.9800.S.01.**

**A Description**

This special provision describes providing pipe grates for pipe apron endwalls as detailed in the plans.

**B Materials**

Furnish steel conforming to the requirements of standard spec 506.2.2.1. Furnish steel pipe conforming to the requirements of standard spec 506.2.3.6.

Furnish pipe grates galvanized according to ASTM A123.

Furnish angles and brackets galvanized according to ASTM A123.

Furnish required hardware galvanized according to ASTM A153.

**C Construction**

Repair pipes, rods, angles and brackets on which the galvanized coating has been damaged according to the requirements of AASHTO M36.

**D Measurement**

The department will measure Pipe Grates in units of work, where one unit is one grate, completed and accepted.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
611.9800.S.01	Pipe Grates, 42-Inch	EACH

Payment is full compensation for furnishing and installing all materials; and for drilling and connecting grates to apron endwalls.

stp-611-010 (20230113)

**Schedule of Items**

Attached, dated January 26, 2023, are the revised Schedule of Items Pages 1 – 12.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 84

END OF ADDENDUM

STORM SEWER STRUCTURES AND COVERS

CATEGORY	STRUCTURE	522.1024 APRON	522.1042 ENDWALLS FOR APRON	522.1042 CULVERT PIPE REINFORCED CONCRETE 24- INCH	611.0530 MANHOLE COVERS TYPE J EACH	611.0535 MANHOLE COVERS TYPE J- SPECIAL EACH	611.0612 INLET COVERS TYPE C EACH	611.0624 INLET COVERS TYPE H EACH	611.0627 INLET COVERS TYPE RIM EACH	611.0642 INLET COVERS TYPE S EACH	611.0666 INLET COVERS TYPE Z EACH	611.2004 MANHOLES 4-FT DIAMETER EACH	611.2006 MANHOLES 6-FT DIAMETER EACH	611.3003 INLETS 3-FT DIAMETER EACH	611.3004 INLETS 4-FT DIAMETER EACH	611.3230 INLETS 2X3-FT EACH	611.3901 INLETS MEDIAN 1 GRATE EACH	611.9800.5.01 PIPE GRATES, 42-INCH EACH	SPV.0060.09 INLETS 6-FT DIAMETER EACH	SPV.0060.10 INLETS 9-FT DIAMETER EACH
0010	10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	11	-	-	-	-	-	-	1	-	-	-	-	-	-	-	1	-	-	-	-
0010	12	-	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	13	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	14	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	20	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	21	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	30	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	31	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	32	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	32A	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	33	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0011	34	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	40	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	41	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	42	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	43	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	44	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	45	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	46	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	47	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	50	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	51	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	60	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
0010	61	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
1	1	1	1	1	1	1	1	4	12	1	3	1	1	1	2	13	1	1	1	1

\*ADDITIONAL QUANTITIES SHOWN ELSEWHERE

Addendum No. 01  
ID 4160-06-71  
Revised Sheet 84  
January 26, 2023



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0004	204.0100 Removing Concrete Pavement	68.000 SY	_____.	_____.
0006	204.0110 Removing Asphaltic Surface	344.000 SY	_____.	_____.
0008	204.0150 Removing Curb & Gutter	3,813.000 LF	_____.	_____.
0010	204.0155 Removing Concrete Sidewalk	312.000 SY	_____.	_____.
0012	204.0170 Removing Fence	50.000 LF	_____.	_____.
0014	204.0195 Removing Concrete Bases	11.000 EACH	_____.	_____.
0016	204.0210 Removing Manholes	2.000 EACH	_____.	_____.
0018	204.0220 Removing Inlets	8.000 EACH	_____.	_____.
0020	204.0245 Removing Storm Sewer (size) 01. 12-Inch	76.000 LF	_____.	_____.
0022	204.0245 Removing Storm Sewer (size) 02. 36-Inch	188.000 LF	_____.	_____.
0024	204.0245 Removing Storm Sewer (size) 03. 42-Inch	139.000 LF	_____.	_____.
0026	204.9060.S Removing (item description) 01. Removing Traffic Signals CTH CE & Railroad St	1.000 EACH	_____.	_____.
0028	205.0100 Excavation Common	5,027.000 CY	_____.	_____.
0030	213.0100 Finishing Roadway (project) 01. 4160-06-71	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	305.0110 Base Aggregate Dense 3/4-Inch	92.000 TON	_____.	_____.
0034	305.0120 Base Aggregate Dense 1 1/4-Inch	6,630.000 TON	_____.	_____.
0036	310.0115 Base Aggregate Open-Graded	14.000 CY	_____.	_____.
0038	311.0110 Breaker Run	2,730.000 TON	_____.	_____.
0040	416.1010 Concrete Surface Drains	2.000 CY	_____.	_____.
0042	455.0605 Tack Coat	130.000 GAL	_____.	_____.
0044	460.2000 Incentive Density HMA Pavement	1,150.000 DOL	1.00000	1,150.00
0046	460.6223 HMA Pavement 3 MT 58-28 S	1,070.000 TON	_____.	_____.
0048	460.7424 HMA Pavement 4 HT 58-28 H	715.000 TON	_____.	_____.
0050	465.0105 Asphaltic Surface	80.000 TON	_____.	_____.
0052	465.0125 Asphaltic Surface Temporary	10.000 TON	_____.	_____.
0054	520.8000 Concrete Collars for Pipe	7.000 EACH	_____.	_____.
0056	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	132.000 LF	_____.	_____.
0058	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	3.000 EACH	_____.	_____.
0060	522.1042 Apron Endwalls for Culvert Pipe Reinforced Concrete 42-Inch	1.000 EACH	_____.	_____.
0062	601.0407 Concrete Curb & Gutter 18-Inch Type D	601.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	601.0411 Concrete Curb & Gutter 30-Inch Type D	691.000 LF	_____.	_____.
0066	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	3,202.000 LF	_____.	_____.
0068	601.0600 Concrete Curb Pedestrian	50.000 LF	_____.	_____.
0070	602.0405 Concrete Sidewalk 4-Inch	8,721.000 SF	_____.	_____.
0072	602.0415 Concrete Sidewalk 6-Inch	156.000 SF	_____.	_____.
0074	602.0515 Curb Ramp Detectable Warning Field Natural Patina	80.000 SF	_____.	_____.
0076	606.0100 Riprap Light	2.000 CY	_____.	_____.
0078	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	32.000 LF	_____.	_____.
0080	608.0342 Storm Sewer Pipe Reinforced Concrete Class III 42-Inch	324.000 LF	_____.	_____.
0082	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	434.000 LF	_____.	_____.
0084	608.3012 Storm Sewer Pipe Class III-A 12-Inch	36.000 LF	_____.	_____.
0086	608.3018 Storm Sewer Pipe Class III-A 18-Inch	64.000 LF	_____.	_____.
0088	611.0530 Manhole Covers Type J	1.000 EACH	_____.	_____.
0090	611.0535 Manhole Covers Type J-Special	1.000 EACH	_____.	_____.
0092	611.0612 Inlet Covers Type C	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0094	611.0624 Inlet Covers Type H	4.000 EACH	_____.	_____.
0096	611.0627 Inlet Covers Type HM	12.000 EACH	_____.	_____.
0098	611.0642 Inlet Covers Type MS	1.000 EACH	_____.	_____.
0100	611.0666 Inlet Covers Type Z	3.000 EACH	_____.	_____.
0102	611.2004 Manholes 4-FT Diameter	1.000 EACH	_____.	_____.
0104	611.2006 Manholes 6-FT Diameter	1.000 EACH	_____.	_____.
0106	611.3003 Inlets 3-FT Diameter	3.000 EACH	_____.	_____.
0108	611.3004 Inlets 4-FT Diameter	2.000 EACH	_____.	_____.
0110	611.3230 Inlets 2x3-FT	13.000 EACH	_____.	_____.
0112	611.3901 Inlets Median 1 Grate	1.000 EACH	_____.	_____.
0114	611.8115 Adjusting Inlet Covers	3.000 EACH	_____.	_____.
0118	612.0106 Pipe Underdrain 6-Inch	280.000 LF	_____.	_____.
0120	619.1000 Mobilization	1.000 EACH	_____.	_____.
0122	620.0300 Concrete Median Sloped Nose	520.000 SF	_____.	_____.
0124	625.0100 Topsoil	4,700.000 SY	_____.	_____.
0126	627.0200 Mulching	3,500.000 SY	_____.	_____.
0128	628.1504 Silt Fence	235.000 LF	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0130	628.1520 Silt Fence Maintenance	470.000 LF	_____.	_____.
0132	628.1905 Mobilizations Erosion Control	5.000 EACH	_____.	_____.
0134	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0136	628.2006 Erosion Mat Urban Class I Type A	4,700.000 SY	_____.	_____.
0138	628.2008 Erosion Mat Urban Class I Type B	175.000 SY	_____.	_____.
0140	628.7005 Inlet Protection Type A	20.000 EACH	_____.	_____.
0142	628.7010 Inlet Protection Type B	1.000 EACH	_____.	_____.
0144	628.7015 Inlet Protection Type C	24.000 EACH	_____.	_____.
0146	628.7020 Inlet Protection Type D	1.000 EACH	_____.	_____.
0148	628.7504 Temporary Ditch Checks	75.000 LF	_____.	_____.
0150	628.7555 Culvert Pipe Checks	5.000 EACH	_____.	_____.
0152	629.0210 Fertilizer Type B	6.000 CWT	_____.	_____.
0154	630.0120 Seeding Mixture No. 20	63.000 LB	_____.	_____.
0156	630.0140 Seeding Mixture No. 40	86.000 LB	_____.	_____.
0158	630.0200 Seeding Temporary	244.000 LB	_____.	_____.
0160	630.0500 Seed Water	204.000 MGAL	_____.	_____.
0162	634.0614 Posts Wood 4x6-Inch X 14-FT	38.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0164	637.2210 Signs Type II Reflective H	338.250 SF	_____.	_____.
0166	637.2215 Signs Type II Reflective H Folding	89.520 SF	_____.	_____.
0168	637.2230 Signs Type II Reflective F	36.000 SF	_____.	_____.
0170	638.2102 Moving Signs Type II	1.000 EACH	_____.	_____.
0172	638.2602 Removing Signs Type II	21.000 EACH	_____.	_____.
0174	638.3000 Removing Small Sign Supports	13.000 EACH	_____.	_____.
0176	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0178	643.0300 Traffic Control Drums	18,000.000 DAY	_____.	_____.
0180	643.0420 Traffic Control Barricades Type III	4,600.000 DAY	_____.	_____.
0182	643.0705 Traffic Control Warning Lights Type A	8,450.000 DAY	_____.	_____.
0184	643.0715 Traffic Control Warning Lights Type C	4,100.000 DAY	_____.	_____.
0186	643.0800 Traffic Control Arrow Boards	107.000 DAY	_____.	_____.
0188	643.0900 Traffic Control Signs	4,750.000 DAY	_____.	_____.
0190	643.1050 Traffic Control Signs PCMS	14.000 DAY	_____.	_____.
0192	643.3150 Temporary Marking Line Removable Tape 4-Inch	12,700.000 LF	_____.	_____.
0194	643.5000 Traffic Control	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0196	644.1440 Temporary Pedestrian Surface Matting	292.000 SF	_____.	_____.
0198	644.1601 Temporary Pedestrian Curb Ramp	20.000 DAY	_____.	_____.
0200	644.1605 Temporary Pedestrian Detectable Warning Field	16.000 SF	_____.	_____.
0202	644.1810 Temporary Pedestrian Barricade	170.000 LF	_____.	_____.
0204	645.0111 Geotextile Type DF Schedule A	140.000 SY	_____.	_____.
0206	645.0130 Geotextile Type R	4.000 SY	_____.	_____.
0208	645.0220 Geogrid Type SR	4,910.000 SY	_____.	_____.
0210	646.1020 Marking Line Epoxy 4-Inch	10,845.000 LF	_____.	_____.
0212	646.3020 Marking Line Epoxy 8-Inch	3,000.000 LF	_____.	_____.
0214	646.5020 Marking Arrow Epoxy	27.000 EACH	_____.	_____.
0216	646.5120 Marking Word Epoxy	6.000 EACH	_____.	_____.
0218	646.6120 Marking Stop Line Epoxy 18-Inch	224.000 LF	_____.	_____.
0220	646.7120 Marking Diagonal Epoxy 12-Inch	60.000 LF	_____.	_____.
0222	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	92.000 LF	_____.	_____.
0224	646.8120 Marking Curb Epoxy	180.000 LF	_____.	_____.
0226	646.8220 Marking Island Nose Epoxy	10.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0228	646.9010 Marking Removal Line Water Blasting 4-Inch	6,800.000 LF	_____.	_____.
0230	646.9110 Marking Removal Line Water Blasting 8-Inch	900.000 LF	_____.	_____.
0232	646.9210 Marking Removal Line Water Blasting Wide	70.000 LF	_____.	_____.
0234	646.9310 Marking Removal Special Marking Water Blasting	4.000 EACH	_____.	_____.
0236	650.4000 Construction Staking Storm Sewer	29.000 EACH	_____.	_____.
0238	650.4500 Construction Staking Subgrade	2,137.000 LF	_____.	_____.
0240	650.5000 Construction Staking Base	2,137.000 LF	_____.	_____.
0242	650.5500 Construction Staking Curb Gutter and Curb & Gutter	4,494.000 LF	_____.	_____.
0244	650.6000 Construction Staking Pipe Culverts	1.000 EACH	_____.	_____.
0246	650.8501 Construction Staking Electrical Installations (project) 01. 4160-06-71	1.000 EACH	_____.	_____.
0248	650.9000 Construction Staking Curb Ramps	4.000 EACH	_____.	_____.
0250	650.9500 Construction Staking Sidewalk (project) 01. 4160-06-71	1.000 EACH	_____.	_____.
0252	650.9911 Construction Staking Supplemental Control (project) 01. 4160-06-71	1.000 EACH	_____.	_____.
0254	650.9920 Construction Staking Slope Stakes	2,137.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0256	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	2,839.000 LF	_____.	_____.
0258	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	3,449.000 LF	_____.	_____.
0260	652.0615 Conduit Special 3-Inch	785.000 LF	_____.	_____.
0262	652.0800 Conduit Loop Detector	1,186.000 LF	_____.	_____.
0264	653.0154 Pull Boxes Non-Conductive 24x36-Inch	3.000 EACH	_____.	_____.
0266	653.0164 Pull Boxes Non-Conductive 24x42-Inch	8.000 EACH	_____.	_____.
0268	653.0905 Removing Pull Boxes	10.000 EACH	_____.	_____.
0270	654.0105 Concrete Bases Type 5	10.000 EACH	_____.	_____.
0272	654.0113 Concrete Bases Type 13	4.000 EACH	_____.	_____.
0274	655.0230 Cable Traffic Signal 5-14 AWG	796.000 LF	_____.	_____.
0276	655.0240 Cable Traffic Signal 7-14 AWG	865.000 LF	_____.	_____.
0278	655.0515 Electrical Wire Traffic Signals 10 AWG	8,154.000 LF	_____.	_____.
0280	655.0700 Loop Detector Lead In Cable	5,712.000 LF	_____.	_____.
0282	655.0800 Loop Detector Wire	3,880.000 LF	_____.	_____.
0284	656.0201 Electrical Service Meter Breaker Pedestal (location) 01. CTH CE & Railroad Street	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0286	657.0100 Pedestal Bases	7.000 EACH	_____.	_____.
0288	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	20.000 EACH	_____.	_____.
0290	657.0310 Poles Type 3	1.000 EACH	_____.	_____.
0292	657.0315 Poles Type 4	9.000 EACH	_____.	_____.
0294	657.0322 Poles Type 5-Aluminum	10.000 EACH	_____.	_____.
0296	657.0420 Traffic Signal Standards Aluminum 13-FT	3.000 EACH	_____.	_____.
0298	657.0425 Traffic Signal Standards Aluminum 15-FT	4.000 EACH	_____.	_____.
0300	657.0585 Trombone Arms 15-FT	1.000 EACH	_____.	_____.
0302	657.0614 Luminaire Arms Single Member 4-Inch Clamp 8-FT	14.000 EACH	_____.	_____.
0304	657.0615 Luminaire Arms Single Member 4 1/2-Inch Clamp 8-FT	18.000 EACH	_____.	_____.
0306	658.0173 Traffic Signal Face 3S 12-Inch	20.000 EACH	_____.	_____.
0308	658.0174 Traffic Signal Face 4S 12-Inch	7.000 EACH	_____.	_____.
0310	658.0416 Pedestrian Signal Face 16-Inch	2.000 EACH	_____.	_____.
0312	658.0500 Pedestrian Push Buttons	2.000 EACH	_____.	_____.
0314	658.5070 Signal Mounting Hardware (location) 01. CTH CE & Railroad Street	1.000 EACH	_____.	_____.
0316	659.1120 Luminaires Utility LED B	32.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0318	690.0150 Sawing Asphalt	4,940.000 LF	_____.	_____.
0320	690.0250 Sawing Concrete	98.000 LF	_____.	_____.
0322	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,200.000 HRS	5.00000	6,000.00
0324	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0326	SPV.0060 Special 01. Concrete Control Cabinet Basement Precast	1.000 EACH	_____.	_____.
0328	SPV.0060 Special 02. Concrete Bases Type 1 Special	7.000 EACH	_____.	_____.
0330	SPV.0060 Special 03. Concrete Bases Type 2 Special	10.000 EACH	_____.	_____.
0332	SPV.0060 Special 04. Install Poles Type 12	4.000 EACH	_____.	_____.
0334	SPV.0060 Special 05. Install Monotube Arms 45-FT	3.000 EACH	_____.	_____.
0336	SPV.0060 Special 06. Install Monotube Arms 50-FT	1.000 EACH	_____.	_____.
0338	SPV.0060 Special 07. Transport and Install Traffic Signal Detection System CTH CE & Railroad St	1.000 EACH	_____.	_____.
0340	SPV.0060 Special 08. Remove, Salvage and Reinstall Broadband Radio Interconnect Antenna	1.000 EACH	_____.	_____.
0342	SPV.0060 Special 09. Inlets 6-FT Diameter	1.000 EACH	_____.	_____.
0344	SPV.0060 Special 10. Inlets 9-FT Diameter	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214029 Project(s): 4160-06-71

Federal ID(s): WISC 2023231

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0346	SPV.0090 Special 01. Cable Traffic Signal 16-14 AWG	4,497.000 LF	_____.	_____.
0348	SPV.0090 Special 02. Tray Cable for Street Lighting 3 Conductor 12 AWG	5,849.000 LF	_____.	_____.
0350	SPV.0090 Special 03. Tray Cable for Street Lighting 2 Conductor 10 AWG	3,015.000 LF	_____.	_____.
0352	SPV.0090 Special 04. Install Communications Cable	2,742.000 LF	_____.	_____.
0354	SPV.0090 Special 05. Storm Sewer Lateral 8-Inch	6.000 LF	_____.	_____.
0356	611.9800.S Pipe Grates (size) 01. 42-Inch	1.000 EACH	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.