



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

February 8, 2023

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #45: 7620-00-70**  
**Elmwood – STH 64**  
**STH 29 to USH 12**  
**STH 128**  
**St. Croix County**

### Letting of February 14, 2023

This is Addendum No. 02, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Deleted Special Provisions	
Article No.	Description
18	Asphaltic Surface Temporary, Item 465.0125

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
650.6000	Construction Staking Pipe Culverts	Each	6	+3	9

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
50	Revised MQ table for Culvert Pipes

<b>Deleted Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of why sheet was deleted)</b>
15	Construction Details (Removed due to potential contractor confusion and recommendations of WisDOT NW Region Pavement Engineer)
16	Construction Details (Removed due to potential contractor confusion and recommendations of WisDOT NW Region Pavement Engineer)
17	Construction Details (Removed due to potential contractor confusion and recommendations of WisDOT NW Region Pavement Engineer)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**

**7620-00-70**

**February 8, 2023**

**Special Provisions**

**3. Prosecution and Progress.**

*Delete paragraph four.*

**18. DELETED**

**Schedule of Items**

Attached, dated February 8, 2023, are the revised Schedule of Items Page 6.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 50

Deleted: 15 – 17.

END OF ADDENDUM

ASPHALT INTERSECTION RUMBLE STRIPS			ASPHALTIC CENTERLINE RUMBLE STRIPS 2-LANE RURAL			CONCRETE BARRIER TEMPORARY PRECAST			WATER			
STATION-LOCATION	465.0450		STATION-LOCATION	465.0475		STATION-LOCATION	603.6000		STATION-LOCATION	624.0100		
23+40-25+40	100		21+15-23+00	185		233+75-233+25	550		19+40-175+20	65		
316+25-322+25	100		27+00-35+20	820		233+75-233+25	550		106+00-107+50	11		
TOTAL =	200		40+65-79+70	3,505		TOTALS =	550		116+50-118+00	11		
			79+70-97+40	1,770					131+65-133+00	11		
			99+40-128+50	2,910					146+50-150+00	11		
			132+50-171+20	3,870					173+20-239+35	27		
			175+20-179+50	430					176+50-178+00	11		
			181+50-206+65	2,515					212+50-214+00	10		
			208+65-212+30	365					225+50-227+00	15		
			214+30-230+20	1,590					263+80-322+30	25		
			263+50-265+00	205					DRIVEWAY	2		
			269+00-277+60	860					SIDEROADS	1		
			279+60-288+45	695					TOTAL =	200		
			280+45-322+30	3,200								
			TOTAL =	25,050								


TEMPORARY SHORING			RIPRAP MEDIUM & GEOTEXTILE FABRIC TYPE HR		
STATION-LOCATION	511.1100		STATION-LOCATION	645.0120	
228+10-228+65	845		106+64	6	
TOTAL =	845		148+14	9	
			TOTALS =	24	

MOBILIZATIONS EROSION CONTROL		
PROJECT	7620-00-70	
EROSION CONTROL	5	
EROSION CONTROL	3	
TOTALS =	5	

CULVERT PIPES		
STATION	520.8700	
39+70	1	
52+14	1	
59+37	1	
119+54	1	
132+50	1	
147+14	1	
148+14	1	
171+13	1	
177+05	1	
196+38	1	
213+04	1	
209+15	1	
226+34(1)	1	
226+46(1)	1	
226+61(1)	1	
TOTALS =	9	

CULVERT PIPES			CULVERT PIPES			CULVERT PIPES			CULVERT PIPES		
STATION	520.8700		STATION	520.9700		STATION	520.9700		STATION	520.9700	
39+70	1		CLEANING PIPES	01.24-INCH		CLEANING PIPES	02.36-INCH		CLEANING PIPES	02.36-INCH	
52+14	1		ENDWALLS FOR CULVERT	30-INCH		ENDWALLS FOR CULVERT	30-INCH		ENDWALLS FOR CULVERT	30-INCH	
59+37	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
119+54	1		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH	
132+50	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
147+14	1		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH	
148+14	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
171+13	1		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH	
177+05	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
196+38	1		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH	
213+04	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
209+15	1		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH	
226+34(1)	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
226+46(1)	1		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH		ENDWALLS FOR CULVERT	36-INCH	
226+61(1)	1		APRON	36-INCH		APRON	36-INCH		APRON	36-INCH	
TOTALS =	9		TOTALS =	242		TOTALS =	242		TOTALS =	86	

Addendum No. 02  
 ID 7620-00-70  
 Revised Sheet 50  
 February 8, 2023



CRASH CUSHION			CRASH CUSHION			CRASH CUSHION			CRASH CUSHION		
STATION	520.8700		STATION	520.9700		STATION	520.9700		STATION	520.9700	
224+00	1		CRASH CUSHION	TL-3		CRASH CUSHION	TL-3		CRASH CUSHION	TL-3	
228+40	1		OBJECT MARKING	OM3-R (W005-68R)		OBJECT MARKING	OM3-R (W005-68R)		OBJECT MARKING	OM3-R (W005-68R)	
TOTAL =	2		BACK WIDTH	4		BACK WIDTH	4		BACK WIDTH	4	
			TEMPORARY	1		TEMPORARY	1		TEMPORARY	1	
			TEST LEVEL	TL-3		TEST LEVEL	TL-3		TEST LEVEL	TL-3	
			TOTALS =	2		TOTALS =	2		TOTALS =	2	

\* ALL PIPE JOINTS SHALL BE TIED.  
 (1) SEE STRUCTURE PLANS FOR CULVERT PIPE QUANTITY



Proposal Schedule of Items

Proposal ID: 20230214045 Project(s): 7620-00-70

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0160	646.9000 Marking Removal Line 4-Inch	1,800.000 LF	_____	_____
0162	650.4500 Construction Staking Subgrade	1,150.000 LF	_____	_____
0164	650.5000 Construction Staking Base	1,150.000 LF	_____	_____
0166	650.6000 Construction Staking Pipe Culverts	9.000 EACH	_____	_____
0168	650.8000 Construction Staking Resurfacing Reference	27,600.000 LF	_____	_____
0170	650.9911 Construction Staking Supplemental Control (project) 01. 7620-00-70	1.000 EACH	_____	_____
0172	650.9920 Construction Staking Slope Stakes	1,150.000 LF	_____	_____
0174	661.0101 Temporary Traffic Signals for Bridges (structure) 01. B-55-0088	1.000 EACH	_____	_____
0176	690.0150 Sawing Asphalt	1,250.000 LF	_____	_____
0178	740.0440 Incentive IRI Ride	20,900.000 DOL	1.00000	20,900.00
0180	SPV.0060 Special 01. Apron Endwalls for Culvert Pipe RCHE 72x113-Inch	6.000 EACH	_____	_____
0182	SPV.0060 Special 02. Landmark Reference Monuments Special	12.000 EACH	_____	_____
0184	SPV.0060 Special 03. Verify Landmark Reference Monuments Special	12.000 EACH	_____	_____
0186	SPV.0090 Special 01. Culvert Pipe RCHE Class HE-IV 72x113-Inch	258.000 LF	_____	_____
Section: 0001			Total:	_____

