


ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 84



DESIGN DESIGNATION

A.A.D.T. (2023)	=	800
A.A.D.T. (2043)	=	875
D.H.V.	=	-
D.D.	=	50/50
T.	=	3.8%
DESIGN SPEED	=	30 MPH
ESALS	=	81,000

CONVENTIONAL SYMBOLS

PLAN	
CORPORATE LIMITS	
PROPERTY LINE	
LOT LINE	
LIMITED HIGHWAY EASEMENT	
EXISTING RIGHT OF WAY	
PROPOSED OR NEW R/W LINE	
SLOPE INTERCEPT	
REFERENCE LINE	
EXISTING CULVERT	
PROPOSED CULVERT (Box or Pipe)	
COMBUSTIBLE FLUIDS	
MARSH AREA	
WOODED OR SHRUB AREA	

PROFILE	
GRADE LINE	
ORIGINAL GROUND	
MARSH OR ROCK PROFILE (To be noted as such)	
SPECIAL DITCH	
GRADE ELEVATION	
CULVERT (Profile View)	

UTILITIES	
ELECTRIC	
FIBER OPTIC	
GAS	
SANITARY SEWER	
STORM SEWER	
TELEPHONE	
WATER	
UTILITY PEDESTAL	
POWER POLE	
TELEPHONE POLE	

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

C GREEN BAY, CHANTEL STREET


BEAVER DAM CREEK BRIDGE

LOC STR

BROWN COUNTY

STATE PROJECT NUMBER


4987-02-78



BEGIN PROJECT
STA 9+50
Y=568903.572
X=83306.832

END PROJECT
STA 10+50

STRUCTURE B-05-0474
STA 10+00



TOTAL NET LENGTH OF CENTERLINE = 0.019 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), BROWN COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12B.

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
4987-02-78	WISC 2023233	1

ACCEPTED FOR
CITY OF GREEN BAY
10/12/22
DATE
[Signature]
DIRECTOR PUBLIC WORKS

ORIGINAL PLANS PREPARED BY
AYRES
WISCONSIN
RYAN D. SCHAITEL
44367
GREEN BAY, WI
PROFESSIONAL ENGINEER
10/12/2022
(Date)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
PREPARED BY
Surveyor _____ AYRES _____
Designer _____ AYRES _____
Project Manager _____ DOUG KIRST, PE _____
Regional Supervisor _____ BRIAN EDWARDS, PE _____

APPROVED FOR THE DEPARTMENT
DATE: *10/12/22*
[Signature]
(Signature)

GENERAL NOTES

THE LOCATION OF EXISTING UTILITY FACILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY FACILITIES WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

PROPERTY LINES AS SHOWN ARE APPROXIMATE.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT APPROVAL OF THE ENGINEER.

BEARINGS SHOWN ON THIS PLAN ARE TRUE BEARINGS TO THE NEAREST SECOND.

ALL TIES ON THIS PLAN ARE HORIZONTAL UNLESS DESCRIBED OTHERWISE.

DISTURBED AREAS WITHIN THE RIGHT OF WAY ARE TO BE SEEDED AND EROSION MAT AS DIRECTED BY THE ENGINEER.

CONSTRUCT ASPHALTIC SURFACE WITH A 1 3/4" UPPER LAYER AND A 2 1/4" LOWER LAYER.

RUNOFF COEFFICIENT TABLE

	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
ROW CROPS	.08 .22	.16 .30	.22 .38	.12 .26	.20 .34	.27 .44	.15 .30	.24 .37	.33 .50	.19 .34	.28 .41	.38 .56
MEDIAN STRIP-TURF	.19 .24	.20 .26	.24 .30	.19 .25	.22 .28	.26 .33	.20 .26	.23 .30	.30 .37	.20 .27	.25 .32	.30 .40
SIDE SLOPE-TURF			.25 .32			.27 .34			.28 .36			.30 .38
PAVEMENT:												
ASPHALT	.70 - .95											
CONCRETE	.80 - .95											
BRICK	.70 - .80											
DRIVES, WALKS	.75 - .85											
ROOFS	.75 - .95											
GRAVEL ROADS, SHOULDERS	.40 - .60											

TOTAL PROJECT AREA= 0.21 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.18 ACRES
SOIL GROUP C

UTILITIES

* AT&T DISTRIBUTION
205 S. JEFFERSON ST.
GREEN BAY, WI 54301
ATTENTION: VICTORIA KASSAB
E-MAIL: vk352k@att.com

TELEPHONE 920-401-7512

* GREEN BAY WATER UTILITY
631 S. ADAMS ST.
GREEN BAY, WI 54305-1210
ATTENTION: KRISTIN ROMANOWICZ
E-MAIL: kristin.romanowicz@greenbaywi.gov

TELEPHONE 920-448-3480
AFTER HOURS EMERGENCY 920-448-3483

* BROWN COUNTY TECHNOLOGY SERVICES
413 S. MADISON ST.
GREEN BAY, WI 54301
ATTENTION: DAN BECKER
E-MAIL: dbecker@mcewi.com

TELEPHONE 920-301-7902

* LUMEN
3235 INTERTECH DR. SUITE 600
BROOKFIELD, WI 53045
ATTENTION: BRAHIM GADDOUR
E-MAIL: brahim.gaddour@lumen.com

TELEPHONE 414-908-1027
CELL 414-704-1026

* SPECTRUM
3520 E. DESTINATION DR.
APPLTEON, WI 54915
ATTENTION: VINCE ALBIN
E-MAIL: vince.albin@charter.com

TELEPHONE 920-831-9249

* WISCONSIN PUBLIC SERVICES - ELECTRIC
2850 S. ASHLAND AVE.
GREEN BAY, WI 54304
ATTENTION: SCOTT ZELLNER
E-MAIL: scott.zellner@wisconsinpublicservice.com

TELEPHONE 920-617-5068
CELL 920-680-2188

* CITY OF GREEN BAY - SEWER
100 N. JEFFERSON ST.
GREEN BAY, WI 54301
ATTENTION: MATT HECKENLAIBLE
E-MAIL: Matt.Heckenlaible@greenbaywi.gov

TELEPHONE 920-448-3100
AFTER HOURS EMERGENCY 920-492-3735

* WISCONSIN PUBLIC SERVICES - GAS
2850 S. ASHLAND AVE.
GREEN BAY, WI 54304
ATTENTION: CHRISTINE BLAZEI
E-MAIL: Christine.Blazei@wisconsinpublicservice.com

TELEPHONE 920-617-5132
CELL 920-246-7603

* TDS TELECOM
525 JUNCTION RD.
MADISON, WI 53717
ATTENTION: SEAN MURRAY
E-MAIL: Sean.murray@tdstelecom.com

TELEPHONE 606-664-4606
CELL 608-886-5207



*-MEMBER OF DIGGERS HOTLINE


STANDARD ABBREVIATIONS

ADT	AVERAGE DAILY TRAFFIC	NC	NORMAL CROWN
AC	ASPHALT CEMENT	PT	POINT OF TANGENCY
AGG	AGGREGATE	PC	POINT OF CURVATURE
ASPH	ASPHALT	PI	POINT OF INTERSECTION
BM	BENCH MARK	PE	PRIVATE ENTRANCE
C/L	CENTERLINE	R	RADIUS
CONC	CONCRETE	REM	REMOVE
CMP	CORRUGATED METAL PIPE	R/L OR RL	REFERENCE LINE
CR.	CREEK	RCCP	REINFORCED CONCRETE CULVERT PIPE
D	DEGREE OF CURVE	RCPPSS	REINFORCED CONCRETE PIPE STORM SEWER
DHV	DESIGN HOUR VOLUME	R.O.	RUNOUT
ESALS	EQUIVALENT SINGLE AXIS LOADS	R/W	RIGHT-OF-WAY
EXIST	EXISTING	STA	STATION
FE	FIELD ENTRANCE	SE	SUPER ELEVATION
HYD	HYDRANT	SS	STORM SEWER
IP	IRON PIPE OR PIN	T	TANGENT
L	LENGTH OF CURVE	TEL	TELEPHONE
LC	LONG CHORD OF CURVE	TLE	TEMPORARY LIMITED EASEMENT
LR	LENGTH OF RUNOFF	T	TRUCKS
MH	MANHOLE	VC	VERTICAL CURVE
		W	WELL

DEPARTMENT OF NATURAL RESOURCES


WDNR
2984 SHAWANO AVE.
GREEN BAY, WISCONSIN 54313
ATTENTION: JAMES DOPERALSKI
E-MAIL: JAMES.DOPERALSKI@WISCONSIN.GOV
TELEPHONE 920-412-0165

TDS
2984 SHAWANO AVE.
GREEN BAY, WISCONSIN 54313
ATTENTION: JAMES DOPERALSKI
E-MAIL: JAMES.DOPERALSKI@WISCONSIN.GOV
TELEPHONE 920-412-0165




EXISTING TYPICAL SECTION FOR CHANTEL STREET


STA. 9+40 - STA. 10+50



FINISHED TYPICAL SECTION FOR CHANTEL STREET

STA. 9+40 - STA. 9+50






NOTES:



- ① CONTRACTION JOINTS SHALL BE SAWED EVERY 15' MAXIMUM OR AS DESIGNATED BY ENGINEER IN FIELD.
- ② EXPANSION JOINTS (3/4") SHALL BE PLACED AT END OF RADII, AND AS DESIGNATED BY ENGINEER IN FIELD.
- ③ NO. 4 REINFORCEMENT BARS SHALL BE 20' LONG WITH A 3/4" EXPANSION TUBE REQUIRED ON ONE END AT EXPANSION JOINTS.
- ④ NO. 4 REINFORCEMENT BARS SHALL BE OVERLAPPED A MINIMUM OF 1'.
- ⑤ 1-1/2" AT DRIVEWAY OPENINGS, 1/2" AT CURB RAMPS.

CONCRETE CURB AND GUTTER 24-INCH TYPE A & D



CURB AND GUTTER REPLACEMENT AT CURB RAMPS

CHANTEL STREET STATION & OFFSET TABLE				
POINT	STATION	OFFSET	Y COORDS	X COORDS
100	9+34.7	34.6 LT	568904.930	83269.076
101	9+39.7	34.6 LT	568909.387	83271.225
102	9+34.8	29.6 LT	568902.766	83273.566
103	9+39.8	29.4 LT	568907.217	83275.928
104	9+34.8	26.1 LT	568901.238	83276.735
105	9+39.8	26.1 LT	568905.751	83278.906
106	9+34.8	24.1 LT	568900.377	83278.521
107	9+39.8	24.1 LT	568904.867	83280.702
108	9+39.7	21.8 LT	568903.844	83282.779
109	9+31.8	26.0 LT	568898.514	83275.478
110	9+42.7	20.9 LT	568906.161	83284.864
111	9+22.6	35.0 LT	568894.182	83263.390
165	9+34.8	21.6 LT	568899.305	83280.729
166	9+39.7	19.6 LT	568902.889	83284.745
167	9+47.9	18.4 LT	568909.700	83289.306
168	9+32.7	22.8 LT	568897.978	83278.721




LEGEND

- XXX.XX ELEVATION
- (XXX) POINT NUMBER
- (SW4) CONCRETE SIDEWALK 4-INCH
- (SW6) CONCRETE SIDEWALK 6-INCH
- ▣ REMOVING SIDEWALK

NOTES:

1. CONTRACTOR TO FIELD VERIFY ELEVATION, GRADES, SLOPES, LENGTHS AND MATCH POINTS PRIOR TO CURB RAMP AND SIDEWALK CONSTRUCTION
2. THE ENGINEER MAY ADJUST ELEVATIONS TO FIT FIELD CONSTRUCTION
3. DASHED LINES SHOWN FOR PROPOSED SIDEWALK ARE FOR INFORMATION ONLY AND DO NOT INDICATE JOINT LOCATIONS
4. SEE THE STANDARD DETAIL DRAWINGS FOR COMPLETE CURB RAMP REQUIREMENTS
5. ALL STATION AND OFFSET INFORMATION REFERENCE CHANTEL ST R/L



CHANTEL STREET STATION & OFFSET TABLE				
POINT	STATION	OFFSET	Y COORDS	X COORDS
117	9+50.0	29.6 RT	568890.654	83333.446
118	9+50.0	34.5 RT	568888.509	83337.864
119	9+44.7	34.5 RT	568883.728	83335.514
120	9+44.7	29.5 RT	568885.905	83331.086
121	9+39.7	34.4 RT	568879.241	83333.308
122	9+34.8	34.4 RT	568874.824	83331.137
123	9+39.6	39.4 RT	568877.000	83337.778
124	9+34.7	39.4 RT	568872.598	83335.566
125	9+39.7	44.4 RT	568874.873	83342.303
126	9+34.6	44.4 RT	568870.354	83340.032
127	9+30.9	34.4 RT	568871.378	83329.443
128	9+28.9	34.4 RT	568869.583	83328.561
129	9+25.6	34.4 RT	568866.592	83327.091
130	9+24.3	37.4 RT	568864.123	83329.220
131	9+20.8	45.8 RT	568857.354	83335.275
132	9+28.9	29.4 RT	568871.790	83324.072
133	9+31.0	29.4 RT	568873.616	83324.979
134	9+34.8	29.4 RT	568877.058	83326.690
135	9+34.9	26.4 RT	568878.431	83323.958
136	9+34.9	24.4 RT	568879.338	83322.151
137	9+32.0	26.4 RT	568875.814	83322.735
138	9+39.8	22.1 RT	568884.790	83322.241
139	9+39.8	24.5 RT	568883.708	83324.371
140	9+39.8	26.5 RT	568882.802	83326.154
141	9+39.7	29.5 RT	568881.427	83328.861
142	9+42.8	21.2 RT	568887.858	83322.825
169	9+23.4	34.4 RT	568864.600	83326.112
170	9+26.4	29.4 RT	568869.500	83322.934
171	9+28.6	26.8 RT	568872.687	83321.576
172	9+34.9	22.0 RT	568880.382	83320.073
173	9+39.9	19.9 RT	568885.748	83320.356
174	9+47.6	18.7 RT	568893.221	83322.646

- LEGEND**
- XXX.XX ELEVATION
 - (XXX) POINT NUMBER
 - (SW4) CONCRETE SIDEWALK 4-INCH
 - (SW6) CONCRETE SIDEWALK 6-INCH
 - REMOVING SIDEWALK
- NOTES:**
1. CONTRACTOR TO FIELD VERIFY ELEVATION, GRADES, SLOPES, LENGTHS AND MATCH POINTS PRIOR TO CURB RAMP AND SIDEWALK CONSTRUCTION
 2. THE ENGINEER MAY ADJUST ELEVATIONS TO FIT FIELD CONSTRUCTIONS
 3. DASHED LINES SHOWN FOR PROPOSED SIDEWALK ARE FOR INFORMATION ONLY AND DO NOT INDICATE JOINT LOCATIONS
 4. SEE THE STANDARD DETAIL DRAWINGS FOR COMPLETE CURB RAMP REQUIREMENTS
 5. ALL STATION AND OFFSET INFORMATION REFERENCE CHANTEL ST R/L



9TH STREET

19+50

19+75

20+00

9TH STREET STATION & OFFSET TABLE				
POINT	STATION	OFFSET	Y COORDS	X COORDS
143	19+71.9	20.8 RT	568852.483	83250.771
144	19+82.9	20.8 RT	568847.642	83260.712



POST

GUY

EXISTING R/W

LEGEND

- XXX.XX ELEVATION
- (XXX) POINT NUMBER
- (SW4) CONCRETE SIDEWALK 4-INCH
- (SW6) CONCRETE SIDEWALK 6-INCH
- [Cross-hatch] REMOVING SIDEWALK

NOTES:

1. CONTRACTOR TO FIELD VERIFY ELEVATION, GRADES, SLOPES, LENGTHS AND MATCH POINTS PRIOR TO CURB RAMP AND SIDEWALK CONSTRUCTION
2. THE ENGINEER MAY ADJUST ELEVATIONS TO FIT FIELD CONSTRUCTION
3. DASHED LINES SHOWN FOR PROPOSED SIDEWALK ARE FOR INFORMATION ONLY AND DO NOT INDICATE JOINT LOCATIONS
4. SEE THE STANDARD DETAIL DRAWINGS FOR COMPLETE CURB RAMP REQUIREMENTS
5. ALL STATION AND OFFSET INFORMATION REFERENCE CHANTEL ST R/L

PROJECT NO: 4987-02-78


HWY: CHANTEL STREET

COUNTY: BROWN

CURB RAMPS

SHEET






E




9TH STREET STATION & OFFSET TABLE				
POINT	STATION	OFFSET	Y COORDS	X COORDS
145	20+24.3	34.6 RT	568817.164	83291.918
146	20+24.4	39.7 RT	568812.588	83289.756
147	20+29.2	39.6 RT	568810.565	83294.172
148	20+29.2	34.5 RT	568815.086	83296.341
149	20+29.2	24.8 RT	568823.907	83300.573
150	20+29.1	22.7 RT	568825.726	83301.446
151	20+26.1	22.8 RT	568827.023	83298.741
152	20+26.1	20.7 RT	568828.828	83299.620
153	20+37.1	20.7 RT	568824.052	83309.516
154	20+37.1	22.7 RT	568822.249	83308.650
155	20+34.1	22.7 RT	568823.555	83305.950
156	20+34.2	24.7 RT	568821.744	83305.081
157	20+34.2	34.5 RT	568812.947	83300.861
158	20+34.2	39.4 RT	568808.481	83298.718
159	20+39.2	39.5 RT	568806.306	83303.179
160	20+39.1	34.5 RT	568810.798	83305.308
175	20+29.1	20.7 RT	568827.530	83302.311
176	20+34.1	20.7 RT	568825.357	83306.818

- LEGEND**
- XXX.XX ELEVATION
 - (XXX) POINT NUMBER
 - (SW6) CONCRETE SIDEWALK 6-INCH
 - ☒ REMOVING SIDEWALK
- NOTES:**
1. CONTRACTOR TO FIELD VERIFY ELEVATION, GRADES, SLOPES, LENGTHS AND MATCH POINTS PRIOR TO CURB RAMP AND SIDEWALK CONSTRUCTION
 2. THE ENGINEER MAY ADJUST ELEVATIONS TO FIT FIELD CONSTRUCTION
 3. DASHED LINES SHOWN FOR PROPOSED SIDEWALK ARE FOR INFORMATION ONLY AND DO NOT INDICATE JOINT LOCATIONS
 4. SEE THE STANDARD DETAIL DRAWINGS FOR COMPLETE CURB RAMP REQUIREMENTS
 5. ALL STATION AND OFFSET INFORMATION REFERENCE CHANTEL ST R/L


LEGEND

-  SILT FENCE
-  SLOPE INTERCEPT
-  TURBIDITY BARRIER
-  SURFACE WATER FLOW
-  INLET PROTECTION



BEGIN PROJECT
STA. 9+50

END PROJECT
STA. 10+50




2




2

LEGEND

-  SIGN ON TEMPORARY SUPPORT
-  WORK AREA
-  TEMPORARY PEDESTRIAN BARRICADE



LEGEND

-  SIGN ON TEMPORARY SUPPORT
-  WORK AREA
-  TEMPORARY PEDESTRIAN BARRICADE

Estimate Of Quantities

4987-02-78

Line	Item	Item Description	Unit	Total	Qty
0002	201.0220	Grubbing	ID	18.000	18.000
0004	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 01. P-5-719	EACH	1.000	1.000
0006	204.0100	Removing Concrete Pavement	SY	41.000	41.000
0008	204.0110	Removing Asphaltic Surface	SY	40.000	40.000
0010	204.0150	Removing Curb & Gutter	LF	173.000	173.000
0012	204.0155	Removing Concrete Sidewalk	SY	87.000	87.000
0014	204.9090.S	Removing (item description) 01. Steel Railing	LF	80.000	80.000
0016	205.0100	Excavation Common	CY	163.000	163.000
0018	206.1001	Excavation for Structures Bridges (structure) 01. B-5-474	EACH	1.000	1.000
0020	210.1500	Backfill Structure Type A	TON	410.000	410.000
0022	213.0100	Finishing Roadway (project) 01. 4987-02-78	EACH	1.000	1.000
0024	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	185.000	185.000
0026	311.0110	Breaker Run	TON	62.000	62.000
0028	415.0080	Concrete Pavement 8-Inch	SY	29.000	29.000
0030	415.4100	Concrete Pavement Joint Filling	SY	41.000	41.000
0032	416.0610	Drilled Tie Bars	EACH	62.000	62.000
0034	455.0605	Tack Coat	GAL	19.000	19.000
0036	465.0105	Asphaltic Surface	TON	71.000	71.000
0038	502.0100	Concrete Masonry Bridges	CY	229.000	229.000
0040	502.3200	Protective Surface Treatment	SY	200.000	200.000
0042	502.3210	Pigmented Surface Sealer	SY	48.000	48.000
0044	505.0400	Bar Steel Reinforcement HS Structures	LB	6,660.000	6,660.000
0046	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	27,170.000	27,170.000
0048	513.2001	Railing Pipe	LF	40.000	40.000
0050	513.7011	Railing Steel Type C2	LF	114.700	114.700
0052	516.0500	Rubberized Membrane Waterproofing	SY	30.000	30.000
0054	550.0010	Pre-Boring Unconsolidated Materials	LF	60.000	60.000
0056	550.1100	Piling Steel HP 10-Inch X 42 Lb	LF	1,040.000	1,040.000
0058	602.0405	Concrete Sidewalk 4-Inch	SF	723.000	723.000
0060	602.0415	Concrete Sidewalk 6-Inch	SF	146.000	146.000
0062	602.0515	Curb Ramp Detectable Warning Field Natural Patina	SF	40.000	40.000
0064	606.0300	Riprap Heavy	CY	125.000	125.000
0066	611.8115	Adjusting Inlet Covers	EACH	1.000	1.000
0068	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	200.000	200.000
0070	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0072	619.1000	Mobilization	EACH	1.000	1.000
0074	624.0100	Water	MGAL	4.000	4.000
0076	628.1504	Silt Fence	LF	135.000	135.000
0078	628.1520	Silt Fence Maintenance	LF	270.000	270.000
0080	628.1905	Mobilizations Erosion Control	EACH	5.000	5.000
0082	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0084	628.6005	Turbidity Barriers	SY	140.000	140.000
0086	628.7005	Inlet Protection Type A	EACH	1.000	1.000
0088	628.7015	Inlet Protection Type C	EACH	2.000	2.000
0090	631.1000	Sod Lawn	SY	250.000	250.000
0092	638.2602	Removing Signs Type II	EACH	2.000	2.000
0094	638.3000	Removing Small Sign Supports	EACH	2.000	2.000
0096	642.5001	Field Office Type B	EACH	1.000	1.000
0098	643.0300	Traffic Control Drums	DAY	1,407.000	1,407.000

Estimate Of Quantities

4987-02-78

Line	Item	Item Description	Unit	Total	Qty
0100	643.0410	Traffic Control Barricades Type II	DAY	1,582.000	1,582.000
0102	643.0420	Traffic Control Barricades Type III	DAY	938.000	938.000
0104	643.0705	Traffic Control Warning Lights Type A	DAY	1,340.000	1,340.000
0106	643.0900	Traffic Control Signs	DAY	2,613.000	2,613.000
0108	643.5000	Traffic Control	EACH	1.000	1.000
0110	644.1810	Temporary Pedestrian Barricade	LF	72.000	72.000
0112	645.0111	Geotextile Type DF Schedule A	SY	140.000	140.000
0114	645.0120	Geotextile Type HR	SY	265.000	265.000
0116	646.6120	Marking Stop Line Epoxy 18-Inch	LF	12.000	12.000
0118	646.7420	Marking Crosswalk Epoxy Transverse Line 6-Inch	LF	175.000	175.000
0120	646.9110	Marking Removal Line Water Blasting 8-Inch	LF	128.000	128.000
0122	650.4500	Construction Staking Subgrade	LF	66.000	66.000
0124	650.5000	Construction Staking Base	LF	76.000	76.000
0126	650.5500	Construction Staking Curb Gutter and Curb & Gutter	LF	297.000	297.000
0128	650.6501	Construction Staking Structure Layout (structure) 01. B-5-474	EACH	1.000	1.000
0130	650.9000	Construction Staking Curb Ramps	EACH	4.000	4.000
0132	650.9500	Construction Staking Sidewalk (project) 01. 4987-02-78	EACH	1.000	1.000
0134	650.9911	Construction Staking Supplemental Control (project) 01. 4987-02-78	EACH	1.000	1.000
0136	650.9920	Construction Staking Slope Stakes	LF	76.000	76.000
0138	690.0150	Sawing Asphalt	LF	37.000	37.000
0140	690.0250	Sawing Concrete	LF	186.000	186.000
0142	715.0502	Incentive Strength Concrete Structures	DOL	1,374.000	1,374.000
0144	715.0720	Incentive Compressive Strength Concrete Pavement	DOL	500.000	500.000
0146	999.2000.S	Installing and Maintaining Bird Deterrent System (station) 01. STA 10+00	EACH	1.000	1.000
0148	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	600.000	600.000
0150	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	300.000	300.000
0152	SPV.0060	Special 01. Remove, Salvage, and Deliver Steel Plates	EACH	2.000	2.000
0154	SPV.0090	Special 01. Concrete Curb & Gutter 24-Inch Type D	LF	219.000	219.000
0156	SPV.0090	Special 02. Concrete Curb & Gutter 24-Inch Type A	LF	78.000	78.000
0158	SPV.0195	Special 01. Select Crushed Material for Travel Corridor	TON	5.000	5.000

3

GRUBBING

CATEGORY	STATION	LOCATION	201.0220 GRUBBING ID
0010	10+32.7	CHANTEL ST, RT	18
TOTAL 0010			18

REMOVING CONCRETE PAVEMENT

CATEGORY	STATION	TO	STATION	LOCATION	204.0100 REMOVING CONCRETE PAVEMENT SY
0010	9+21	-	9+40	CHANTEL ST, RT	24
0010	9+23	-	9+40	CHANTEL ST, LT	17
TOTAL 0010					41

REMOVING ASPHALTIC SURFACE

CATEGORY	STATION	TO	STATION	LOCATION	204.0110 REMOVING ASPHALTIC SURFACE SY
0010	9+40	-	9+50	CHANTEL ST, LT & RT	40
TOTAL 0010					40

3

REMOVING CURB & GUTTER

CATEGORY	STATION	TO	STATION	LOCATION	204.0150 REMOVING CURB & GUTTER LF
0010	9+40	-	9+84	CHANTEL ST, LT & RT	87
0010	10+18	-	10+50	CHANTEL ST, LT & RT	64
0010	19+72	-	19+83	9TH ST, RT	11
0010	20+27	-	20+38	9TH ST, RT	11
TOTAL 0010					173

REMOVING CONCRETE SIDEWALK

CATEGORY	STATION	TO	STATION	LOCATION	204.0155 REMOVING CONCRETE SIDEWALK SY
0010	9+31	-	9+45	CHANTEL ST, LT	8
0010	9+34	-	9+88	CHANTEL ST, RT	41
0010	10+18	-	10+50	CHANTEL ST, RT	22
0010	19+72	-	19+83	9TH ST, RT	8
0010	20+24	-	20+39	9TH ST, RT	8
TOTAL 0010					87

EARTHWORK SUMMARY

Division	From/To Station	Location	Common Excavation (item #205.0100)	Unusable Pavement Material (4)	Available Material (5)	Unexpanded Fill	Expanded Fill (13)	Mass Ordinate +/- (14)	Waste
			Cut (1)				Factor 1.30		
1	9+50 - 10+50	CHANTEL ST	163	45	118	2	3	160	160
Division 1 Totals			163	45	118	2	3	160	160

REMOVE, SALVAGE, AND DELIVER STEEL PLATES

CATEGORY	STATION	LOCATION	SPV.0060.01 EACH
0030	10+18	CHANTEL ST, LT & RT	2
TOTAL 0030			2

- 1) Unusable Pavement Material is included in Cut
- 4) Unusable Pavement Material = Existing Asphaltic Pavement. Backfill any areas below subgrade with borrow.
- 5) Available Material = Cut - Unusable Pavement Material
- 13) Expanded Fill. Factor = 1.3 Expanded Fill = Unexpanded Fill * Fill Factor
- 14) The Mass Ordinate + or - Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.

BASE AGGREGATE DENSE AND BREAKER RUN

CATEGORY	STATION	TO	STATION	LOCATION	305.0120	311.0110	624.0100	REMARKS
					BASE AGGREGATE DENSE 1 1/4- INCH TON	BREAKER RUN TON	WATER	
0010	9+22	-	9+84	CHANTEL ST, LT & RT	21	-	-	SIDEWALK AND CURB RAMP WORK
0010	9+40	-	9+50	CHANTEL ST, RT & LT	4	-	-	PAVEMENT REPLACEMENT
0010	9+50	-	9+84	CHANTEL ST, RT & LT	75	32	2	MAINLINE
0010	10+18	-	10+50	CHANTEL ST, RT & LT	72	30	2	MAINLINE
0010	10+18	-	10+50	CHANTEL ST, LT & RT	7	-	-	SIDEWALK
0010	19+72	-	19+83	9TH ST, RT	1	-	-	CURB AND GUTTER
0010	20+24	-	20+39	9TH ST, RT	5	-	-	SIDEWALK AND CURB RAMP WORK
TOTAL 0010					185	62	4	

HMA PAVEMENT ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	455.0605	465.0105
					TACK COAT GAL	ASPHALTIC SURFACE TON
0010	9+40	-	9+85	CHANTEL ST	11	41
0010	10+18	-	10+50	CHANTEL ST	8	30
TOTAL 0010					19	71

CONCRETE CURB AND GUTTER

CATEGORY	STATION	TO	STATION	LOCATION	*	SPV.0090.01	SPV.0090.02
					416.0610 DRILLED TIE BARS EACH	CONCRETE CURB & GUTTER 24- INCH TYPE D LF	CONCRETE CURB & GUTTER 24- INCH TYPE A LF
0010	9+22	-	9+40	CHANTEL ST, RT	2	-	33
0010	9+24	-	9+40	CHANTEL ST, LT	2	-	23
0010	9+40	-	9+50	CHANTEL ST, LT & RT	-	87	-
0010	9+50	-	9+84	CHANTEL ST, LT & RT	-	68	-
0010	10+18	-	10+50	CHANTEL ST, LT & RT	4	64	-
0010	19+72	-	19+83	9TH ST, RT	8	-	11
0010	20+27	-	20+38	9TH ST, RT	10	-	11
TOTAL 0010					26	219	78

* ADDITIONAL QUANTITIES SHOWN ELSEWHERE

CONCRETE PAVEMENT ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	415.0080	415.4100	*
					CONCRETE PAVEMENT 8- INCH SY	CONCRETE PAVEMENT JOINT FILLING SY	416.0610 DRILLED TIE BARS EACH
0010	9+21	-	9+40	CHANTEL ST, RT	17	24	20
0010	9+23	-	9+40	CHANTEL ST, LT	12	17	16
TOTAL 0010					29	41	36

* ADDITIONAL QUANTITIES SHOWN ELSEWHERE

STEEL RAILING

CATEGORY	STATION	TO	STATION	LOCATION	204.9090.S.01	513.2001
					REMOVING STEEL RAILING LF	RAILING PIPE LF
0010	9+69	-	9+88	CHANTEL ST, LT	20	-
0010	10+12	-	10+31	CHANTEL ST, LT	20	-
0010	9+69	-	9+88	CHANTEL ST, RT	20	20
0010	10+12	-	10+31	CHANTEL ST, RT	20	20
TOTAL 0010					80	40

CONCRETE SIDEWALK ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	602.0405	602.0415	602.0515
					CONCRETE SIDEWALK 4- INCH SF	CONCRETE SIDEWALK 6- INCH SF	CURB RAMP DETECTABLE WARNING FIELD NATURAL PATINA SF
0010	9+31	-	9+45	CHANTEL ST, LT	-	60	10
0010	9+34	-	9+88	CHANTEL ST, RT	307	86	20
0010	9+74	-	9+84	CHANTEL ST, LT	55	-	-
0010	10+18	-	10+28	CHANTEL ST, LT	55	-	-
0010	10+18	-	10+50	CHANTEL ST, RT	173	-	-
0010	20+24	-	20+39	9TH ST, RT	133	-	10
TOTAL 0010					723	146	40

3

ADJUSTING INLET COVERS

CATEGORY	STATION	LOCATION	611.8115 ADJUSTING INLET COVERS EACH
0010	9+48	CHANTEL ST, RT	1
TOTAL 0010			1

SOD LAWN

CATEGORY	STATION	TO	STATION	LOCATION	631.1000 SOD LAWN SY
0010	9+21	-	9+84	CHANTEL ST, LT & RT	113
0010	10+18	-	10+50	CHANTEL ST, LT & RT	63
0010	19+72	-	20+39	9TH ST, RT	24
0010				UNDISTRIBUTED	50
TOTAL 0010					250

MOBILIZATION EROSION CONTROL

CATEGORY	STATION	TO	STATION	LOCATION	628.1905 MOBILIZATIONS EROSION CONTROL EACH	628.1910 MOBILIZATIONS EMERGENCY EROSION CONTROL EACH
0010	9+50	-	10+50	PROJECT	5	3
TOTAL 0010					5	3

3

SILT FENCE

CATEGORY	STATION	TO	STATION	LOCATION	628.1504 SILT FENCE LF	628.1520 SILT FENCE MAINTENANCE LF
0010	9+40	-	9+84	CHANTEL ST, RT	24	48
0010	9+40	-	9+84	CHANTEL ST, LT	26	52
0010	10+18	-	10+50	CHANTEL ST, RT	34	68
0010	10+18	-	10+50	CHANTEL ST, LT	24	48
UNDISTRIBUTED					27	54
TOTAL 0010					135	270

TURBIDITY BARRIERS

CATEGORY	STATION	TO	STATION	LOCATION	628.6005 TURBIDITY BARRIERS SY
0010	9+75	-	9+95	CHANTEL ST, LT & RT	73
0010	10+05	-	10+25	CHANTEL ST, LT & RT	67
TOTAL 0010					140

NOTE: TURBIDITY BARRIER ESTIMATED TO Q2 ELEVATION.

INLET PROTECTION

CATEGORY	STATION	LOCATION	628.7005 INLET PROTECTION TYPE A EACH	628.7015 INLET PROTECTION TYPE C EACH
0010	19+64	9TH ST, LT	-	1
0010	9+48	CHANTEL ST, RT	1	1
TOTAL 0010			1	2

REMOVING SIGNS AND SMALL SIGN SUPPORTS

CATEGORY	STATION	LOCATION	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORTS EACH	REMARKS
0010	9+55	CHANTEL ST, RT	1	1	WEIGHT LIMIT SIGN
		SW QUAD OF CHANTEL & 7TH ST	1	1	WEIGHT LIMIT SIGN
TOTAL 0010			2	2	

3

MARKING LINE

CATEGORY	STATION	TO	STATION	LOCATION	646.6120 MARKING STOP LINE EPOXY 18- INCH LF	646.7420 MARKING CROSSWALK EPOXY TRANSVERSE LINE 6-INCH LF	646.9110 MARKING REMOVAL LINE WATER BLASTING 8- INCH LF
0010	19+72	-	19+72	9TH ST, RT & LT	-	175	128
0010		9+50		CHANTEL ST, LT	12	-	-
TOTAL 0010					12	175	128

SAWING PAVEMENT

CATEGORY	STATION	TO	STATION	LOCATION	690.0150 SAWING ASPHALT LF	690.0250 SAWING CONCRETE LF
0010	9+21	-	9+40	CHANTEL ST, RT	-	52
0010	9+23	-	9+40	CHANTEL ST, LT	-	41
0010		9+40		CHANTEL ST, LT & RT	-	39
0010		10+50		CHANTEL ST, LT & RT	37	9
0010	19+72	-	19+83	9TH ST, RT	-	20
0010	20+27	-	20+38	9TH ST, RT	-	25
TOTAL 0010					37	186

3

TRAFFIC CONTROL


CATEGORY	LOCATION	643.0300 APPROX SERVICE PERIOD	643.0300 TRAFFIC CONTROL DRUMS NO. IN SERVICE DAY	643.0410 TRAFFIC CONTROL BARRICADES TYPE II NO. IN SERVICE DAY	643.0420 TRAFFIC CONTROL BARRICADES TYPE III NO. IN SERVICE DAY	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A NO. IN SERVICE DAY	643.0900 TRAFFIC CONTROL SIGNS NO. IN SERVICE DAY	644.1810 TEMPORARY PEDESTRIAN BARRICADE LF	REMARKS			
DETOUR												
0010	CHANTEL ST NORTH APPROACH	67	-	-	9	603	14	938	6	402	-	REFER TO SDD "BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL C & D"
0010	CHANTEL ST SOUTH APPROACH	67	-	-	5	335	6	402	1	67	-	REFER TO SDD "BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL D"
0010	9TH STREET	67	11	737	-	-	-	-	5	335	-	REFER TO SDD "WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY"
	UNDISTRIBUTED	67	10	670	-	-	-	-	-	-	-	
PEDESTRIAN DETOUR												
0010	CHANTEL ST PHASE 1	57	-	-	16	912	-	-	17	1139	72	
0010	CHANTEL ST PHASE 2	10	-	-	10	670	-	-	10	670	-	
TOTAL 0010			1,407	1,582	938	1,340	2,613	72				

CONSTRUCTION STAKING

CATEGORY	STATION	TO	STATION	LOCATION	650.4500 CONSTRUCTION STAKING SUBGRADE LF	650.5000 CONSTRUCTION STAKING BASE LF	650.5500 CONSTRUCTION STAKING CURB GUTTER AND CURB & GUTTER LF	650.6501.01 CONSTRUCTION STAKING STRUCTURE LAYOUT (B-5-474) EACH	650.9000 CONSTRUCTION STAKING CURB RAMPS EACH	650.9920 CONSTRUCTION STAKING SLOPE STAKES LF	650.9500.01 CONSTRUCTION STAKING SIDEWALK (4987-02-78) EACH	650.9911.01 CONSTRUCTION STAKING SUPPLEMENTAL CONTROL (4987-02-78) EACH
0010	9+50	-	10+50	PROJECT	-	-	297	-	4	-	1	1
0010	9+40	-	9+50	CHANTEL ST, RT & LT	-	10	-	-	-	10	-	-
0010	9+50	-	9+84	CHANTEL ST, RT & LT	34	34	-	-	-	34	-	-
0010	10+18	-	10+50	CHANTEL ST, RT & LT	32	32	-	-	-	32	-	-
TOTAL 0010					66	76	297	-	4	76	1	1
0020	9+84	-	10+18	B-5-474	-	-	-	1	-	-	-	-
TOTAL 0020					-	-	-	1	-	-	-	-

LEGEND

- .XXXX. SAW CUTS
- X TREE TO BE GRUBBED
- [Cross-hatched box] REMOVING CONCRETE SIDEWALK



PAVEMENT REPLACEMENT
STA. 9+40 - STA. 9+50

CONCRETE CURB AND
GUTTER 24-INCH TYPE A
REQ'D.

BURIED TELEPHONE CABLE
(APPROXIMATE LOCATION)

STA. 9+00.35 CHANEL STREET =
STA. 20+00.00 9TH STREET
Y = 568858.905
X = 83285.151

CONSTRUCTION LIMITS
STA. 9+40


CONCRETE CURB AND
GUTTER 24-INCH TYPE A
REQ'D.

BEGIN PROJECT
STA. 9+50
Y = 568903.572
X = 83306.832

BENCH MARKS


NO.	STATION	DESCRIPTION	ELEV.
301	9+43	TAG BOLT ON HYD.-27' LT	638.27
300	11+60	SW COR CONC SIGN LEDGE-52' RT	643.72

END PROJECT
STA. 10+50
Y = 568993.534
X = 83350.498




Standard Detail Drawing List


08D01-22A	CONCRETE CURB & GUTTER
08D01-22B	CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS
08D05-20A	CURB RAMPS TYPES 1 AND 1-A
08D05-20B	CURB RAMPS TYPES 2 AND 3
08D05-20C	CURB RAMPS TYPES 4A AND 4A1
08D05-20D	CURB RAMPS TYPE 4B AND 4B1
08D05-20E	CURB RAMPS TYPES 5, 6, 7A, 7B & 8
08D05-20F	CURB RAMPS RADIAL DETECTABLE WARNING FIELD APPLICATIONS
08D05-20G	CURB RAMPS RECTANGULAR AND RADIAL DETECTABLE WARNING PLATES
08E09-06	SILT FENCE
08E10-02	INLET PROTECTION TYPE A, B, C AND D
08E11-02	TURBIDITY BARRIER
12A03-10	NAME PLATE (STRUCTURES)
13C01-19	CONCRETE PAVEMENT LONGITUDINAL JOINTS AND TIES
13C04-17	URBAN NON-DOWELED CONCRETE PAVEMENT
13C18-07A	CONCRETE PAVEMENT JOINTING
13C18-07B	CONCRETE PAVEMENT STEEL REINFORCEMENT
13C18-07C	CONCRETE PAVEMENT JOINT TYPES
13C19-03	HMA LONGITUDINAL JOINTS
15C02-08A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-08B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C11-09B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15C33-04	STOP LINE AND CROSSWALK PAVEMENT MARKING
15D28-04	TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY
15D30-07A	TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION
15D30-07B	TRAFFIC CONTROL, TEMPORARY ADA COMPLIANT PEDESTRIAN ACCOMMODATION
15D30-07C	TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION
15D30-07F	TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION




TYPES A^① & D




6" SLOPED CURB TYPES G^① & J




4" SLOPED CURB TYPES G^① & J




TYPES K^① & L
(OPTIONAL CURB SHAPE)




TYPES K^① & L
CONCRETE CURB AND GUTTER 30"




TYPES A^① & D
CONCRETE CURB AND GUTTER 18"



6" SLOPED CURB TYPES A^① & D




4" SLOPED CURB TYPES A^① & D
CONCRETE CURB AND GUTTER 36"



4" SLOPED CURB TYPES R^① & T


TBT & TBTT	X
30"	22"
36"	28"



TYPES TBT & TBTT^①
CONCRETE CURB AND GUTTER


PAVEMENT THICKNESS
AND MAXIMUM CONCRETE
PANEL WIDTH TABLE

PAVEMENT THICKNESS	MAXIMUM PANEL WIDTH
LESS THAN 10"	12'
10" & ABOVE	15'



PARTIAL SECTION OF PAVEMENT *
WITH INTEGRAL CURB AND GUTTER

* BIKE LANE IS NOT SHOWN



REVERSE SLOPE GUTTER^⑥
(TYPICAL FOR ALL CURB & GUTTER TYPES)

GENERAL NOTES

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.


INTEGRAL CURB AND GUTTER SHALL CONFORM TO THE DETAILS SHOWN FOR CONCRETE CURB AND GUTTER INCLUDING THE TRANSVERSE GUTTER SLOPE.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.


- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ③ USE 8" MINIMUM GUTTER THICKNESS WHEN USED WITH AN ADJACENT CONCRETE TRUCK APRON PLACED BEHIND BACK OF CURB.
- ④ THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 8" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑤ UNLESS OTHERWISE NOTED, FOR STAKING PURPOSES THE FACE OF CURB IS 6" FROM THE BACK OF CURB.
- ⑥ WHEN REVERSE SLOPE GUTTER IS REQUIRED, THE LOCATION(S) WILL BE SHOWN ELSEWHERE IN THE PLAN.
- ⑦ USE 4% GUTTER CROSS SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.
- ⑧ INCLUDE LONGITUDINAL JOINT AND TIE BARS ALONG LANE EDGE WHEN CONCRETE PANEL WIDTH EXCEEDS THE MAXIMUM WIDTH PER TABLE BELOW. LONGITUDINAL JOINT(S) ARE NOT ALLOWED WITHIN TRAFFIC LANES AND BIKE LANES. LONGITUDINAL JOINT MAY BE SAWED.
- ⑨ CONCRETE CURB AND GUTTER 4-INCH SLOPED 30-INCH TYPE "R" AND "T" = 17 INCHES
CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE "R" AND "T" = 23 INCHES

6

6



END SECTION CURB AND GUTTER



DETAIL OF CURB AND GUTTER AT INLETS
(TYPICAL H INLET COVER SHOWN)


GENERAL NOTES

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.


PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2'-0" BEHIND THE BACK OF CURBS.


- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑨ REFER TO SDD 08D18 AND 08D19 FOR ADDITIONAL DRIVEWAY ENTRANCE CURB DETAILS.



TYPICAL TIE BAR LOCATION ①




TYPES A ① & D




TYPES G ① & J

CONCRETE CURB




PLAN VIEW



SECTION A - A

TIE BARS DRILLED INTO EXISTING PAVEMENT




DRIVEWAY ENTRANCE CURB ⑨
(WHEN DIRECTED BY THE ENGINEER)

CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2021 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER


FHWA




**PLAN VIEW
CURB RAMP TYPE 1
(CENTER OF CORNER RADIUS)**




**PLAN VIEW
CURB RAMP TYPE 1 - A
(NO TERRACE)**




VIEW A - A FOR TYPE 1



SECTION C - C FOR TYPE 1 - A



SECTION B - B FOR TYPE 1



VIEW D - D FOR TYPE 1 - A

GENERAL NOTES

AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
 DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

WHEN NECESSARY, THE SIDEWALK ELEVATION MAY BE LOWERED TO MEET THE HIGH POINT ON THE RAMP.
 TYPE 1 CURB RAMPS SHALL HAVE A NORMAL SIDEWALK APRON AND CURB ON BOTH SIDES OF RAMP.

DETECTABLE WARNING FIELD SHALL BE MEASURED AND PAID BY THE SQUARE FOOT AS "CURB RAMP DETECTABLE WARNING FIELD". THE CONCRETE PEDESTRIAN CURB, IF NEEDED, SHALL BE MEASURED AND PAID BY THE LINEAR FOOT AS "CONCRETE CURB PEDESTRIAN". CONCRETE SIDEWALK IN THE CURB RAMP AREA SHALL BE MEASURED AND PAID BY THE SQUARE FOOT AS CONCRETE SIDEWALK, INCLUDING THE AREA UNDER THE DETECTABLE WARNING FIELD.

SELECT CURB RAMP DETECTABLE WARNING FIELD MATERIALS AND DEVICES FROM THE DEPARTMENT'S APPROVED MATERIALS LIST. THE COLOR OF THE DETECTABLE WARNING FIELD IS SPECIFIED ELSEWHERE AND IS INCIDENTAL TO THE BID ITEM OF "CURB RAMP DETECTABLE WARNING FIELD"

DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.

SURFACE TEXTURE OF THE RAMP SHALL BE OBTAINED BY COARSE BROOMING TRANSVERSE TO THE SLOPE OF THE RAMP.


- ① THIS POINT IS AN EXTENSION OF OUTSIDE EDGE OF APPROACHING SIDEWALK WHERE IT MEETS THE BACK OF CONCRETE CURB. POINT LOCATION MAY BE ADJUSTED TO ALIGN WITH BEGINNING OF FULL-HEIGHT CURB IF THIS DISTANCE IS SHORT.
- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4" INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ MAXIMUM 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑤ PROVIDE A LEVEL LANDING IN THE STREET AND GUTTER AREA (2% MAXIMUM SLOPE IN ANY DIRECTION). WHEN THE GUTTER SLOPE EXCEEDS 2%, CONSTRUCT THE LEVEL LANDING IN THE STREET AREA.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.

LEGEND


- 1/2" EXPANSION JOINT SIDEWALK
- - - - - CONTRACTION JOINT FIELD LOCATED
- ||||||| PAVEMENT MARKING CROSSWALK (WHITE)

**CURB RAMPS
TYPE 1 AND 1-A**






STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



PLAN VIEW CURB RAMP TYPE 2 (CENTER OF CORNER RADIUS)



PLAN VIEW CURB RAMP TYPE 3 (OUTSIDE OF CROSSWALK AREA)



GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE SHALL BE FROM THE SAME MANUFACTURER.
- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4 - INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE (2.67% OR LESS) AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET X 5 FEET.
- ⑦ WHEN GRADE BREAK DISTANCE EXCEEDS 5 FEET, USE RADIAL DETECTABLE WARNING FIELD PER SDD 8D5-f.
- ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- ⑨ WHEN DISTANCE IS LESS THAN 6' - 0", IT MAY BE DIFFICULT TO ACHIEVE A 7% SLOPE OR FLATTER ALONG THE RAMP. REDUCE CURB HEIGHT IN TRIANGLE AREA TO ACHIEVE 7% SLOPE OR FLATTER ON RAMP. CONSTRUCT 2-INCH MINIMUM CURB HEIGHT BETWEEN 10:1 FLARES.


- * MAXIMUM 2.0% SLOPE IN ALL DIRECTIONS IN FRONT OF GRADE BREAK
- ** WIDTH SHOWN ELSEWHERE IN THE PLANS

LEGEND

- 1/2" EXPANSION JOINT SIDEWALK
- - - CONTRACTION JOINT SIDEWALK
- ||||| PAVEMENT MARKING CROSSWALK (WHITE)

**CURB RAMPS
TYPE 2 AND 3**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**PLAN VIEW
CURB RAMP TYPE 4A**

RADIUS (AT CURB FACE)	X
10 FEET	4' - 7"
15 FEET	6' - 5 1/2"

INTERMEDIATE RADII CAN BE INTERPOLATED




SECTION A - A FOR TYPE 4A

GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4" INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- ⑦ WHEN THIS GRADE BREAK DISTANCE EXCEEDS 5 FEET, USE RADIAL DETECTABLE WARNING FIELD PER SDD 8D5-f.
- ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- ⑩ INSTALL TRANSITION NOSE (INCIDENTAL TO OTHER PAY ITEMS). DO NOT MARK TRANSITION NOSE.


LEGEND

- 1/2" EXPANSION JOINT SIDEWALK
- - - CONTRACTION JOINT SIDEWALK
- ||||| PAVEMENT MARKING CROSSWALK (WHITE)




SECTION C - C FOR TYPE 4A

* MAXIMUM 2.0% SLOPE IN ALL DIRECTIONS IF FRONT OF GRADE BREAK




**SECTION B - B FOR
TYPE 4A AND TYPE 4A1**


** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED



**PLAN VIEW
CURB RAMP TYPE 4A1**




ISOMETRIC VIEW FOR TYPE 4A



ISOMETRIC VIEW FOR TYPE 4A1

**CURB RAMPS
TYPE 4A AND 4A1**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




PLAN VIEW CURB RAMP TYPE 4B

RADIUS (AT CURB FACE)	W = 3' - 0"		W = 4' - 0"		W = 5' - 0"		W = 6' - 0"		W = 7' - 0"		W = 8' - 0"		W = 9' - 0"		W = 10' - 0"	
	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y	X	Y
10 FEET	2' - 10 1/4"	0' - 5"	2' - 1"	1' - 4 1/2"	1' - 5"	2' - 1"	0' - 10"	2' - 7 1/2"	0' - 3 1/4"	3' - 0 1/4"						
15 FEET	4' - 6 3/4"	2' - 1 3/4"	3' - 9"	3' - 5 3/4"	3' - 1 1/4"	4' - 6"	2' - 6 3/4"	5' - 4 1/2"	2' - 1"	6' - 1"	1' - 8"	6' - 8 1/2"	1' - 3 1/4"	7' - 2 1/2"	0' - 10 3/4"	7' - 7 1/4"
20 FEET	5' - 9 3/4"	3' - 6 1/2"	4' - 11 1/2"	5' - 1 3/4"	4' - 3 1/4"	6' - 5 1/2"	3' - 8 3/4"	7' - 7"	3' - 3"	8' - 6 1/2"	2' - 10"	9' - 4 1/2"	2' - 5 1/2"	10' - 1 1/4"	2' - 1 1/4"	10' - 9"
30 FEET			6' - 9 1/4"	7' - 11 1/4"	6' - 0 1/4"	9' - 8"	5' - 5"	11' - 1 3/4"	4' - 10 3/4"	12' - 5 3/4"	4' - 5 1/2"	13' - 7 3/4"	4' - 0 3/4"	14' - 8 1/2"	3' - 8 1/2"	15' - 8 1/4"
40 FEET									6' - 1 3/4"	15' - 8 1/2"	5' - 8"	17' - 2"	5' - 3"	18' - 5 3/4"	4' - 10 3/4"	19' - 8 1/4"
50 FEET															5' - 10 1/4"	23' - 2"

INTERMEDIATE RADII CAN BE INTERPOLATED
 DIMENSION "Y" IS CALCULATED BASED ON 6'-0" RAMP LENGTH
 DIMENSION "X" IS CALCULATED BASED ON 5'-0" SIDEWALK WIDTH


- LEGEND**
- 1/2" EXPANSION JOINT SIDEWALK
 - CONTRACTION JOINT SIDEWALK
 - PAVEMENT MARKING CROSSWALK (WHITE)



SECTION C - C FOR TYPE 4B


GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/2 - INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- ⑦ WHEN THIS GRADE BREAK DISTANCE EXCEEDS 5 FEET, USE RADIAL DETECTABLE WARNING FIELD PER SDD 8D5-f.
- ⑧ PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- ⑩ INSTALL TRANSITION NOSE (INCIDENTAL TO OTHER PAY ITEMS). DO NOT MARK TRANSITION NOSE.




SECTION A - A FOR TYPE 4B

* MAXIMUM 2.0% SLOPE IN ALL DIRECTIONS IF FRONT OF GRADE BREAK




SECTION B - B FOR TYPE 4B AND TYPE 4B1


** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED



PLAN VIEW CURB RAMP TYPE 4B1




ISOMETRIC VIEW FOR TYPE 4B



ISOMETRIC VIEW FOR TYPE 4B1

CURB RAMPS TYPE 4B AND 4B1


STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION



CURB RAMP TYPE 8

DETECTABLE WARNINGS AT RAILROAD CROSSING

*** DETAILS TO BE DETERMINED BY ENGINEER



CURB RAMP TYPE 5
MEDIAN ISLAND
NON-ELEVATED PEDESTRIAN CROSSING

GENERAL NOTES

AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.


SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.

DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.

- ② GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4 - INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- ③ AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- ④ ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- ⑥ PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LEVEL LANDING SIZE IS 5 FEET BY 5 FEET.
- ⑩ INSTALL TRANSITION NOSE (INCIDENTAL TO OTHER PAY ITEMS). DO NOT MARK TRANSITION NOSE.
- ⑪ SLOPE SIDEWALK TOWARD LANDING AS SHOWN WHERE THERE IS NO TERRACE OR WHERE THE TERRACE WIDTH IS LESS THAN 6 FEET WIDE.
- ⑫ THE EDGE OF THE DETECTABLE WARNING FIELD NEAREST TO A RAILROAD CROSSING SHALL BE 1.5 FEET ±0.1' FROM THE FACE OF THE GATE ARM IF THE GATE ARM EXTENDS ACROSS THE SIDEWALK. WHERE THERE IS NO PEDESTRIAN GATE, THE EDGE OF THE DETECTABLE WARNING FIELD NEAREST TO THE RAILROAD CROSSING SHALL BE 15 FEET FROM THE NEAREST RAIL.
- ⑬ DO NOT INSTALL DETECTABLE WARNING FIELDS AT THE EDGES OF STREET-LEVEL PEDESTRIAN REFUGE ISLANDS IF A MINIMUM 2 FOOT CONCRETE SURFACE WITHOUT DETECTABLE WARNINGS (MEASURED IN THE DIRECTION OF PEDESTRIAN TRAVEL) CANNOT BE ACHIEVED.


LEGEND

- ===== 1/2" EXPANSION JOINT SIDEWALK
- - - - - CONTRACTION JOINT FIELD LOCATED
- ||||||| PAVEMENT MARKING CROSSWALK (WHITE)




CURB RAMP TYPE 6
DETECTABLE WARNING AT ISLANDS

REFER TO GENERAL NOTES ② AND ③ FOR ALL ISLAND CURB RAMPS




CURB RAMP TYPE 7A
MID BLOCK CROSSING



CURB RAMP TYPE 7B
MID BLOCK CROSSING

NOTE: THESE PARALLEL AND PARALLEL/PERPENDICULAR CURB RAMPS MAY BE USED AT INTERSECTIONS AND MID BLOCK LOCATIONS.




SECTION B - B FOR TYPE 7A


CURB RAMPS
TYPE 5, 6, 7A, 7B & 8

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

RADIAL DETECTABLE WARNING FIELD PLACEMENT WHEN 5 FOOT GRADE BREAK DISTANCE PER SDD 8D5-c IS EXCEEDED



PLAN VIEW CURB RAMP TYPE 4A1 (GRADE BREAK DISTANCE GREATER THAN 5 FEET)




SECTION A - A FOR TYPE 4A1

**** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED

*** MAXIMUM 8.33%

- LEGEND**
- 1/2" EXPANSION JOINT SIDEWALK
 - - - - - CONTRACTION JOINT SIDEWALK
 - ||||| PAVEMENT MARKING CROSSWALK (WHITE)




DETAIL A


GENERAL NOTES

- AVOID PLACING DRAINAGE STRUCTURES, JUNCTION BOXES OR OTHER OBSTRUCTIONS IN FRONT OF RAMP ACCESS AREAS.
- DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.
- DETECTABLE WARNING FIELDS THAT ARE INSTALLED AS A GROUP OR SIDE BY SIDE, SHALL BE FROM THE SAME MANUFACTURER.
- APPLY RADIAL DETECTABLE WARNING PLACEMENT SIMILARLY FOR TYPE 4A AND 4A1 CURB RAMPS AND SIMILARLY FOR TYPE 4B AND 4B1 CURB RAMPS. TYPE 4A AND 4B RAMPS ARE NOT SHOWN.
- REFER TO SDD 8D5-g FOR ADDITIONAL RADIAL PLATE REQUIREMENTS.
- FIELD CUTS AT INTERMEDIATE JOINTS WITHIN THE RADIAL DETECTABLE WARNING FILED ARE PROHIBITED.
- DETERMINE FINAL RADIAL WARNING FIELD CONFIGURATION AND ITS INDIVIDUAL PLATE LOCATIONS. PERFORM PRE-LAYOUT PRIOR TO PLACEMENT IN PLASTIC CONCRETE. FOLLOW MANUFACTURER'S PRODUCT LIST AND INSTALLATION RECOMMENDATIONS.
- 2 GRADE CHANGE BETWEEN GUTTER FLAG SLOPE AND THE CURB RAMP SLOPE SHALL NOT EXCEED 11%. MAXIMUM GUTTER FLAG SLOPE IS 4%. PROVIDE LONGITUDINAL DRAINAGE AROUND CURB AND AWAY FROM CURB RAMP. NO VERTICAL LIPS OR DISCONTINUITIES GREATER THAN 1/4 INCH ARE ALLOWED. SLOPE OF CURB HEAD OPENING SHALL MATCH THE RAMP SLOPE, MINIMALLY 1.5% AND NOT TO EXCEED 7%. WHEN ADJACENT TO 1.5% LANDING, CONSTRUCT CURB HEAD OPENING AT 1.5% IN THE DIRECTION OF PEDESTRIAN TRAVEL.
- 3 AN 8.33% CURB RAMP SLOPE IS ALLOWABLE WITH FLATTENED GUTTER FLAG SLOPE AND NOT TO EXCEED 11% GRADE CHANGE.
- 4 ±0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- 6 PROVIDE A LEVEL LANDING (MAXIMUM 2% SLOPE) IN ANY DIRECTION OF PEDESTRIAN TRAVEL. STANDARD LANDING SIZE IS 5 FEET BY 5 FEET.
- 8 PROVIDE GRADE BREAK PERPENDICULAR TO DIRECTION OF WHEELCHAIR TRAVEL.
- 14 CONSULT ENGINEER IF GRADE BREAK LOCATION (END OF LANDING DIMENSION "XR") REQUIRES FIELD ADJUSTMENT WHEN ESTABLISHING FINAL RADIAL DETECTABLE WARNING FIELD LOCATION.
- 15 FIELD SAW CUTS ALONG RADIAL DETECTABLE WARNING PLATES WILL BE NECESSARY TO MATCH EACH CURB RAMP EDGE. AVOID CUTTING THROUGH DOMES WHENEVER POSSIBLE. MAKE FIELD CUTS TRUE TO LINE AND WITHIN 1/8" DEVIATION. SMOOTH EDGES OF FIELD CUT PLATES.
- 16 USE 1' X 2" RECTANGULAR END PLATE AT END OF TYPE 4A1 RAMP AND PROVIDE MINIMUM 2' - 0" DETECTABLE WARNING FIELD COVERAGE (IN DIRECTION OF PEDESTRIAN TRAVEL) ALONG THE ENTIRE CURB RAMP WIDTH.
- 17 A MAXIMUM 3 INCH CONCRETE BORDER WITH IS ALLOWABLE IN FROM OF RADIAL DETECTABLE WARNING FIELD FOR CONSTRUCTABILITY PURPOSES. CONCRETE BORDER WIDTH MAY VARY UP TO 1 INCH.

RADIAL DETECTABLE WARNING FIELD PLACEMENT WHEN 5 FOOT GRADE BREAK DISTANCE PER SDD 8D5-d IS EXCEEDED




PLAN VIEW CURB RAMP TYPE 4B1 (GRADE BREAK DISTANCE GREATER THAN 5 FEET)



SECTION B - B FOR TYPE 4B1


**** IF RAMP SLOPE IS LESS THAN 5.0%, THEN NO ADJACENT UPHILL LANDING IS REQUIRED

*** MAXIMUM 8.33%




DETAIL B

RADIAL DETECTABLE WARNING FIELD PLACEMENT WHEN 5 FOOT GRADE BREAK DISTANCE PER SDD 8D5-b IS EXCEEDED




PLAN VIEW CURB RAMP TYPE 2 (GRADE BREAK DISTANCE GREATER THAN 5 FEET) (ON LINE WITH SIDEWALK)

NOTE: SECOND TYPE 2 RAMP NOT SHOWN



SECTION C - C FOR TYPE 2

- * MAXIMUM 2% SLOPE IN ALL DIRECTIONS IN FRONT OF GRADE BREAK
- ** WIDTH SHOWN ELSEWHERE IN THE PLANS
- *** MAXIMUM 8.33%




DETAIL C

CURB RAMPS RADIAL DETECTABLE WARNING FIELD APPLICATIONS


STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

	MIN.	MAX.
A	1.6"	2.4"
B	0.65"	1.5"
C	*	*
D	0.9"	1.4"

* THE C DIMENSION IS 50% TO 65% OF THE D DIMENSION.




PLAN VIEW




ELEVATION VIEW

**TRUNCATED DOMES
DETECTABLE WARNING PATTERN DETAIL**




RECTANGULAR
PLATES




RADIAL
PLATES

PLAN VIEW
DETECTABLE WARNING FIELDS (TYPICAL)



PLAN VIEW
RADIAL DETECTABLE
WARNING FIELD ATTRIBUTES



PLAN VIEW
RADIAL WEDGE PLATE
CONNECTION DETAIL

GENERAL NOTES

DETECTABLE WARNING FIELDS THAT ARE INSTALLED AT A CURB RAMP SHALL BE FROM THE SAME MANUFACTURER.

PLACE ALL DETECTABLE WARNING FIELD SYSTEMS IN ACCORDANCE TO THE MANUFACTURER'S RECOMMENDATION.

FIELD CUTS AT INTERMEDIATE JOINTS WITHIN THE RADIAL DETECTABLE WARNING FIELD ARE PROHIBITED.

DETERMINE FINAL RADIAL WARNING FIELD CONFIGURATION AND ITS INDIVIDUAL PLATE LOCATIONS. PERFORM PRE-LAYOUT PRIOR TO PLACEMENT IN PLASTIC CONCRETE. FOLLOW MANUFACTURER'S PRODUCT LIST AND INSTALLATION RECOMMENDATIONS.

FOR RADIAL DETECTABLE WARNING FIELD APPLICATIONS WHERE STANDARD RADIAL PLATES ARE NOT AVAILABLE AT AN INTERSECTION CURB RADIUS, A COMBINATION OF SQUARE OR RECTANGULAR PLATES AND RADIAL PLATES MAY BE USED TO FORM RADIAL CONFIGURATION. RADIAL WEDGE PLATES IN COMBINATION WITH SQUARE PLATES ARE ALSO ACCEPTABLE. FOLLOW MANUFACTURER'S RECOMMENDATIONS.

REFER TO CONTRACT AND STANDARD SPECIFICATIONS FOR FIELD CUTTING REQUIREMENTS.

DO NOT EMBED IN CONCRETE ANY FIELD-CUT PLATES WITH CUT EDGES SHORTER THAN 6 INCHES. CONSULT WITH MANUFACTURER FOR RE-DRILLING AND ANCHORING REQUIREMENTS OF FIELD-CUT PLATES.

15 FIELD SAW CUTS ALONG RADIAL DETECTABLE WARNING PLATES WILL BE NECESSARY TO MATCH EACH CURB RAMP EDGE. AVOID CUTTING THROUGH DOMES WHENEVER POSSIBLE. MAKE FIELD CUTS TRUE TO LINE AND WITHIN 1/8" DEVIATION. SMOOTH EDGES OF FIELD CUT PLATES.

CURB RAMPS RECTANGULAR AND RADIAL DETECTABLE WARNING PLATES	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2019 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
<small>FHWA</small>	



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL

NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS




SILT FENCE

* NOTE: 8'-0" POST SPACING ALLOWED IF A WOVEN GEOTEXTILE FABRIC IS USED.



JOINING TWO LENGTHS OF SILT FENCE ⑤





SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)

SILT FENCE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
4-29-05 /S/ Beth Canestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



INLET PROTECTION, TYPE A


GENERAL NOTES

INLET PROTECTION DEVICES SHALL BE MAINTAINED OR REPLACED AT THE DIRECTION OF THE ENGINEER.

MANUFACTURED ALTERNATIVES APPROVED AND LISTED ON THE DEPARTMENT'S EROSION CONTROL PRODUCT ACCEPTABILITY LIST MAY BE SUBSTITUTED.


WHEN REMOVING OR MAINTAINING INLET PROTECTION, CARE SHALL BE TAKEN SO THAT THE SEDIMENT TRAPPED ON THE GEOTEXTILE FABRIC DOES NOT FALL INTO THE INLET. ANY MATERIAL FALLING INTO THE INLET SHALL BE REMOVED IMMEDIATELY.

- ① FINISHED SIZE, INCLUDING FLAP POCKETS WHERE REQUIRED, SHALL EXTEND A MINIMUM OF 10" AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
- ② FOR INLET PROTECTION, TYPE C (WITH CURB BOX), AN ADDITIONAL 18" OF FABRIC IS WRAPPED AROUND THE WOOD AND SECURED WITH STAPLES. THE WOOD SHALL NOT BLOCK THE ENTIRE HEIGHT OF THE CURB BOX OPENING.
- ③ FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2X4.



**INLET PROTECTION, TYPE B
(WITHOUT CURB BOX)**

(CAN BE INSTALLED IN ANY INLET WITHOUT A CURB BOX)



INLET PROTECTION, TYPE C (WITH CURB BOX)

INSTALLATION NOTES

TYPE B & C

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.


THE CONTRACTOR SHALL DEMONSTRATE A METHOD OF MAINTENANCE, USING A SEWN FLAP, HAND HOLDS OR OTHER METHOD TO PREVENT ACCUMULATED SEDIMENT FROM ENTERING THE INLET.

TYPE D

DO NOT INSTALL INLET PROTECTION TYPE D IN INLETS SHALLOWER THAN 30", MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE.

TRIM EXCESS FABRIC IN THE FLOW LINE TO WITHIN 3" OF THE GRATE.


THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE, BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES, OF 3". WHERE NECESSARY THE CONTRACTOR SHALL CINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3" CLEARANCE. THE TIES SHALL BE PLACED AT A MAXIMUM OF 4" FROM THE BOTTOM OF THE BAG.



INLET PROTECTION, TYPE D


(CAN BE INSTALLED IN ANY INLET TYPE WITH OR WITHOUT A CURB BOX AS PER NOTE ②)

INLET PROTECTION TYPE A, B, C, AND D	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 10/16/02 DATE	/s/ Beth Connestra CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA	




SECTION B - B

**TURBIDITY BARRIER - FLOAT ALTERNATIVE
CAUTION - SEE NOTE 6**




PLAN VIEW



SECTION A - A

TURBIDITY BARRIER - STANDARD POST INSTALLATION



PLAN VIEW


TURBIDITY BARRIER PLACEMENT DETAILS

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- ① DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- ② SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- ③ WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- ④ IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- ⑤ ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- ⑥ FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- ⑦ ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- ⑧ USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



PLAN VIEW



SECTION C - C


**TURBIDITY BARRIER DETAIL SHOWING
TYPICAL PLACEMENT AT STRUCTURES**

TURBIDITY BARRIER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
6/4/02 DATE /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT
ENGINEER

FHWA




TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.




SECTION A-A



ALTERNATE LUG


6

6



**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.




ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)


S.D.D. 12 A 3-10

S.D.D. 12 A 3-10

NAME PLATE (STRUCTURES)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE 3/26/10	/S/ Scot Becker CHIEF STRUCTURAL DEVELOPMENT ENGINEER
FHWA	



CONSTRUCTION JOINT




SAWED JOINT

GENERAL NOTES

CREATE A LONGITUDINAL JOINT FOR PAVEMENT WIDTHS GREATER THAN 15 FEET.


CORRELATE LONGITUDINAL JOINTS WITH LANE LINES WHEN POSSIBLE.

- ① ANCHOR TIE BARS INTO DRILLED HOLES WITH AN EPOXY.
- ② PAVEMENT THAT WAS IN PLACE PRIOR TO THE CONTRACT.




PLAN VIEW


NO. 6 TIE BARS SPACED 30\"/>




**SECTION A-A
LONGITUDINAL CONSTRUCTION JOINT
TIE BARS ANCHORED
INTO EXISTING PAVEMENT**



DETAIL "A"



DETAIL "B"




DETAIL "C"

TIE BAR TABLE

PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
< 10 1/2"	NO. 4	30"	36"
≥ 10 1/2"	NO. 5	36"	36"
	NO. 4 *	30"	24" **

* SUBSTITUTE BENT BARS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES)

** CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.




**PLAN VIEW
SHOWING LOCATION OF TIE BARS**

**CONCRETE PAVEMENT
LONGITUDINAL JOINTS AND TIES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
March 2018 /S/ Peter Kemp, P.E.
DATE PAVEMENT SUPERVISOR
FHWA




JOINT DETAIL

PAVEMENT DEPTH AND JOINT SPACING TABLE


PAVEMENT DEPTH (D)	CONTRACTION JOINT SPACING
6", 6 1/2"	12'
7", 7 1/2"	14'
8" & ABOVE	15'



CONTRACTION JOINT



TIED TRANSVERSE CONSTRUCTION JOINT



CONTRACTION JOINT LOCATIONS

GENERAL NOTES

CONTRACTION JOINTS

CONSTRUCT TRANSVERSE CONTRACTION JOINTS NORMAL TO THE CENTERLINE.

LOCATE AND ORIENT CONTRACTION JOINTS THROUGH INTERSECTIONS AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

CONSTRUCTION JOINTS

LOCATE CONSTRUCTION JOINTS A MINIMUM OF 6 FEET FROM THE NEAREST CONTRACTION JOINT AND ALIGN PARALLEL TO THE CONTRACTION JOINTS.

FORM OR SAW CONSTRUCTION JOINTS.

THE CONTRACTOR MAY INSERT TIE BARS THROUGH THE HEADER BOARD AFTER THE CONCRETE HAS BEEN PLACED.

- ① REFER TO TYPICAL CROSS SECTIONS FOR PAVED WIDTH AND LOCATION OF LONGITUDINAL JOINTS.
- ② PROVIDE A SMOOTH VERTICAL FACE FOR THE ENTIRE DEPTH OF THE PAVEMENT WHEN FORMING CONSTRUCTION JOINTS. PROVIDE A 1/4-INCH RADIUS AT FORMED JOINTS.


6

6


S.D.D. 13 C 4-17

S.D.D. 13 C 4-17


URBAN NON-DOWELED CONCRETE PAVEMENT	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED March 2018 DATE	/s/ Peter Kemp, P.E. PAVEMENT SUPERVISOR
FHWA	




DETAIL "A"



DETAIL "B"



DETAIL "C"



DETAIL "D"


GENERAL NOTES

- THE PRIMARY ROADWAY CONTROLS THE TRANSVERSE JOINT PATTERN.
- ALIGN NEW JOINTS WITH EXISTING JOINTS OR CRACKS.
- CONSTRUCT TRANSVERSE JOINTS PERPENDICULAR TO THE ROADWAY.
- ADJUST TRANSVERSE JOINTS TO ALIGN WITH UTILITY FIXTURES (E.G MANHOLES AND INLETS) IN THE PAVEMENT STRUCTURE WHEN POSSIBLE. WATER VALVES DO NOT REQUIRE JOINT ADJUSTMENT.
- AVOID SLABS LESS THAN 2 FEET WIDE OR GREATER THAN 15 FEET WIDE.
- SEE TABLE FOR TRANSVERSE JOINT SPACING. JOINT SPACING SPECIFIED IS MAXIMUM AND ACTUAL SPACING CAN BE ADJUSTED TO ACCOMMODATE INTERSECTIONS.
- AVOID ANGLES LESS THAN 60° BY DOGLEGGING JOINTS THROUGH CURVE RADIUS POINTS. USE 90° ANGLES WHEN POSSIBLE.
- CORRELATE LONGITUDINAL JOINTS WITH LANE LINES WHEN POSSIBLE.


- ① PROVIDE TRANSVERSE JOINTS AT ALL PAVEMENT WIDTH CHANGES.
- ② CONSTRUCT DOWELED EXPANSION JOINT ON THE SIDE ROAD OF AN INTERSECTION IF THE SIDE ROAD IS CONCRETE PAVEMENT AND GREATER THAN 300 FEET IN LENGTH. ALIGN EXPANSION JOINT WITH EDGE OF RADIUS.
- ③ THE ENGINEER MAY APPROVE SLIGHT VARIATIONS FROM THESE JOINTING DETAILS.

PAVEMENT DEPTH AND JOINT SPACING TABLE


PAVEMENT DEPTH (D)	CONTRACTION JOINT SPACING
6", 6 1/2"	12'
7", 7 1/2"	14'
8" & ABOVE	15'




STANDARD INTERSECTION



SKEWED INTERSECTION



APPROACH TO MEDIAN



LARGE RIGHT TURN

CONCRETE PAVEMENT JOINTING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


LEGEND

- - - - - POTENTIAL DOWELED EXPANSION JOINT
- - - - - DOWELED JOINT
- TIED JOINT

GENERAL NOTES


USE AN EXPANSION JOINT FILLER MEETING THE REQUIREMENTS OF STANDARD SPECIFICATION 415.

6



STANDARD INTERSECTION

6




SKewed INTERSECTION

SDD 13C18 - 07b


SDD 13C18 - 07b

**CONCRETE PAVEMENT
STEEL REINFORCEMENT**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



DOWELED TRANSVERSE ①



UNTIED - LONGITUDINAL

EXPANSION JOINTS

TIE BAR TABLE


PAVEMENT DEPTH (D)	TIE BAR SIZE	TIE BAR LENGTH (L)	MAX. TIE BAR SPACING
< 10 1/2"	NO. 4	30"	36"
≥ 10 1/2"	NO. 5	36"	36"
	NO. 4*	30"	24" **

* SUBSTITUTE BENT BARS AT LONGITUDINAL JOINTS WHEN EQUIPMENT LIMITATIONS DURING CONSTRUCTION WARRANT (e.g. AUXILIARY LANES OR TURN LANES)


** CONFORM TO 15" MINIMUM SPACING FROM TRANSVERSE JOINTS; SPACING BETWEEN TIE BARS WILL BE 30" AT TRANSVERSE JOINTS.

GENERAL NOTES


- ① USE DOWELED EXPANSION JOINTS ON SIDE ROADS AT INTERSECTIONS (TO ISOLATE THE SIDE ROAD FROM THE THROUGH STREET) IF THE SIDE ROAD IS CONCRETE PAVEMENT AND GREATER THAN 300 FEET IN LENGTH.
- ② SPACE CONTRACTION JOINTS IN ACCORDANCE WITH SDD 13C4, 13C11 OR 13C13.
- ③ LOCATE CONSTRUCTION JOINTS A MINIMUM OF 6 FEET FROM THE NEAREST CONTRACTION JOINT AND ALIGN PARALLEL TO CONTRACTION JOINTS.
- ④ CONSTRUCTION JOINTS CAN BE FORMED OR SAWED.
- ⑤ IF JOINT IS FORMED, PROVIDE A 1/4" RADIUS.
- ⑥ ANCHOR TIE BARS INTO DRILLED HOLES WITH AN EPOXY.




UNDOWELED TRANSVERSE




TIED LONGITUDINAL




DOWELED TRANSVERSE ③




TIED LONGITUDINAL



DOWELED TRANSVERSE



TIED TRANSVERSE ③
(FOR USE ON NON-DOWELED PAVEMENTS ONLY)




TIED LONGITUDINAL TO EXISTING

CONTRACTION JOINTS ②


CONSTRUCTION JOINTS ④

CONCRETE PAVEMENT JOINT TYPES


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)**

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY $1" \pm 0.5"$ AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY 0.1" AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO 2" FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)


6

6

SDD 13C19 - 03

SDD 13C19 - 03

HMA LONGITUDINAL JOINTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2020 DATE	/S/ Steven Hefel HMA PAVEMENT ENGINEER
FHWA	



**DETAIL A
MAINLINE CLOSURE WITH POSTED DETOUR**

WORK ZONE GREATER THAN OR EQUAL TO 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

**DETAIL B
MAINLINE CLOSURE WITH POSTED DETOUR**


WORK ZONE LESS THAN 1/2 MILE FROM
DETOUR ROUTE (1000 FEET IF URBAN)

LEGEND

- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- WORK AREA
- FLAGS, 16" X 16" MIN. (ORANGE)

SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750

- M4 - 8
- M3 - X
- OR OR M1 - 4 M1 - 6 M1 - 5A
- OR M05 - 1 M06 - 1




**DETAIL C
MAINLINE CLOSURE, NO POSTED DETOUR**

SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦


**BARRICADES AND SIGNS
FOR MAINLINE CLOSURES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER
FHWA



**DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW**



**DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW**

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

THE R11 - 2, R11 - 3, M4 - 9, R11 - 4, AND R10 - 61 SIGNS PLACED ON THE BARRICADES SHALL COVER NO MORE THAN THE TOP RAIL. THE SIGNS SHALL NOT COVER ANY PORTION OF THE MIDDLE RAIL OR BOTTOM RAILS.

"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:

- R11 - 2 SHALL BE 48" X 30"
- R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60" X 30"
- M4 - 9 SHALL BE 30" X 24"
- M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
- MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
- D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
- R1 - 1 SHALL BE 36" X 36"


- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

**BARRICADES AND SIGNS
FOR
VARIOUS CLOSURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA



DRUM




42" CONE

DO NOT USE IN TAPERS
1/2 SPACING OF DRUMS


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.

* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2021 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER


GENERAL NOTES

STOP SIGN SHALL BE PLACED A MINIMUM OF 6 FEET TO A MAXIMUM OF 50 FEET FROM THE EDGELINE LOCATION.


- ① 18-INCH STOP LINES MAY BE DELETED OR ADDED BY THE REGION MARKING ENGINEER BASED ON VISIBILITY AND SIGHT LINES.
- ② NO STOP LINE IS REQUIRED IF STOP SIGN IS LESS THAN OR EQUAL TO 40 FEET FROM THE EDGELINE.
- ③ NO STOP LINE IS REQUIRED IF STOP SIGN IS LESS THAN OR EQUAL TO 30 FEET FROM THE FLANGELINE EXTENSION.
- ④ MOVE CLOSER TO THE EDGE OF TRAVEL LINE AS NEEDED FOR VISIBILITY AND SIGHT LINES (NO CLOSER THAN 4 FEET).
- ⑤ LADDER BAR CROSSWALKS SHOULD ONLY BE USED FOR MID BLOCK CROSSINGS. USE 2 - 6" TRANSVERSE LINES INSTEAD.



TYPICAL STOP LINE PAVEMENT MARKING WITH CURB AND GUTTER




TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH RIGHT TURN LANE



TYPICAL STOP LINE PAVEMENT MARKING FOR SIDEROADS WITH CROSSWALK MARKING

TYPICAL PAVEMENT MARKING FOR MID-BLOCK CROSSWALK



TYPICAL STOP LINE PAVEMENT MARKING WITHOUT CURB AND GUTTER





STOP LINE AND CROSSWALK PAVEMENT MARKING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2019 /S/ Matthew Rauch
DATE STATE SIGNING AND MARKING ENGINEER

FHWA

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  DIRECTION OF TRAFFIC
-  WORK ZONE

GENERAL NOTES

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY THE REGIONAL TRAFFIC UNIT.

"WO" SIGN IS THE SAME AS "W" SIGN EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.


CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

W20-1A AND G20-2A SIGNS ARE NOT REQUIRED IF THE WORK AREA IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT. G20-2A SIGNS MAY ALSO BE OMITTED IF DURATION OF WORK IS LESS THAN 7 CONTINUOUS DAYS AND NIGHTS.

6

6



POSTED SPEED LIMIT PRIOR TO WORK STARTING (MPH)	ADVANCE WARNING SIGN SPACING (A) FEET	SHOULDER TAPER L / 3 W, LATERAL OFFSET (FT)						BUFFER SPACE (B) FEET
		3	4	5	6	7	8	
25	200'	10	14	17	21	24	28	55
30	200'	15	20	25	30	35	40	85
35	350'	20	27	34	40	47	54	120
40	350'	26	35	44	53	62	70	170
45	500'	45	59	74	89	104	119	220
50	500'	50	66	83	99	116	132	280
55	500'	54	73	91	109	127	145	335'

TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2020 /S/ Andrew Heidtke
DATE STATEWIDE WORK ZONE TRAFFIC SAFETY ENGINEER


FHWA

SDD 15D28 - 04

SDD 15D28 - 04




NARROW SIDEWALK PASSING DETAIL



TEMPORARY PEDESTRIAN ACCESS

GENERAL NOTES

- BARRICADE DEVICE SELECTED FROM APPROVED PRODUCT LIST
- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② SHEETING REQUIRED ON MORE THAN 50% OF BARRICADE WIDTH.
- ③ PLACE SHEETING ON BOTH SIDES OF THE BARRICADE.
- * USE THIS DETAIL FOR SHEETING PLACEMENT REFERENCE.




TEMPORARY PEDESTRIAN BARRICADE*


GENERAL NOTES

CURB RAMPS SHALL BE 48" MIN. WIDTH WITH A FIRM, STABLE AND SLIP RESISTANT SURFACE.
 CURB RAMPS AND LANDINGS SHALL HAVE A 1:50 (2%) MAX. CROSS-SLOPE.
 CLEAR SPACE OF 48" X 48" SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.
 LATERAL JOINTS OR GAPS BETWEEN SURFACES SHALL BE LESS THAN 1/2" WIDTH.
 CHANGES BETWEEN SURFACE HEIGHTS SHALL NOT EXCEED 1/2". LATERAL EDGES MAY BE VERTICAL UP TO 1/4" HIGH AND SHALL BE BEVELED AT 1:2 BETWEEN 1/4" AND 1/2".


- ① INSTALL CONTRASTING TEMPORARY DETECTABLE WARNING FIELD AT PEDESTRIAN STREET CROSSINGS, AS SHOWN IN THE PLANS.
- ② PROTECTIVE EDGING WITH A 2" MIN. HEIGHT SHALL BE INSTALLED WHEN A CURB RAMP OR LANDING PLATFORM HAS A VERTICAL DROP OF 6" OR GREATER OR HAS A SIDE APRON SLOPE STEEPER THAN 1:3 (33%). PROTECTIVE EDGING SHOULD BE CONSIDERED WHEN CURB RAMPS OR LANDING PLATFORMS HAVE A VERTICAL DROP OF 3" OR MORE.
- ③ DETECTABLE EDGING WITH 6" MIN. HEIGHT AND CONTRASTING COLOR SHALL BE INSTALLED ON ALL CURB RAMP LANDINGS WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
- ④ DO NOT RESTRICT WATER FLOW IN THE GUTTER SYSTEM.
- ⑤ 6" MINIMUM BETWEEN CURB FACE AND EDGE OF RAMP
- ⑥ IF ONLY PART OF THE END PANEL OF TEMPORARY PEDESTRIAN BARRICADE PANEL IS NEEDED, EXTEND EXCESS PORTION OF TEMPORARY PEDESTRIAN BARRICADE PANEL HERE.



PERSPECTIVE VIEW





FRONT VIEW



SIDE VIEW

TEMPORARY CURB RAMP PARALLEL TO CURB

<p>TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION</p>
<p>STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION</p>



TEMPORARY CURB RAMP PERPENDICULAR TO CURB

GENERAL NOTES

CURB RAMPS SHALL BE 48" MINIMUM WIDTH WITH A FIRM, STABLE AND SLIP RESISTANT SURFACE.

ALTERNATE SIDEWALK WORK BETWEEN LEFT AND RIGHT SIDE OF ROADWAY TO MAINTAIN PEDESTRIAN ACCESS.

CURB RAMPS AND LANDINGS SHALL HAVE A 1:50 (2%) MAX. CROSS-SLOPE.







CLEAR SPACE OF 48" X 48" SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.

LATERAL JOINTS OR GAPS BETWEEN SURFACES SHALL BE LESS THAN 1/2" WIDTH.

CHANGES BETWEEN SURFACE HEIGHTS SHALL NOT EXCEED 1/2". LATERAL EDGES MAY BE VERTICAL UP TO 1/4" HIGH AND SHALL BE BEVELED AT 1:2 BETWEEN 1/4" AND 1/2".


- ① INSTALL CONTRASTING TEMPORARY DETECTABLE WARNING FIELD AT PEDESTRIAN STREET CROSSINGS, AS SHOWN IN THE PLANS
- ② PROTECTIVE EDGING WITH A 2" MIN. HEIGHT SHALL BE INSTALLED WHEN A CURB RAMP OR LANDING PLATFORM HAS A VERTICAL DROP OF 6" OR GREATER OR HAS A SIDE APRON SLOPE STEEPER THAN 1:3 (33%). PROTECTIVE EDGING SHOULD BE CONSIDERED WHEN CURB RAMPS OR LANDING PLATFORMS HAVE A VERTICAL DROP OF 3" OR MORE.
- ③ DETECTABLE EDGING WITH 6" MIN. HEIGHT AND CONTRASTING COLOR SHALL BE INSTALLED ON ALL CURB RAMP LANDINGS WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
- ④ DO NOT RESTRICT WATER FLOW IN THE GUTTER SYSTEM.
- ⑤ CAN ONLY BE USED FOR RAMPS WITH 6" OR LESS OF VERTICAL CHANGE.

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  SIGN ON TEMPORARY SUPPORT
-  UNDER PEDESTRIAN TRAFFIC
-  WORK AREA
-  TEMPORARY PEDESTRIAN BARRICADE
-  DIRECTION OF TRAFFIC

GENERAL NOTES


- SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE WISCONSIN STANDARD SIGN PLATES.
- WHERE TEMPORARY BARRICADE RUNS PARALLEL ALONG SIDEWALK, PLACE THE FACE OF THE BARRICADE AT THE EDGE OF THE SIDEWALK.
- SIGNS THAT REMAIN IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.
- ① IF TERRACE IS LESS THAN 6 FEET WIDE, OMIT TEMPORARY PEDESTRIAN BARRICADE FROM THE SIDEWALK TO THE CURB.
 - ② PLACE BARRICADE CLOSURE SO THAT THE TEMPORARY PEDESTRIAN BARRICADE END IS AT THE LAST OPEN SIDEWALK ACCESS TO RESIDENCES OR BUSINESSES BEFORE THE SIDEWALK CLOSURE.
 - ③ IF TEMPORARY PEDESTRIAN BARRICADE PANEL IS WIDER THAN THE SIDEWALK WIDTH, THE PORTION OF EXCESS PANEL SHOULD EXTEND INTO THE TERRACE.
 - ④ MOUNTING HEIGHT OF 5 FEET FROM THE SURFACE TO THE BOTTOM OF SIGN.






SIDEWALK DETOUR, SIDEWALK ONLY ON ONE SIDE

TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

URBAN AREA



RURAL AREA (See Note 2)



GENERAL NOTES

1. Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
2. If signs are mounted on or behind barrier wall, see A4-10 sign plate.
The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (±). The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±).
3. For expressways and freeways, mounting height is 7'- 3" (±) or 6'-3" (±) depending upon existence of a sub-sign.
4. Minimum mounting height for signs mounted on traffic signal poles is 5'- 3" (±).
5. Offset distance shall be consistent with existing signs or consistent throughout length of project.
6. The (±) tolerance for mounting height is 3 inches.
7. Folding signs shall be mounted at a height of 5'-3" (±) or as directed by the Engineer.

POST EMBEDMENT DEPTH

Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

* * The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

TYPICAL INSTALLATION OF PERMANENT TYPE II SIGNS ON SINGLE POSTS


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 5/13/2020 PLATE NO. A4-3.22

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



G20-2A

Metric equivalent
for this sign is:


SIZE	
1	900 mm X 450 mm
2	1200 mm X 600 mm
3	1200 mm X 600 mm
4	1200 mm X 600 mm
5	1200 mm X 600 mm

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.	Area sq.
1	36	18	1 1/8	3/8	1/2	4	3 3/4	2 1/2	4 1/8	4 1/8	11 1/8	2	1	12 1/8													4.5	0.41
2	48	24	1 1/2	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2													8.0	0.72
3	48	24	1 1/2	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2													8.0	0.72
4	48	24	1 1/2	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2													8.0	0.72
5	48	24	1 1/2	1/2	5/8	6	4 1/2	3 3/4	5 7/8	6 3/4	16 3/4	2 1/2	1 3/4	18 1/2													8.0	0.72


STANDARD SIGN G20-2A	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R. Rauch</i> for State Traffic Engineer
DATE 9/30/09	PLATE NO. G20-2A.8

NOTES

1. Sign is Type II-Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. M4-9BL is the same as M4-9BR except the arrow is reversed.



M4 - 9BR



Arrow Detail

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	30	24	1 1/8	3/8	1/2	5	5 1/4	7 1/8	3 3/4	1	1 1/8	1 5/8	11 3/4	7	6	2											5.00
3																											
4																											
5																											

STANDARD SIGN
M4-9B L&R


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 7/1/19 PLATE NO. M4-9B.2

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



M4-9BA

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2	30	24	1 1/8	3/8	1/2	5	4	7 1/8	2 1/2	1	1 7/8	1 5/8	11 3/4	9 1/8													5.0
3																											
4																											
5																											

STANDARD SIGN
M4-9BA

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 3/24/16 PLATE NO. M4-9BA.1

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - White
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Use Size 2 for Sidewalks. Use Size 3 for Paths and Trails.



R9-9

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	24	12	1 3/4	1/2	1/2	3	2 1/8	1 3/4	10	8 1/8																	2.0
2M	24	12	1 3/4	1/2	1/2	3	2 1/8	1 3/4	10	8 1/8																	2.0
3	30	18	1 3/4	1/2	1/2	4	3 1/2	3	12 1/2	10 1/4																	3.75
4																											
5																											

STANDARD SIGN
R9-9


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 8/11/16 PLATE NO. R9-9.6

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



R9-9A

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	30	18	1 1/8	3/8	1/2	3	2 1/2	2	10 1/2	8	7																3.75
2M	30	18	1 1/8	3/8	1/2	3	2 1/2	2	10 1/2	8	7																3.75
3																											
4																											
5																											

STANDARD SIGN
R9-9A

WISCONSIN DEPT OF TRANSPORTATION



APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 8/31/2020 PLATE NO. R9-9A.1

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - C except Size 1 is Series D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Use Size 2 for Sidewalks. Use Size 3 for Paths and Trails.
6. R9-11D (double arrow)
R9-11L (left arrow)
R9-11R (right arrow)



R9-11

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	24	12	1 1/8	3/8	3/8	1 1/2	1 1/2	1 1/2	9 3/4	5/8	1 1/2	7 5/8	3 1/2	9 1/4	6 5/8	5 1/8		1	1/8	2 3/4							2.0
2M	24	12	1 1/8	3/8	3/8	1 1/2	1 1/2	1 1/2	9 3/4	5/8	1 1/2	7 5/8	3 1/2	9 1/4	6 5/8	5 1/8		1	1/8	2 3/4							2.0
3	30	15	1 1/8	3/8	1/2	2	1 1/2	1 1/2	13	3/4	2	10 1/4	4 5/8	12 3/8	8 7/8	6 7/8		1 1/4	1/4	3 5/8							3.125
4																											
5																											

STANDARD SIGN
R9-11

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 3/30/2021 PLATE NO. R9-11.4


PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: _____ **E**

7

7

NOTES

1. Sign is Type II - Type H Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - White
Message - Black
3. Message Series - D
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



R11-2B

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
2M	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
3	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
4	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0
5	48	30	1 3/8	1/2	5/8	8	5	4	19 3/4	9 3/4	9 7/8																10.0

STANDARD SIGN
R11-2B

WISCONSIN DEPT OF TRANSPORTATION


APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 4/1/11 PLATE NO. R11-2B.2


PROJECT NO: _____ SHEET NO: _____ E

NOTES

1. Sign is Type II - Type H Reflective
2. Color:
Background - White
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Substitute appropriate numerals to nearest quarter mile and optically adjust spacing to achieve proper balance.



R11-3C ** See Note 5



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36	15	1 3/8	1/2	5/8	4	3	2 1/2	13 1/4	2 1/4	3	8	8	1 1/2	2	10 3/4		7 1/8									3.75
2S	60	24	1 3/8	1/2	5/8	6	5	4	20 1/8	3	5	12	13 1/4	1 3/4	3	17 3/8		11 7/8									10.0
2M	60	24	1 3/8	1/2	5/8	6	5	4	20 1/8	3	5	12	13 1/4	1 3/4	3	17 3/8		11 7/8									10.0
3																											
4																											
5																											

STANDARD SIGN
R11-3C









WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 7/28/16 PLATE NO. R11-3C.3

NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.



W20-1A

W20-1C

W20-1B

W20-1G

W20-1F

W20-1E


SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	5	2 5/8	3 1/4	10 1/8	7	7 5/8	8 7/8	1 1/8	4 1/2	3 1/2	9	3 1/4	2 1/2	2 1/4	5 5/8	9	1 3/8	8	1 3/4	10 3/4	6	9.0
2S	48		2 1/4	3/4	1	8	3 3/4	5 1/8	15 3/8	11 1/8	12 1/8	14 3/8	1 5/8	6 7/8	5 3/8	13 7/8	4 3/8	3 7/8	3	8 5/8	13 3/4	2 1/8	11 7/8	2 3/4	16 3/8	9	16.0
2M	48		2 1/4	3/4	1	8	3 3/4	5 1/8	15 3/8	11 1/8	12 1/8	14 3/8	1 5/8	6 7/8	5 3/8	13 7/8	4 3/8	3 7/8	3	8 5/8	13 3/4	2 1/8	11 7/8	2 3/4	16 3/8	9	16.0
3	48		2 1/4	3/4	1	8	3 3/4	5 1/8	15 3/8	11 1/8	12 1/8	14 3/8	1 5/8	6 7/8	5 3/8	13 7/8	4 3/8	3 7/8	3	8 5/8	13 3/4	2 1/8	11 7/8	2 3/4	16 3/8	9	16.0
4	48		2 1/4	3/4	1	8	3 3/4	5 1/8	15 3/8	11 1/8	12 1/8	14 3/8	1 5/8	6 7/8	5 3/8	13 7/8	4 3/8	3 7/8	3	8 5/8	13 3/4	2 1/8	11 7/8	2 3/4	16 3/8	9	16.0
5	48		2 1/4	3/4	1	8	3 3/4	5 1/8	15 3/8	11 1/8	12 1/8	14 3/8	1 5/8	6 7/8	5 3/8	13 7/8	4 3/8	3 7/8	3	8 5/8	13 3/4	2 1/8	11 7/8	2 3/4	16 3/8	9	16.0

STANDARD SIGN
W20-1A, B, C, D, E, F, G & H


WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer


DATE 3/25/2020 PLATE NO. W20-1.11




W20-3A




W20-3D




W20-3C



W20-3B



W20-3G



W20-3F

NOTES

1. Sign is Type II - Type F Reflective - reference WIS DOT Standard Specification for HIGHWAY and STRUCTURE CONSTRUCTION latest edition.
2. Color:
Background - Orange
Message - Black
3. Message Series - see note 5
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.
5. Lines 1 and 2 are Series D.
Line 3 is Series D for AHEAD and Series C for all other distances.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	5	3 3/8	3 1/2	1 1/8	4	8 3/8	8 7/8	12 1/2	11	9	6	10 1/8	2 1/2	1 7/8	5 5/8	8	1 3/8	4 1/2	3 1/2	10 3/4	1 3/4	9.0
2S	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
2M	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
3	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
4	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0
5	48		2 1/4	3/4	1	7	4 1/2	4 3/4	1 1/2	5 1/4	11 3/4	12 1/2	17 1/4	14 5/8	12	8	13 1/2	3 3/8	2 5/8	7 1/2	10 5/8	1 7/8	6	4 5/8	14 3/8	2 3/8	16.0


STANDARD SIGN
W20-3A, B, C, D, F & G

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 3/18/11 PLATE NO. W20-3.7

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: _____ E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Orange
Message - Black
3. Message Series - C
4. Corners may be square or rounded when base material is plywood but borders shall be rounded as shown. When base material is metal, the corners and borders shall be rounded.

7

7

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1	36		1 5/8	5/8	3/4	6	3 1/2	16	9																		9.0
2S	48		2 1/4	3/4	1	8	5	21 3/8	11 1/4																		16.0
2M	48		2 1/4	3/4	1	8	5	21 3/8	11 1/4																		16.0
3	48		2 1/4	3/4	1	8	5	21 3/8	11 1/4																		16.0
4	48		2 1/4	3/4	1	8	5	21 3/8	11 1/4																		16.0
5	48		2 1/4	3/4	1	8	5	21 3/8	11 1/4																		16.0



STANDARD SIGN
W21-5

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R Rauch*
for State Traffic Engineer

DATE 4/30/2020 PLATE NO. W21-5.6

PROJECT NO: _____ HWY: _____ COUNTY: _____ SHEET NO: **E**



DESIGN DATA

LIVE LOAD:
 DESIGN LOADING: HL-93
 INVENTORY RATING FACTOR: 1.13
 OPERATING RATING FACTOR: 1.47
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV) = 250 KIPS

STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 "/S.F.

MATERIAL PROPERTIES:

CONCRETE MASONRY { SUPERSTRUCTURE $f'c = 4,000$ p.s.i.
 { ALL OTHER $f'c = 3,500$ p.s.i.
 HIGH STRENGTH BAR STEEL REINFORCEMENT (GRADE 60) $f_y = 60,000$ p.s.i.

HYDRAULIC DATA:

100 YEAR FREQUENCY

$Q_{100} = 840$ c.f.s.
 $VEL. = 6.0$ f.p.s.
 $HW_{100} = EL. 636.75$
 $WATERWAY AREA = 138$ sq. ft.
 $DRAINAGE AREA = 1.3$ sq. mi.
 $SCOUR CRITICAL CODE = 5$
 $DATUM = NAVD88 (2012)$

2 YEAR FREQUENCY

$Q_2 = 390$ c.f.s.
 $VEL. = 3.2$ f.p.s.
 $HW_2 = EL. 634.40$

FREQUENCY OF OVERTOPPING

$Q_{71} = 770$ c.f.s.
 $WATER SURFACE EL. 636.12$
 $FREQUENCY = 71$ YEARS

FOUNDATION DATA:

ABUTMENTS TO BE SUPPORTED ON HP 10 x 42 STEEL PILING DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 110 TONS # PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC FORMULA. ESTIMATED LENGTH 65'-0". PRE-BORE PILES ADJACENT TO SANITARY LINE 15'-0".


THE FACTORED AXIAL RESISTANCE OF PILES IN COMPRESSION USED FOR DESIGN IS THE REQUIRED DRIVING RESISTANCE MULTIPLIED BY A RESISTANCE FACTOR OF 0.5 USING MODIFIED GATES TO DETERMINE DRIVEN PILE CAPACITY.

TRAFFIC DATA:

A.A.D.T. = 800 (2023)
 A.A.D.T. = 875 (2043)
 R.D.S. = 30 M.P.H.

- * ATTACHMENT FOR THRIE BEAM TYPE GUARDRAIL.
- DENOTES WING NUMBER.
- ECO-PASSAGE. SEE DETAIL ON SHEET 2.

COST OF EXCAVATION OR FILL IN THE HATCHED AREAS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE FOR "EXCAVATION FOR STRUCTURES BRIDGES B-5-474".



ELEVATION

LIST OF DRAWINGS


1. GENERAL PLAN
2. QUANTITIES AND NOTES
3. SUBSURFACE EXPLORATION
4. SOUTH ABUTMENT
5. SOUTH ABUTMENT PILE LAYOUT
6. SOUTH ABUTMENT WING 1 DETAILS
7. SOUTH ABUTMENT WING 2 DETAILS
8. SOUTH ABUTMENT DETAILS & BILL OF BARS
9. NORTH ABUTMENT
10. NORTH ABUTMENT PILE LAYOUT
11. NORTH ABUTMENT WING 3 DETAILS
12. NORTH ABUTMENT WING 4 DETAILS
13. NORTH ABUTMENT DETAILS & BILL OF BARS
14. ALTERNATE CONSTRUCTION JOINT
15. SUPERSTRUCTURE
16. SUPERSTRUCTURE PLAN
17. SUPERSTRUCTURE DETAILS AND BILL OF BARS
18. COMBINATION RAIL TYPE "C2"
19. COMBINATION RAIL TYPE "C2" DETAILS



10/11/2022

BRIDGE OFFICE CONTACT:
 AARON BONK
 (608)-261-0261
 CONSULTANT CONTACT:
 ARLEN BEAUDETTE
 (715)-834-3161

PROFILE GRADE LINE
(CHANTEL STREET)



10/11/2022 PENTABLE:BRcou_shd_util.tbi

DATE: DATE: CHECKED BY: BACK CHECKED BY: CORRECTED BY:

8

8


NO.	DATE	REVISION	BY
ORIGINAL PLANS PREPARED BY			
AVRES 3433 Oakwood Hills Parkway Eau Claire, WI 54701 www.AyresAssociates.com			
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
ACCEPTED		SDR 11/15/22	DATE
CHIEF STRUCTURES DESIGN ENGINEER			
STRUCTURE B-5-474			
CHANTEL STREET OVER BEAVER DAM CREEK			
COUNTY	BROWN	TOWN/CITY/VILLAGE	GREEN BAY
DESIGN SPEC. AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS			
DESIGNED BY	JCK	DESIGN CK'D.	ZSS
DRAWN BY	ZSS/CLP	PLANS CK'D.	AEB
GENERAL PLAN			SHEET 1 OF 19

TOTAL ESTIMATED QUANTITIES



BID ITEM NUMBER	BID ITEMS	UNIT	S. ABUT.	N. ABUT.	SUPER.	TOTAL
203.0260	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS P-5-719	EACH	-----	-----	-----	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGES B-5-474	EACH	-----	-----	-----	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	205	205	-----	410
502.0100	CONCRETE MASONRY BRIDGES	CY	47.0	47.0	135.0	229
502.3200	PROTECTIVE SURFACE TREATMENT	SY	-----	-----	200	200
502.3210	PIGMENTED SURFACE SEALER	SY	-----	-----	48	48
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	3,330	3,330	-----	6,660
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	2,190	2,200	22,780	27,170
513.7011	RAILING STEEL TYPE C2	LF	-----	-----	114.7	114.7
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	15	15	-----	30
550.0010	PRE-BORING CONSOLIDATED MATERIALS	LF	30	30	-----	60
550.1100	PILING STEEL HP 10-INCH x 42 LB	LF	520	520	-----	1,040
606.0300	RIPRAP HEAVY	CY	55	60	-----	125
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	100	100	-----	200
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	2	2	-----	4
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	70	70	-----	140
645.0120	GEOTEXTILE TYPE HR	SY	130	135	-----	265
SPV.0195.01	SELECT CRUSHED MATERIAL FOR TRAVEL CORRIDOR	TON	-----	5	-----	5
NON-BID ITEMS						
	FILLER	SIZE	-----	-----	-----	1/2" & 3/4"

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.
 BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS SHOWN OR NOTED OTHERWISE.
 THE FIRST DIGIT OF A THREE DIGIT BAR NO. AND THE FIRST TWO DIGITS OF A FOUR DIGIT BAR NO. SIGNIFIES THE BAR SIZE. JOINT FILLER SHALL CONFORM TO THE REQUIREMENTS OF A.A.S.H.T.O. DESIGNATION M 153, TYPE I, II OR III OR A.A.S.H.T.O. DESIGNATION M 213.
 THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH RIPRAP HEAVY AND GEOTEXTILE TYPE HR TO THE EXTENT SHOWN ON THE GENERAL PLAN SHEET AND IN THE ABUTMENT DETAILS.
 SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE UNLESS AN ALTERNATE METHOD IS APPROVED BY THE ENGINEER.
 THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES BRIDGES B-5-474" SHALL BE THE EXISTING GROUNDLINE.
 THE EXISTING STRUCTURE, P-5-719, TO BE REMOVED, IS A 23.5-FT. LONG SINGLE-SPAN PRESTRESSED CONCRETE CHANNEL BRIDGE ON STEEL PILE BENT VERTICAL ABUTMENTS WITH CONCRETE BACKING WITH A 40.5-FT. CLEAR ROADWAY WIDTH AND 7-FT WIDE SIDEWALKS.
 THE BACKFILL QUANTITIES ARE BASED ON THE PAY LIMITS SHOWN ON THE PLANS AND MAY NOT REFLECT ACTUAL PLACED QUANTITIES. "BACKFILL STRUCTURE TYPE A" REQUIRED DIRECTLY BEHIND ABUTMENTS AND ABUTMENTS WINGS FOR 3 FEET. BACKFILL PLACED BEYOND PAY LIMITS OR EXCEEDING PLAN QUANTITIES SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES.
 PROTECTIVE SURFACE TREATMENT AND PIGMENTED SURFACE SEALER IS TO BE APPLIED AS SHOWN IN DETAIL ON THIS SHEET.
 BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS NOTED OTHERWISE.
 EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.
 EXTENT OF BELOW GRADE SUBSTRUCTURES ARE NOT KNOWN. REMOVE EXISTING SUBSTRUCTURES AS NEEDED TO BUILD NEW SUBSTRUCTURES. COST OF SUBSTRUCTURE REMOVAL IS CONSIDERED INCIDENTAL TO "REMOVING STRUCTURE" BID ITEM.
 AT THE BACK FACE OF ABUTMENTS AND AT EXISTING ABUTMENT REMOVALS, ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH BACKFILL STRUCTURE TYPE A.
 AT ABUTMENTS, CONCRETE POURED UNDERWATER WILL BE ALLOWED AND SHALL BE DONE IN ACCORDANCE WITH SECTION 502.3.5.3 OF THE STANDARD SPECIFICATIONS.
 TWO STEEL SHEET PILES NEAR THE NORTH ABUTMENT MEASURING 6-FT. BY 20-FT. ARE TO BE SALVAGED. SEE SPECIAL PROVISIONS FOR EXACT DETAILS.




TYPICAL FILL SECTION AT WING TIPS




BACKFILL STRUCTURE LIMITS THRU ABUTMENT

- ☐ BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- ⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8.



ECO-PASSAGE DETAIL

- ECO-PASSAGE. FILL VOIDS IN RIPRAP HEAVY WITH "SELECT CRUSHED MATERIAL FOR TRAVEL CORRIDOR". TO FULLY FILL ALL VOIDS AND LEAVE, ON AVERAGE, TWO INCHES ABOVE THE LOWEST ROCK POINTS WHERE THEY ABUT EACH OTHER. PROVIDE LEVEL SURFACE OF THE ECO-PASSAGE. THE TRANSITIONS OF THE AT-GRADE ECO PASSAGE TO THE EDGES OF THE RIPRAP HEAVY SHALL BE GRADUAL WITH NO MORE THAN 2:1 SLOPE. "SELECT CRUSHED MATERIAL FOR TRAVEL CORRIDOR" SHALL BE COMPACTED ONCE IN PLACE.



PROTECTIVE SURFACE TREATMENT AND PIGMENTED SURFACE SEALER DETAIL

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
 Eau Claire, WI 54701
 www.AyresAssociates.com

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		ZSS	PLANS CK'D. AEB
QUANTITIES AND NOTES			SHEET 2 OF 19



10/14/2022 PENTABLE:BRReou_shd_uhll.tbi

8

8

BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
1	JULY 19, 2021	568927.09	83334.92
2	JULY 20, 2021	568971.92	83323.33

BORINGS COMPLETED BY: ECS MIDWEST, LLC
 REPORT COMPLETED BY: ECS MIDWEST, LLC
 ALL COORDINATES REFERENCED TO WCCS NAD 83(91) BROWN COUNTY




STATE PROJECT NUMBER

4987-02-78

MATERIAL SYMBOLS

	ASPHALT		TOPSOIL		PEAT
	CONCRETE		FILL		GRAVEL
	SAND		CLAY		SILT
	BOULDERS OR COBBLES		LIMESTONE		BEDROCK (UNKNOWN)
	SHALE		SANDSTONE		IGNEOUS/META

LEGEND OF BORING



(1) UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)

(2) UNLESS OTHERWISE SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION

- AT TIME OF DRILLING
- END OF DRILLING
- AFTER DRILLING

ABBREVIATIONS

F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		ZSS	PLANS CKD. AEB
SUBSURFACE EXPLORATION			SHEET 3 OF 19

10/11/2022 PENTABLE:BRou...shd_util.tbl


8

8


NOTE:
SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE).




ELEVATION
(LOOKING SOUTH)
FOR SECTION A SEE SHEET 8.



SECTION B



SECTION C



PLAN

▲ 3/4" CORK FILLER ON VERTICAL FACE ONLY.

⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".

⊠ VERTICAL 18" RUBBERIZED MEMBRANE WATERPROOFING TO EXTEND FROM BRIDGE SEAT TO TOP OF WINGWALL.

⊡ VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING


10/11/2022
PENTABLE:BRReou_shd_util.tbl

8

8

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
SOUTH ABUTMENT			SHEET 4 OF 19



PILE LAYOUT

VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING

FOR PILE SPLICE DETAIL SEE SHEET 2.

10/11/2022
PENTABLE:RReou_shd_util.tbl


8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY	CLP	PLANS CK'D.	AEB
SOUTH ABUTMENT PILE LAYOUT			SHEET 5 OF 19

ORIGINAL PLANS PREPARED BY

AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com



ELEVATION - WING 1



SECTION D

- ⊕ 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
- OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
- ⊞ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.


4/25/2022 PENTABLE:BRRedu_shd_util.tbl

8


8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
SOUTH ABUTMENT WING 1 DETAILS			SHEET 6 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com



ELEVATION - WING 2



SECTION E

FOR CLARITY PARAPET NOT SHOWN.
FOR DETAILS SEE SHEET 18

- 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
- OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
- ▣ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.

4/25/2022 PENTABLE:BRedu_shd_util.tbl

8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
SOUTH ABUTMENT WING 2 DETAILS			SHEET 7 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com

BILL OF BARS


BAR NO.	COATED BAR	NO. REOD.	LENGTH	BENT BAR	BUNDLED	BAR SERIES	2,190* COATED	3,330* UNCOATED
LOCATION								
A401		8	28-0	X			BODY @ PILES	
A402		16	2-3				BODY @ PILES	
A503		67	14-2	X			BODY VERT.	
A604		11	26-11				BODY HORIZ.	
A605		11	29-10				BODY HORIZ.	
A806		14	12-11	X			BODY HORIZ. B.F. @ WINGS	
A607		7	17-10				BODY HORIZ. B.F. BTWN WINGS	
A608		7	20-9				BODY HORIZ. B.F. BTWN WINGS	
A409		3	7-11				BODY HORIZ.	
A410		3	9-10				BODY HORIZ.	
A511		16	5-1	X			BODY VERT.	
A412		40	3-3	X			BODY VERT. TOP	
A413		16	4-6	X			BODY VERT. TOP @ WINGS	
A414		2	6-9				BODY HORIZ. TOP F.F. @ WINGS	
A415		2	26-11				BODY HORIZ. TOP	
A416		2	29-10				BODY HORIZ. TOP	
A517	X	12	15-8	X			WING 1 VERT.	
A518	X	6	14-2				WING 1 HORIZ. F.F.	
A619	X	8	13-11				WING 1 HORIZ. B.F. & TOP	
A520	X	17	9-2	X			WING 1 VERT.	
A421	X	7	11-8				WING 1 HORIZ. E.F.	
A422	X	17	5-1	X			WING 1 VERT. TOP	
A623	X	2	11-8				WING 1 HORIZ. TOP E.F.	
A424	X	3	4-7				BODY VERT. @ END @ WING 1	
A525	X	12	15-8	X			WING 2 VERT.	
A526	X	6	14-2				WING 2 HORIZ. F.F.	
A627	X	8	13-11				WING 2 HORIZ. B.F. & TOP	
A528	X	17	9-2	X			WING 2 VERT.	
A429	X	7	11-8				WING 2 HORIZ. E.F.	
A430	X	17	5-1	X			WING 2 VERT. TOP	
A631	X	2	11-8				WING 2 HORIZ. TOP E.F.	
A432	X	3	4-7				BODY VERT. @ END @ WING 2	
A533	X	40	6-0	X			PARAPET VERT.	
A534	X	40	4-9	X			PARAPET VERT.	
A535	X	16	11-8				PARAPET HORIZ.	

BENDING DIMENSIONS ARE OUT TO OUT OF BARS.



SECTION A

◆ ABUTMENT TO BE SUPPORTED ON HP 10 x 42 STEEL PILING DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 110 TONS PER PILE. ESTIMATED LENGTH 65'-0". PRE-BORE PILES ADJACENT TO SANITARY LINE 15'-0".







SECTION G-G

* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 x 1-INCH SHEET METAL SCREWS.

RODENT SHIELD DETAIL



FOR LOCATION OF SECTION A SEE SHEET 4.

⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON THIS SHEET. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".


⊗ STEEL TROWEL TOP SURFACE OF ABUTMENT. PLACE MULTIPLE LAYERS OF POLYETHYLENE SHEETS OVER ENTIRE ABUTMENT TOP BEFORE PLACING SUPERSTRUCTURE. TOTAL THICKNESS OF SHEETS SHALL BE AT LEAST 0.03".

FOR PILE SPLICE DETAIL SEE SHEET 2.


4/25/2022 PENTABLE:BRReou_shd_ufl.tbi

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY CLP		PLANS CK'D. AEB	
SOUTH ABUTMENT DETAILS & BILL OF BARS			SHEET 8 OF 19


NOTE:
SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 1/8" BELOW SURFACE OF CONCRETE).




ELEVATION
(LOOKING NORTH)
FOR SECTION A SEE SHEET 13.



SECTION B



SECTION C



PLAN

▲ 3/4" CORK FILLER ON VERTICAL FACE ONLY.

⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".

⊞ VERTICAL 18" RUBBERIZED MEMBRANE WATERPROOFING TO EXTEND FROM BRIDGE SEAT TO TOP OF WINGWALL.

⊞ VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING


10/11/2022 PENTABLE:BRReou_shd_util.tbl

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
NORTH ABUTMENT			SHEET 9 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com



PILE LAYOUT

▨ VERT. CONST. JT. - KEYWAY FORMED BY A SURFACED BEVELED 2" x 8". BEVEL EXPOSED EDGES 3/4". FOR ALTERNATE CONST. JT. DETAILS SEE SHEET 14. SEAL JOINT AT BACK FACE WITH 18" RUBBERIZED MEMBRANE WATERPROOFING
 FOR PILE SPlice DETAIL SEE SHEET 2.

10/11/2022 PENTABLE:BRReou_shd_util.tbl

8



8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY	CLP	PLANS CK'D.	AEB
NORTH ABUTMENT PILE LAYOUT			SHEET 10 OF 19

ORIGINAL PLANS PREPARED BY

AYRES

3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com



- ⊕ 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
- OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
- ⊞ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.



4/25/2022 PENTABLE:BRRedu_shd_util.tbl

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
NORTH ABUTMENT WING 3 DETAILS			SHEET 11 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com



FOR CLARITY PARAPET NOT SHOWN.
FOR DETAILS SEE SHEET 18

- 3/4" "V" GROOVE ON FRONT FACE OF WINGWALL. ONLY REQUIRED IF OPTIONAL CONSTRUCTION JOINT IS USED.
- OPT. CONST. JOINT FORMED BY A BEVELED 2" x 6" KEYWAY WITH MEMBRANE ON BACKFACE.
- ▣ 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HOIRZONTAL AND VERTICAL JOINTS ON BACKFACE.

4/25/2022 PENTABLE:BRedu_shd_util.tbl

8


8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
ORIGINAL PLANS PREPARED BY AYRES 3433 Oakwood Hills Parkway Equ Claire, WI 54701 www.AyresAssociates.com			NORTH ABUTMENT WING 4 DETAILS
			SHEET 12 OF 19

BILL OF BARS





BAR NO.	COATED BAR	NO. REQ'D.	LENGTH	BENT BAR	BUNDLED	BAR SERIES	2,200* COATED	3,330* UNCOATED	LOCATION
B401		8	28-0	X					BODY @ PILES
B402		16	2-3						BODY @ PILES
B503		67	14-2	X					BODY VERT.
B604		11	26-11						BODY HORIZ.
B605		11	29-10						BODY HORIZ.
B806		14	12-11	X					BODY HORIZ. B.F. @ WINGS
B607		7	17-10						BODY HORIZ. B.F. BTWN WINGS
B608		7	20-9						BODY HORIZ. B.F. BTWN WINGS
B409		3	7-11						BODY HORIZ.
B410		3	9-10						BODY HORIZ.
B511		16	5-1	X					BODY VERT.
B412		40	3-3	X					BODY VERT. TOP
B413		16	4-6	X					BODY VERT. TOP @ WINGS
B414		2	6-9						BODY HORIZ. TOP F.F. @ WINGS
B415		2	26-11						BODY HORIZ. TOP
B416		2	29-10						BODY HORIZ. TOP
B517	X	12	15-8	X					WING 3 VERT.
B518	X	6	14-2						WING 3 HORIZ. F.F.
B619	X	8	13-11						WING 3 HORIZ. B.F. & TOP
B520	X	17	9-8	X					WING 3 VERT.
B421	X	7	11-8						WING 3 HORIZ. E.F.
B422	X	17	5-1	X					WING 3 VERT. TOP
B623	X	2	11-8						WING 3 HORIZ. TOP E.F.
B424	X	3	4-7						BODY VERT. @ END @ WING 3
B525	X	12	15-8	X					WING 4 VERT.
B526	X	6	14-2						WING 4 HORIZ. F.F.
B627	X	8	13-11						WING 4 HORIZ. B.F. & TOP
B528	X	17	9-8	X					WING 4 VERT.
B429	X	7	11-8						WING 4 HORIZ. E.F.
B430	X	17	5-1	X					WING 4 VERT. TOP
B631	X	2	11-8						WING 4 HORIZ. TOP E.F.
B432	X	3	4-7						BODY VERT. @ END @ WING 4
B533	X	40	6-0	X					PARAPET VERT.
B534	X	40	4-9	X					PARAPET VERT.
B535	X	16	11-8						PARAPET HORIZ.

BENDING DIMENSIONS ARE OUT TO OUT OF BARS.



◆ ABUTMENT TO BE SUPPORTED ON HP 10 x 42 STEEL PILING DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 110 TONS PER PILE. ESTIMATED LENGTH 65'-0". PRE-BORE PILES ADJACENT TO SANITARY LINE 15'-0".

ALL HORIZONTAL BARS IN BODY ARE B604, B605 BARS UNLESS SHOWN OTHERWISE.



FOR LOCATION OF SECTION A SEE SHEET 9.

⊖ PIPE UNDERDRAIN WRAPPED 6-INCH. SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN AS DETAILED ON SHEET 8. RODENT SHIELD TO BE INCIDENTAL TO BID PRICE OF "PIPE UNDERDRAIN WRAPPED 6-INCH".


⊗ STEEL TROWEL TOP SURFACE OF ABUTMENT. PLACE MULTIPLE LAYERS OF POLYETHYLENE SHEETS OVER ENTIRE ABUTMENT TOP BEFORE PLACING SUPERSTRUCTURE. TOTAL THICKNESS OF SHEETS SHALL BE AT LEAST 0.03".

FOR PILE SPLICE DETAIL SEE SHEET 2.

4/25/2022 PENTABLE:BRReou_shd_util.tbl

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
NORTH ABUTMENT DETAILS & BILL OF BARS			SHEET 13 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equi Claire, WI 54701
www.AyresAssociates.com



ALTERNATE CONSTRUCTION JOINT AT ABUTMENT

NOTES

PARTIAL ZINC OR PLASTIC BULKHEAD MAY BE USED AS ALTERNATE CONSTRUCTION JOINT, WITH THE PERMISSION OF THE ENGINEER, AT THE CONTRACTOR'S EXPENSE.

VERTICAL CONSTRUCTION JOINT KEYWAY IS NOT REQUIRED WHEN USING ALTERNATE CONSTRUCTION JOINT.

CARE IS TO BE USED IN CASTING CONCRETE AROUND BULKHEAD TO PREVENT DISLOCATION OR MISALIGNMENT OF THE BULKHEAD.

① USE A JOINT TOOL TO CONSTRUCT A CONTRACTION JOINT APPROXIMATELY 1/2" DEEP.


4/25/2022
PENTABLE:BRedu_shd_util.tbl

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
ALTERNATE CONSTRUCTION JOINT			SHEET 14 OF 19



ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com



△ ± 0.5% CONSTRUCTION TOLERANCE IN SIDEWALK CROSS SLOPE. THE SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2% WITHOUT PRIOR APPROVAL FROM THE ENGINEER.

☑ CONST. JOINT - STRIKE OFF AS SHOWN AND LEAVE ROUGH. FOR DECK POUR, MATCH BRIDGE X-SLOPE.

☑ 3/4" V-GROOVE. EXTEND V-GROOVE TO 6" FROM FRONT FACE OF ABUTMENTS - TYP.



TYPICAL SECTION THRU SIDEWALK

PART LONGITUDINAL SECTION

☑ 18" RUBBERIZED MEMBRANE WATERPROOFING


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
SUPERSTRUCTURE			SHEET 15 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equi Claire, WI 54701
www.AyresAssociates.com

4/25/2022 PENTABLE:BRRedu_shd_u.tif.tbi

8

8



PLAN

4/25/2022
PENTABLE:BRRedu_shd_util.tbl

8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
SUPERSTRUCTURE PLAN			SHEET 16 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com

BILL OF BARS

BAR NO.	COATED BAR	NO. REQ'D.	LENGTH	BENT BAR	BUNDLE	BAR SERIES	22,780* COATED
							LOCATION
S401	X	80	3-3	X			SLAB @ ABUT. NOTCH
S402	X	4	39-4				SLAB @ ABUT. NOTCH
S503	X	110	5-10	X			SLAB @ ABUT.
S504	X	110	3-4	X			SLAB @ ABUT.
S905	X	109	29-7				SLAB LONG. BOT.
S506	X	45	53-10				SLAB TRANS. BOT.
S507	X	35	53-10				SLAB TRANS. TOP
S508	X	55	34-2				SLAB LONG. TOP
S409	X	140	3-4	X			SLAB @ SDWK. @ EDGE OF SLAB
S410	X	140	3-1	X			SLAB @ SDWK. @ CURB
S411	X	20	34-2				SDWK. LONG. TOP
S512	X	210	7-3	X			SDWK. TRANS. TOP
S513	X	86	4-4	X			SLAB @ PARAPET VERT.
S514	X	86	4-9	X			SLAB @ PARAPET VERT.
S515	X	16	34-2				PARAPET HORIZ.



BENDING DIMENSIONS ARE OUT TO OUT OF BARS.



CAMBER AND SLAB THICKNESS DIAGRAM

CAMBER SHOWN IS BASED ON 3 TIMES DEAD LOAD DEFLECTION.

CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION AND FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT.



S503

TOP OF DECK ELEVATIONS

LOCATION	℄ OF S. ABUT.	0.1 PT	0.2 PT	0.3 PT	0.4 PT	0.5 PT	0.6 PT	0.7 PT	0.8 PT	0.9 PT	℄ OF N. ABUT.
W. EDGE OF SLAB	636.16	636.22	636.27	636.33	636.39	636.45	636.51	636.57	636.64	636.70	636.76
E. EDGE OF SIDEWALK	636.30	636.36	636.42	636.47	636.53	636.59	636.65	636.72	636.78	636.84	636.90
℄ OF CHANTEL STREET	636.70	636.76	636.82	636.87	636.93	636.99	637.05	637.12	637.18	637.24	637.30
W. EDGE OF SIDEWALK	636.30	636.36	636.42	636.47	636.53	636.59	636.65	636.72	636.78	636.84	636.90
E. EDGE OF SLAB	636.16	636.22	636.27	636.33	636.39	636.45	636.51	636.57	636.64	636.70	636.76

ELEVATIONS SHOWN ARE FINISHED DECK AND DO NOT INCLUDE ALLOWANCES OF DEAD LOAD DEFLECTION AND FUTURE CREEP.


SURVEY TOP OF SLAB ELEVATIONS

LOCATION	℄ OF S. ABUT.	5/10 PTS.	℄ OF N. ABUT.
W. GUTTER			
℄ OF STRUCTURE			
E. GUTTER			

PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF DECK ELEVATIONS AT THE ℄ OF ABUTMENTS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR ℄. RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.

TO DETERMINE FALSEWORK ELEVATION AT EDGE OF SLAB, CROWN OR REFERENCE LINE, FOLLOW THIS PROCEDURE:


- TOP OF SLAB ELEVATION AT FINAL GRADE
- MINUS..... SLAB THICKNESS
- PLUS..... CAMBER
- PLUS..... FORM SETTLEMENT/DEFLECTION DUE TO PLACEMENT OF SLAB CONCRETE (TO BE COMPUTED BY THE CONTRACTOR)
- EQUALS = TOP OF SLAB FALSEWORK ELEVATION




DETAIL OF ANCHOR ASSEMBLY

NOTE: HEX HEAD CAP SCREWS & WASHERS TO BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 CLASS C.


ASSEMBLY SHALL BE BID ITEM "ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD", EACH.




S504




S409, S410



S512



S513




S514

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY CLP		PLANS CK'D. AEB	
SUPERSTRUCTURE DETAILS AND BILL OF BARS			SHEET 17 OF 19


ORIGINAL PLANS PREPARED BY



3433 Oakwood Hills Parkway
Eau Claire, WI 54701
www.AyresAssociates.com




PLAN OF PARAPET




AT ABUTMENTS

INSIDE ELEVATION OF PARAPET



SECTION A-A



OUTSIDE FACE OF PARAPET








4/25/2022 PENTABLE:BRedu_shd_util.tbl

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
COMBINATION RAIL TYPE "C2"			SHEET 18 OF 19

ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
Equ Claire, WI 54701
www.AyresAssociates.com



LEGEND

- 1A PLATE 5/8" X 6" X 8" WITH 3/4" X 1/2" SLOTTED HOLES.
- 1C PLATE 5/8" X 8" X 1'-1" WITH 3/4" X 1/2" SLOTTED HOLES.
- 1D PLATE 5/8" X 8" X 1'-6" WITH 3/4" X 1/2" SLOTTED HOLES.
- 2A 1/4" X 5" X 7" ANCHOR PLATE WITH 1/16" DIA. HOLES FOR THR'D. RODS NO. 3.
- 2C 1/4" X 2 1/2" X 7 1/4" ANCHOR PLATE WITH 1/16" DIA. HOLES FOR THR'D. RODS NO. 3.
- 3 5/8" DIA. X 9" LONG, TYPE 316 STAINLESS STEEL THREADED RODS (MIN. TENSILE STRENGTH = 70 KSI) WITH NUT AND WASHERS OF SAME ALLOY GROUP. ALTERNATIVE ANCHORAGE: CONCRETE ADHESIVE ANCHORS 3/8"-INCH. EMBED 7" IN CONCRETE FOR RAIL POSTS. EMBED 5" IN CONCRETE FOR END RAILS. ADHESIVE ANCHORS SHALL CONFORM TO SECTION 502.2.12 OF THE STANDARD SPECIFICATIONS.
- 4A STRUCTURAL TUBING 3" X 1/2" X 3/16". PLACE VERTICAL. WELD TO NO. 1 & 5.
- 5A STRUCTURAL TUBING 3" X 1/2" X 3/16" RAILS. WELD TO NO. 1 & NO. 4. INSIDE OF TUBE TO BE PAINTED AT ALL FIELD ERECTION & EXPANSION JOINTS.
- 5C STRUCTURAL TUBING 2 1/2" DIA. (STANDARD SIZE) (2.875" O.D.). WELD TO NO. 1 & NO. 4. INSIDE OF TUBE TO BE PAINTED AT ALL FIELD ERECTION & EXPANSION JOINTS.
- 6A BAR 1" X 1" PICKETS. WELD TO NO. 5. PLACE VERTICAL.
- 9A RECTANGULAR SLEEVE FABRICATED FROM 3/16" PLATES. PROVIDE "SLIDING FIT".
- 9B CIRCULAR SLEEVE FABRICATED FROM STRUCTURAL TUBING 2" DIA. (STANDARD SIZE) (2.375" O.D.).
- 10A RECTANGULAR SLEEVE FABRICATED FROM 3/16" PLATES. (1'-4" @ FIELD ERECTION JTS.) (1'-4" @ STRIP SEAL JTS.)
- 10B CIRCULAR SLEEVE FABRICATED FROM STRUCTURAL TUBING 2" DIA. (STANDARD SIZE) (2.375" O.D.). (1'-4" @ FIELD ERECTION JTS.) (1'-4" @ STRIP SEAL EXP. JTS.)

RAILING NOTES

BID ITEM SHALL BE "RAILING STEEL TYPE C2", WHICH SHALL INCLUDE ALL STEEL ITEMS SHOWN.

POST BASE PLATES SHALL BE FLAT WITH ALL SURFACES SMOOTH AND FREE FROM WARP AND ALL EDGES SMOOTH, STRAIGHT AND VERTICAL. ALL PLATE CUTS SHALL BE MACHINE OR MACHINE FLAME CUTS.

ALL PLATES, BARS, AND RECTANGULAR SLEEVES SHALL CONFORM TO ASTM A709 GRADE 36. ALL STRUCTURAL TUBING SHALL CONFORM TO ASTM A500 GRADE B.

ANCHORAGES SHALL BE ACCURATELY PLACED TO PROVIDE CORRECT ALIGNMENT OF RAILING. SET NORMAL TO GRADE.

CUT BOTTOM OF POST TO MAKE POST VERTICAL IN BOTH TRANSVERSE AND LONGITUDINAL DIRECTION.

STEEL SHIMS SHALL BE PROVIDED & USED UNDER BASE PLATES WHERE REQUIRED FOR ALIGNMENT, AND SHALL BE GALVANIZED.

CAULK AROUND PERIMETER OF BASE PLATES, NO. 1, AND FILL BOLT SLOT OPENINGS IN SHIMS AND BASE PLATES WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER.

ALL JOINTS AND RECESSES IN CONCRETE PARAPET ARE TO BE VERTICAL.

ALL MATERIAL (EXCEPT NO. 3 & 12) SHALL BE GALVANIZED AFTER FABRICATION. PRIOR TO GALVANIZING, THE STEEL RAILING SHALL BE GIVEN A NO. 6 BLAST CLEANING PER SSPC SPECIFICATIONS, PAINT OVER GALVANIZING WITH AN APPROVED TIE COAT AND TOP COAT AS SPECIFIED IN THE CONTRACT DOCUMENTS. THE RAILING SHALL BE PAINTED AMS STD. COLOR NO. 27038.

VENT HOLES SHALL BE DRILLED IN POST AND RAIL MEMBERS AS REQUIRED TO FACILITATE GALVANIZING AND DRAINAGE.





RAILING SHALL BE FABRICATED IN LENGTHS THAT INCLUDE 3 OR 4 POSTS.

TOUCH-UP PAINTING TO BE DONE AT COMPLETION OF STEEL RAILING INSTALLATION TO THE SATISFACTION OF THE ENGINEER AT NO EXTRA COST.

4/25/2022 PENTABLE:BRRequ_shd_util.tbl

8

8



ORIGINAL PLANS PREPARED BY
AYRES 3433 Oakwood Hills Parkway
 Eau Claire, WI 54701
 www.AyresAssociates.com


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-5-474			
DRAWN BY		CLP	PLANS CK'D. AEB
COMBINATION RAIL TYPE "C2" DETAILS			SHEET 19 OF 19

EARTHWORK-CHANTEL ST


STATION	AREA (SF)			INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)		
	CUT	UNUSABLE PAVEMENT MATERIAL	FILL	CUT	UNUSABLE PAVEMENT MATERIAL	FILL	CUT	EXPANDED FILL	MASS ORDINATE
				NOTE 1	NOTE 2	NOTE 3	NOTE 1		NOTE 8
09+50	63.93	18.63	4.44	0	0	0	0	0	0
09+75	67.70	18.63	0.41	61	17	2	61	3	41
09+84	67.70	18.63	0.41	23	6	0	84	3	58
B-05-0474									
10+18	64.93	18.63	0.01	0	0	0	84	3	58
10+25	64.93	18.63	0.01	17	5	0	101	3	70
10+50	68.69	18.63	0.60	62	17	0	163	3	115

163 45 2

Notes:	
1 - Cut	Cut includes Salvaged/Unusable Pavement material
2 - Salvaged/Unusable Pavement Material	This does not show up in cross sections
3 - Fill	Does not include Unusable Pavement Exc volume
8 - Mass Ordinate	Cut - Unusable Pavement Material - (Fill * Fill Factor)



PROJECT NO: 4987-02-78 HWY: CHANTEL STREET COUNTY: BROWN CROSS SECTIONS: CHANTEL STREET SHEET 9



9

9

PROJECT NO: 4987-02-78 HWY: CHANTEL STREET COUNTY: BROWN CROSS SECTIONS: CHANTEL STREET SHEET E

FILE NAME : I:\45\450509 CHANTEL ST\C3D\SHEETSP\LAN\090201-XS.DWG PLOT DATE : 10/14/2022 10:02 AM PLOT BY : SCHAITEL, RYAN PLOT NAME : PLOT SCALE : 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>