Wisconsin Department of Transportation

Division of Transportation Systems Development
Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

March 8, 2023

NOTICE TO ALL CONTRACTORS:

Proposal #04: 1661-09-72, WISC 2023270
Prairie du Chien - Fennimore
South Town Ln/Selch Rd Intersection
USH 18
Crawford County

Letting of March 14, 2023

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
209.2500	Backfill Granular Grade 2	Ton	290	-290	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
29	Miscellaneous Quantities (Aggregate summary table updated to reflect bid item removal, as item is incidental to storm sewer pipe.)

Schedule of Items
Attached, dated March 8, 2023, are the revised Schedule of Items Pages 1 – 8.

Plan Sheets
The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 29

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

3

PREPARE FOUNDATION FOR CONCRETE PAVEMENT

CATEGORY	LOCATION	211.0201.01 PREPARE FOUNDATION FOR CONCRETE PAVEMENT (PROJECT) (01. 1661-09-72) EACH	REMARKS
0010	PROJECT 1661-09-72	1	
	TOTAL 0010	1	

FINISHING ROADWAY

CATEGORY	LOCATION	213.0100.01 FINISHING ROADWAY (PROJECT) (01. 1661-09-72) EACH	REMARKS
0010	PROJECT 1661-09-72	1	
	TOTAL 0010	1	

AGGREGATE SUMMARY

CATEGORY	STA - STA	LOCATION	305.0110 BASE AGGREGATE DENSE 3/4-INCH TON	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH TON	REMARKS
0010	193+59 'EB' - 194+99 'EB'	LT	-	100	
0010	194+96 'EB'	LT	5	-	NW CURB RAMP
0010	196+06 'EB'	RT	10	-	SW CURB RAMPS
0010	196+10 'EB'	RT	15	-	SE CURB RAMP
0010	196+12 'EB' - 197+20 'EB'	LT & RT	-	80	
		TOTAL 0010	30	180	

CONCRETE PAVEMENT SUMMARY

CATEGORY	STATION	TO	STATION	LOCATION	415.1100 CONCRETE PAVEMENT HES 10-INCH SY	416.0610 DRILLED TIE BARS EACH	416.0620 DRILLED DOWEL BARS EACH	REMARKS
0010	193+59 E'B'	-	194+99 'EB'	LT	235	140	25	
0010	194+74 'EB'	-	194+99 'EB'	LT	30	20	20	
0010	196+12 'EB'	-	197+23 'EB'	LT	175	100	20	
0010	196+12 'EB'	-	196+36 'EB'	RT	30	20	20	
				TOTAL 0010	470	280	85	

TEMPORARY DRAINAGE

CATEGORY	STATION	TO	STATION	LOCATION	520.2024 CULVERT PIPE TEMPORARY 24-INCH LF	REMARKS
0010	196+05 'EB'	-	196+88 'EB'	RT	85	
				TOTAL 0010	85	

Addendum No. 01
ID 1661-09-72
Revised Sheet 29
March 8. 2023

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	370.000 SY	_____._____	_____._____
0004	204.0110 Removing Asphaltic Surface	15.000 SY	_____._____	_____._____
0006	204.0150 Removing Curb & Gutter	560.000 LF	_____._____	_____._____
0008	204.0155 Removing Concrete Sidewalk	155.000 SY	_____._____	_____._____
0010	204.0195 Removing Concrete Bases	4.000 EACH	_____._____	_____._____
0012	204.0220 Removing Inlets	3.000 EACH	_____._____	_____._____
0014	204.0245 Removing Storm Sewer (size) 01. 12-Inch	108.000 LF	_____._____	_____._____
0016	204.0245 Removing Storm Sewer (size) 02. 15-Inch	8.000 LF	_____._____	_____._____
0018	204.9060.S Removing (item description) 01. Traffic Signals (USH 18 & S Town Ln/Selch Rd)	1.000 EACH	_____._____	_____._____
0022	211.0201 Prepare Foundation for Concrete Pavement (project) 01. 1661-09-72	1.000 EACH	_____._____	_____._____
0024	213.0100 Finishing Roadway (project) 01. 1661-09-72	1.000 EACH	_____._____	_____._____
0026	305.0110 Base Aggregate Dense 3/4-Inch	30.000 TON	_____._____	_____._____
0028	305.0120 Base Aggregate Dense 1 1/4-Inch	180.000 TON	_____._____	_____._____
0030	415.1100 Concrete Pavement HES 10-Inch	470.000 SY	_____._____	_____._____
0032	416.0610 Drilled Tie Bars	280.000 EACH	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	416.0620 Drilled Dowel Bars	85.000 EACH	_____._____	_____._____
0036	520.2024 Culvert Pipe Temporary 24-Inch	85.000 LF	_____._____	_____._____
0038	520.8000 Concrete Collars for Pipe	3.000 EACH	_____._____	_____._____
0040	601.0413 Concrete Curb & Gutter 6-Inch Sloped 30-Inch Type G	85.000 LF	_____._____	_____._____
0042	601.0600 Concrete Curb Pedestrian	30.000 LF	_____._____	_____._____
0044	602.0405 Concrete Sidewalk 4-Inch	1,040.000 SF	_____._____	_____._____
0046	602.0505 Curb Ramp Detectable Warning Field Yellow	20.000 SF	_____._____	_____._____
0048	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	65.000 SF	_____._____	_____._____
0050	602.2400 Concrete Safety Islands	665.000 SF	_____._____	_____._____
0052	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	108.000 LF	_____._____	_____._____
0054	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	8.000 LF	_____._____	_____._____
0056	611.0606 Inlet Covers Type B	2.000 EACH	_____._____	_____._____
0058	611.2005 Manholes 5-FT Diameter	1.000 EACH	_____._____	_____._____
0060	611.3225 Inlets 2x2.5-FT	1.000 EACH	_____._____	_____._____
0062	618.0100 Maintenance And Repair of Haul Roads (project) 01. 1991-09-72	1.000 EACH	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	619.1000 Mobilization	1.000 EACH	_____._____	_____._____
0066	624.0100 Water	10.000 MGAL	_____._____	_____._____
0068	625.0100 Topsoil	520.000 SY	_____._____	_____._____
0070	628.1504 Silt Fence	285.000 LF	_____._____	_____._____
0072	628.1520 Silt Fence Maintenance	285.000 LF	_____._____	_____._____
0074	628.1905 Mobilizations Erosion Control	1.000 EACH	_____._____	_____._____
0076	628.1910 Mobilizations Emergency Erosion Control	1.000 EACH	_____._____	_____._____
0078	628.2002 Erosion Mat Class I Type A	3,550.000 SY	_____._____	_____._____
0080	628.7015 Inlet Protection Type C	9.000 EACH	_____._____	_____._____
0082	628.7555 Culvert Pipe Checks	6.000 EACH	_____._____	_____._____
0084	629.0210 Fertilizer Type B	9.000 CWT	_____._____	_____._____
0086	630.0140 Seeding Mixture No. 40	11.000 LB	_____._____	_____._____
0088	630.0200 Seeding Temporary	16.000 LB	_____._____	_____._____
0090	630.0500 Seed Water	2.000 MGAL	_____._____	_____._____
0092	633.5350 Markers Permanent Flexible	6.000 EACH	_____._____	_____._____
0094	638.2102 Moving Signs Type II	4.000 EACH	_____._____	_____._____
0096	638.2602 Removing Signs Type II	8.000 EACH	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	642.5001 Field Office Type B	1.000 EACH	_____._____	_____._____
0100	643.0300 Traffic Control Drums	2,068.000 DAY	_____._____	_____._____
0102	643.0420 Traffic Control Barricades Type III	114.000 DAY	_____._____	_____._____
0104	643.0500 Traffic Control Flexible Tubular Marker Posts	261.000 EACH	_____._____	_____._____
0106	643.0705 Traffic Control Warning Lights Type A	244.000 DAY	_____._____	_____._____
0108	643.0715 Traffic Control Warning Lights Type C	402.000 DAY	_____._____	_____._____
0110	643.0800 Traffic Control Arrow Boards	72.000 DAY	_____._____	_____._____
0112	643.0900 Traffic Control Signs	736.000 DAY	_____._____	_____._____
0114	643.1050 Traffic Control Signs PCMS	14.000 DAY	_____._____	_____._____
0116	643.3150 Temporary Marking Line Removable Tape 4-Inch	2,998.000 LF	_____._____	_____._____
0118	643.5000 Traffic Control	1.000 EACH	_____._____	_____._____
0120	644.1810 Temporary Pedestrian Barricade	181.000 LF	_____._____	_____._____
0122	646.1020 Marking Line Epoxy 4-Inch	865.000 LF	_____._____	_____._____
0124	646.3545 Marking Line Grooved Wet Ref Contrast Epoxy 8-Inch	480.000 LF	_____._____	_____._____
0126	646.5020 Marking Arrow Epoxy	4.000 EACH	_____._____	_____._____
0128	646.6120 Marking Stop Line Epoxy 18-Inch	82.000 LF	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0130	646.7120 Marking Diagonal Epoxy 12-Inch	35.000 LF	_____._____	_____._____
0132	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	290.000 LF	_____._____	_____._____
0134	646.8120 Marking Curb Epoxy	30.000 LF	_____._____	_____._____
0136	646.9010 Marking Removal Line Water Blasting 4-Inch	1,230.000 LF	_____._____	_____._____
0138	650.4000 Construction Staking Storm Sewer	2.000 EACH	_____._____	_____._____
0140	650.7000 Construction Staking Concrete Pavement	248.000 LF	_____._____	_____._____
0142	650.8501 Construction Staking Electrical Installations (project) 01. 1661-09-72	1.000 EACH	_____._____	_____._____
0144	650.9000 Construction Staking Curb Ramps	4.000 EACH	_____._____	_____._____
0146	650.9500 Construction Staking Sidewalk (project) 01. 1661-09-72	1.000 EACH	_____._____	_____._____
0148	650.9911 Construction Staking Supplemental Control (project) 01. 1661-09-72	1.000 EACH	_____._____	_____._____
0150	650.9920 Construction Staking Slope Stakes	136.000 LF	_____._____	_____._____
0152	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	11.000 LF	_____._____	_____._____
0154	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	532.000 LF	_____._____	_____._____
0156	652.0615 Conduit Special 3-Inch	451.000 LF	_____._____	_____._____
0158	653.0164 Pull Boxes Non-Conductive 24x42-Inch	6.000 EACH	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0160	653.0900 Adjusting Pull Boxes	8.000 EACH	_____._____	_____._____
0162	653.0905 Removing Pull Boxes	2.000 EACH	_____._____	_____._____
0164	654.0101 Concrete Bases Type 1	1.000 EACH	_____._____	_____._____
0166	654.0113 Concrete Bases Type 13	2.000 EACH	_____._____	_____._____
0168	655.0210 Cable Traffic Signal 3-14 AWG	15.000 LF	_____._____	_____._____
0170	655.0230 Cable Traffic Signal 5-14 AWG	1,252.000 LF	_____._____	_____._____
0172	655.0260 Cable Traffic Signal 12-14 AWG	882.000 LF	_____._____	_____._____
0174	655.0305 Cable Type UF 2-12 AWG Grounded	1,129.000 LF	_____._____	_____._____
0176	655.0515 Electrical Wire Traffic Signals 10 AWG	1,441.000 LF	_____._____	_____._____
0178	655.0610 Electrical Wire Lighting 12 AWG	318.000 LF	_____._____	_____._____
0180	655.0700 Loop Detector Lead In Cable	910.000 LF	_____._____	_____._____
0182	657.0100 Pedestal Bases	1.000 EACH	_____._____	_____._____
0184	657.0361 Poles Type 13-Over Height	2.000 EACH	_____._____	_____._____
0186	657.0425 Traffic Signal Standards Aluminum 15-FT	2.000 EACH	_____._____	_____._____
0188	657.0430 Traffic Signal Standards Aluminum 10-FT	1.000 EACH	_____._____	_____._____
0190	657.0545 Monotube Arms 45-FT	1.000 EACH	_____._____	_____._____
0192	657.0555 Monotube Arms 55-FT	1.000 EACH	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0194	657.0815 Luminaire Arms Steel 15-FT	2.000 EACH	_____._____	_____._____
0196	658.0173 Traffic Signal Face 3S 12-Inch	4.000 EACH	_____._____	_____._____
0198	658.0174 Traffic Signal Face 4S 12-Inch	4.000 EACH	_____._____	_____._____
0200	658.0416 Pedestrian Signal Face 16-Inch	1.000 EACH	_____._____	_____._____
0202	658.0500 Pedestrian Push Buttons	1.000 EACH	_____._____	_____._____
0204	658.5070 Signal Mounting Hardware (location) 01. 1661-09-72	1.000 EACH	_____._____	_____._____
0206	659.1125 Luminaires Utility LED C	2.000 EACH	_____._____	_____._____
0208	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	7.000 EACH	_____._____	_____._____
0210	690.0150 Sawing Asphalt	35.000 LF	_____._____	_____._____
0212	690.0250 Sawing Concrete	720.000 LF	_____._____	_____._____
0214	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0216	SPV.0060 Special 01. Retroreflective Backplate 3S	4.000 EACH	_____._____	_____._____
0218	SPV.0060 Special 02. Retroreflective Backplate 4S	4.000 EACH	_____._____	_____._____
0220	SPV.0060 Special 03. Adjusting Concrete Bases	9.000 EACH	_____._____	_____._____
0222	SPV.0060 Special 04. Temporary Multi-Use Path	1.000 EACH	_____._____	_____._____
0224	SPV.0090 Special 01. Install State-Supplied Non-Intrusive Detection Cable	495.000 LF	_____._____	_____._____

Proposal ID: 20230314004 Project(s): 1661-09-72

Federal ID(s): WISC 2023270

Section: 0001 Total: _____._____

Total Bid: _____._____