



## Wisconsin Department of Transportation

---

September 7, 2023

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### **NOTICE TO ALL CONTRACTORS:**

**Proposal #14: 1021-03-71, WISC 2023619**  
Eau Claire – Osseo  
CTH J Bridge B-18-0212 (West Bound)  
IH 94  
Eau Claire County

**1021-03-72 , WISC 2023620**  
Eau Claire – Osseo  
CTH D Bridge B-18-0213 (East Bound)  
IH 94  
Eau Claire County

**1021-03-73, WISC 2023621**  
Eau Claire – Osseo  
CTH J Bridge B-18-0211 (East Bound)  
IH 94  
Eau Claire County

**1022-09-74, WISC 2023622**  
Eau Claire – Osseo  
CTH D Bridge B-18-0214 (West Bound)  
IH 94  
Eau Claire County

**1022-09-78, WISC 2023623**  
Eau Claire – Osseo  
USH 53 to Mallard Road (EB & WB)  
IH 94  
Eau Claire County

### **Letting of September 12, 2023**

This is Addendum No. 03, which provides for the following:

**Special Provisions:**

<b>Revised Special Provisions</b>	
Article No.	Description
27	Select Borrow, Item 208.1100
36	Temporary Structure Station 618'S2 WB'+75

<b>Added Special Provisions</b>	
Article No.	Description
76	Backfill Granular Grade 1

**Schedule of Items:**

<b>Revised Bid Item Quantities</b>					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
208.1100	Select Borrow	CY	29,413	-26,700	2,713

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
324	Changed items totals and subtotals in the earthwork summary table in MQ sheets

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 03**  
**1021-03-71/72/73 & 1022-09-74/78**  
**September 7, 2023**

**Special Provisions**

**27. Select Borrow, Item 208.1100.**

*Replace entire section titled B Materials with the following:*

**B Materials**

Furnish and use material that consists of granular material meeting the following requirements: No more than 8% P-200 of that portion of the #4 sieve. Allowable materials include natural sand, natural gravel, produced sand, foundry sand, produced gravel, fly ash, Portland cement, and other broken or fragmented mineral materials. The designed mixture shall be self-leveling and shall be free of shrinkage after hardening. Design the mixture to reach a state of hardening such that it can support foot traffic in no more than 24 hours. Provide a mixture that also meets the following requirements.

<b>TEST</b>	<b>METHOD</b>	<b>VALUE</b>
Flow (inch)	ASTM D-6103	9 min
Compressive	ASTM D-6024	20-40 @ 14 days
Strength (psi)		40-80 @ 28 days
		80-120 @ 90 days

Chemical admixtures to control air content and setting time are allowable. Ten days before placement, furnish the engineer with a design mix detailing all components and their proportions in the mix.

**36. Temporary Structure Station 618'S2\_WB'+75.**

*After the following to the end of the article:*

Adjustments to the temporary profile are allowed to meet clearance requirements.

**76. Backfill Granular Grade 1.**

*Conform to standard spec 208 as modified in this special provision.*

**B Material**

Furnish and use material that consists of granular material meeting the following requirements: No more than 8% P-200 of that portion of the #4 sieve.

**Schedule of Items**

Attached, dated September 7, 2023, are the revised Schedule of Items Page 5.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 324

END OF ADDENDUM





Proposal Schedule of Items

Proposal ID: 20230912014 Project(s): 1021-03-71, 1021-03-72, 1021-03-73, 1022-09-74, 1022-09-78

Federal ID(s): WISC 2023623, WISC 2023619, WISC 2023620, WISC 2023621, WISC 2023622

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0110	208.0100 Borrow	84,698.000 CY	_____.	_____.
0112	208.1100 Select Borrow	2,713.000 CY	_____.	_____.
0114	209.0200.S Backfill Controlled Low Strength	387.000 CY	_____.	_____.
0116	209.1100 Backfill Granular Grade 1	26,700.000 CY	_____.	_____.
0118	210.1500 Backfill Structure Type A	2,605.000 TON	_____.	_____.
0120	210.2500 Backfill Structure Type B	6,272.000 TON	_____.	_____.
0122	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 1022-09-78	1.000 EACH	_____.	_____.
0124	211.0400 Prepare Foundation for Asphaltic Shoulders	25.000 STA	_____.	_____.
0126	213.0100 Finishing Roadway (project) 01. 1022-09-78	1.000 EACH	_____.	_____.
0128	213.0100 Finishing Roadway (project) 02. 1021-03-71	1.000 EACH	_____.	_____.
0130	213.0100 Finishing Roadway (project) 03. 1021-03-72	1.000 EACH	_____.	_____.
0132	213.0100 Finishing Roadway (project) 04. 1021-03-73	1.000 EACH	_____.	_____.
0134	213.0100 Finishing Roadway (project) 05. 1022-09-74	1.000 EACH	_____.	_____.

