



Wisconsin Department of Transportation

October 26, 2023

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #41: 7996-00-43, WISC 2023248
C Menomonie, CTH B
USH 12 to EB IH94 Ramps
CTH B
Dunn County**

Letting of November 14, 2023

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
658.0174	Traffic Signal Face 4S 12-Inch	Each	0	2	2

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
254	Miscellaneous Quantities (add the new bid item to the 'Faces' table)

Schedule of Items

Attached, dated October 26, 2023, are the revised Schedule of Items Page 14.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 254

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

CTH B & 3M DRIVE / 610TH AVENUE
DUNN COUNTY
CATEGORY 0010

POLES

SIGNAL BASE NO.	657.0100 PEDESTAL BASES EACH	657.0255* TRANSFORMER BASES BREAKAWAY 11 1/2-INCH BOLT CIRCLE EACH	657.0315 POLES TYPE 4 EACH	657.0347 POLES TYPE 9 SPECIAL EACH	657.0425 TRAFFIC SIGNAL STANDARDS ALUMINUM 15-FT EACH	657.0541 MONOTUBE ARMS 40-FT SPECIAL EACH	657.0609* LUMINAIRE ARMS SINGLE MEMBER 4-INCH CLAMP 6-FT EACH	659.1115 LUMINAIRES UTILITY LED A EACH
SB1	--	1	1	--	--	--	1	1
SB2	--	--	--	1	--	1	--	--
SB3	1	--	--	--	1	--	--	--
SB4	1	--	--	--	1	--	--	--
SB5	--	1	1	--	--	--	2	2
SB6	--	--	--	1	--	--	--	--
SB7	--	1	1	--	--	--	1	1
SB8	--	--	--	1	--	1	--	--
SB9	1	--	--	--	1	--	--	--
SB10	1	--	1	--	1	--	--	2
SB11	--	1	1	--	--	2	--	2
SB12	--	--	1	--	1	--	--	--
TOTAL	4	4	4	4	4	4	6	6

TRAFFIC SIGNAL CONTROLLER

LOCATION	SPV.0060.07 TRAFFIC SIGNAL CABINET AND CONTROLLER EACH
CTH B & 3M DRIVE / 610TH AVENUE	1
TOTAL	1

TEMPORARY TRAFFIC SIGNALS

LOCATION	661.0201.01 TEMPORARY TRAFFIC SIGNALS FOR INTERSECTIONS EACH
CTH B & 3M DRIVE / 610TH AVENUE	1
TOTAL	1

Addendum No. 01
ID 7996-00-43
Revised Sheet 254
October 26, 2023

FACES

SIGNAL HEAD NO.	SIGNAL BASE NO.	658.0173 TRAFFIC SIGNAL FACE 3S 12-INCH EACH	658.0174 TRAFFIC SIGNAL FACE 4S 12-INCH EACH
13	SB1	1	--
21	SB1	--	1
19	SB2	1	--
20	SB2	1	--
22	SB2	--	1
1	SB3	1	--
11	SB3	1	--
12	SB4	1	--
4	SB5	1	--
8	SB6	1	--
9	SB6	1	--
16	SB7	1	--
18	SB7	1	--
14	SB8	1	--
15	SB8	1	--
17	SB8	1	--
5	SB9	1	--
7	SB9	1	--
6	SB10	1	--
10	SB11	1	--
2	SB12	1	--
3	SB12	1	--
TOTAL		20	2

LEGEND

*ADDITIONAL QUANTITIES SHOWN ELSEWHERE.
^ FINAL LOCATION TO BE DETERMINED BY THE ENGINEER IN THE FIELD.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0004	204.0100 Removing Concrete Pavement	7,954.000 SY	_____.	_____.
0006	204.0110 Removing Asphaltic Surface	2,657.000 SY	_____.	_____.
0008	204.0150 Removing Curb & Gutter	11,833.000 LF	_____.	_____.
0010	204.0155 Removing Concrete Sidewalk	560.000 SY	_____.	_____.
0012	204.0195 Removing Concrete Bases	46.000 EACH	_____.	_____.
0014	204.0220 Removing Inlets	26.000 EACH	_____.	_____.
0016	204.0245 Removing Storm Sewer (size) 01. 12 Inch	448.000 LF	_____.	_____.
0018	204.0245 Removing Storm Sewer (size) 02. 15 Inch	250.000 LF	_____.	_____.
0020	204.0245 Removing Storm Sewer (size) 03. 18 Inch	603.000 LF	_____.	_____.
0022	204.0245 Removing Storm Sewer (size) 04. 24 Inch	132.000 LF	_____.	_____.
0024	204.9060.S Removing (item description) 01. Street Light Assembly	22.000 EACH	_____.	_____.
0026	204.9060.S Removing (item description) 02. Lighting Controls	1.000 EACH	_____.	_____.
0028	204.9060.S Removing (item description) 03. Removing Traffic Signals CTH B & 3M Drive/610th Avenue	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.9090.S Removing (item description) 01. Electrical Conductors From Existing Conduit	4,300.000 LF	_____.	_____.
0032	205.0100 Excavation Common	20,834.000 CY	_____.	_____.
0034	208.0100 Borrow	92.000 CY	_____.	_____.
0036	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 7996-00-43	1.000 EACH	_____.	_____.
0038	211.0400 Prepare Foundation for Asphaltic Shoulders	12.000 STA	_____.	_____.
0040	213.0100 Finishing Roadway (project) 01. 7996-00-43	1.000 EACH	_____.	_____.
0042	305.0110 Base Aggregate Dense 3/4-Inch	1,620.000 TON	_____.	_____.
0044	305.0120 Base Aggregate Dense 1 1/4-Inch	29,487.000 TON	_____.	_____.
0046	415.0090 Concrete Pavement 9-Inch	15,258.000 SY	_____.	_____.
0048	415.0100 Concrete Pavement 10-Inch	26,844.000 SY	_____.	_____.
0050	415.0210 Concrete Pavement Gaps	8.000 EACH	_____.	_____.
0052	415.1090 Concrete Pavement HES 9-Inch	2,246.000 SY	_____.	_____.
0054	415.1100 Concrete Pavement HES 10-Inch	3,345.000 SY	_____.	_____.
0056	416.0610 Drilled Tie Bars	252.000 EACH	_____.	_____.
0058	416.0620 Drilled Dowel Bars	60.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0060	455.0605 Tack Coat	189.000 GAL	_____.	_____.
0062	460.2000 Incentive Density HMA Pavement	850.000 DOL	1.00000	850.00
0064	460.5244 HMA Pavement 4 LT 58-34 S	1,324.000 TON	_____.	_____.
0066	465.0105 Asphaltic Surface	27.000 TON	_____.	_____.
0068	465.0125 Asphaltic Surface Temporary	716.000 TON	_____.	_____.
0070	465.0310 Asphaltic Curb	45.000 LF	_____.	_____.
0072	520.8000 Concrete Collars for Pipe	1.000 EACH	_____.	_____.
0074	521.6118 Culvert Pipe Corrugated Steel Aluminum Coated 18-Inch	38.000 LF	_____.	_____.
0076	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	4.000 LF	_____.	_____.
0078	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	1.000 EACH	_____.	_____.
0080	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	1.000 EACH	_____.	_____.
0082	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	12.000 EACH	_____.	_____.
0084	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	1.000 EACH	_____.	_____.
0086	524.0624 Apron Endwalls for Culvert Pipe Salvaged 24-Inch	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	525.0318 Apron Endwalls for Culvert Pipe Aluminum 18-Inch	2.000 EACH	_____.	_____.
0090	601.0411 Concrete Curb & Gutter 30-Inch Type D	531.000 LF	_____.	_____.
0092	601.0555 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type A	13,221.000 LF	_____.	_____.
0094	602.0405 Concrete Sidewalk 4-Inch	4,815.000 SF	_____.	_____.
0096	603.8000 Concrete Barrier Temporary Precast Delivered	62.000 LF	_____.	_____.
0098	603.8125 Concrete Barrier Temporary Precast Installed	62.000 LF	_____.	_____.
0100	603.8500 Anchoring Concrete Barrier Temporary Precast	62.000 LF	_____.	_____.
0102	606.0200 Riprap Medium	71.000 CY	_____.	_____.
0104	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	390.000 LF	_____.	_____.
0106	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	906.000 LF	_____.	_____.
0108	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	348.000 LF	_____.	_____.
0110	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	55.000 LF	_____.	_____.
0112	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	359.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0114	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	8.000 LF	_____.	_____.
0116	611.0627 Inlet Covers Type HM	32.000 EACH	_____.	_____.
0118	611.0636 Inlet Covers Type HM-S	12.000 EACH	_____.	_____.
0120	611.0642 Inlet Covers Type MS	2.000 EACH	_____.	_____.
0122	611.0651 Inlet Covers Type S	1.000 EACH	_____.	_____.
0124	611.3004 Inlets 4-FT Diameter	9.000 EACH	_____.	_____.
0126	611.3230 Inlets 2x3-FT	35.000 EACH	_____.	_____.
0128	611.3902 Inlets Median 2 Grate	2.000 EACH	_____.	_____.
0130	611.8110 Adjusting Manhole Covers	10.000 EACH	_____.	_____.
0132	611.8120.S Cover Plates Temporary	1.000 EACH	_____.	_____.
0134	611.9710 Salvaged Inlet Covers	2.000 EACH	_____.	_____.
0136	618.0100 Maintenance and Repair of Haul Roads (project) 01. 7996-00-43	1.000 EACH	_____.	_____.
0138	619.1000 Mobilization	1.000 EACH	_____.	_____.
0140	620.0300 Concrete Median Sloped Nose	506.000 SF	_____.	_____.
0142	624.0100 Water	294.000 MGAL	_____.	_____.
0144	625.0500 Salvaged Topsoil	34,447.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0146	627.0200 Mulching	33,548.000 SY	_____.	_____.
0148	628.1504 Silt Fence	9,157.000 LF	_____.	_____.
0150	628.1520 Silt Fence Maintenance	9,157.000 LF	_____.	_____.
0152	628.1905 Mobilizations Erosion Control	7.000 EACH	_____.	_____.
0154	628.1910 Mobilizations Emergency Erosion Control	6.000 EACH	_____.	_____.
0156	628.2004 Erosion Mat Class I Type B	898.000 SY	_____.	_____.
0158	628.7005 Inlet Protection Type A	58.000 EACH	_____.	_____.
0160	628.7015 Inlet Protection Type C	56.000 EACH	_____.	_____.
0162	628.7504 Temporary Ditch Checks	275.000 LF	_____.	_____.
0164	628.7555 Culvert Pipe Checks	8.000 EACH	_____.	_____.
0166	629.0210 Fertilizer Type B	22.000 CWT	_____.	_____.
0168	630.0120 Seeding Mixture No. 20	600.000 LB	_____.	_____.
0170	630.0130 Seeding Mixture No. 30	210.000 LB	_____.	_____.
0172	630.0200 Seeding Temporary	27.000 LB	_____.	_____.
0174	630.0500 Seed Water	384.000 MGAL	_____.	_____.
0176	633.5200 Markers Culvert End	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0178	634.0614 Posts Wood 4x6-Inch X 14-FT	30.000 EACH	_____.	_____.
0180	634.0616 Posts Wood 4x6-Inch X 16-FT	47.000 EACH	_____.	_____.
0182	634.0618 Posts Wood 4x6-Inch X 18-FT	3.000 EACH	_____.	_____.
0184	634.0620 Posts Wood 4x6-Inch X 20-FT	9.000 EACH	_____.	_____.
0186	634.0622 Posts Wood 4x6-Inch X 22-FT	1.000 EACH	_____.	_____.
0188	637.2210 Signs Type II Reflective H	1,273.000 SF	_____.	_____.
0190	637.2215 Signs Type II Reflective H Folding	40.000 SF	_____.	_____.
0192	637.2230 Signs Type II Reflective F	72.000 SF	_____.	_____.
0194	638.2102 Moving Signs Type II	7.000 EACH	_____.	_____.
0196	638.2602 Removing Signs Type II	103.000 EACH	_____.	_____.
0198	638.3000 Removing Small Sign Supports	72.000 EACH	_____.	_____.
0200	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0202	643.0300 Traffic Control Drums	63,512.000 DAY	_____.	_____.
0204	643.0420 Traffic Control Barricades Type III	9,739.000 DAY	_____.	_____.
0206	643.0500 Traffic Control Flexible Tubular Marker Posts	412.000 EACH	_____.	_____.
0208	643.0600 Traffic Control Flexible Tubular Marker Bases	358.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0210	643.0705 Traffic Control Warning Lights Type A	11,733.000 DAY	_____.	_____.
0212	643.0715 Traffic Control Warning Lights Type C	3,852.000 DAY	_____.	_____.
0214	643.0800 Traffic Control Arrow Boards	123.000 DAY	_____.	_____.
0216	643.0900 Traffic Control Signs	13,870.000 DAY	_____.	_____.
0218	643.1050 Traffic Control Signs PCMS	600.000 DAY	_____.	_____.
0220	643.3105 Temporary Marking Line Paint 4-Inch	28,605.000 LF	_____.	_____.
0222	643.3150 Temporary Marking Line Removable Tape 4-Inch	30,905.000 LF	_____.	_____.
0224	643.3205 Temporary Marking Line Paint 8-Inch	665.000 LF	_____.	_____.
0226	643.3250 Temporary Marking Line Removable Tape 8-Inch	1,285.000 LF	_____.	_____.
0228	643.3805 Temporary Marking Stop Line Paint 18-Inch	107.000 LF	_____.	_____.
0230	643.3850 Temporary Marking Stop Line Removable Tape 18-Inch	481.000 LF	_____.	_____.
0232	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0234	645.0120 Geotextile Type HR	215.000 SY	_____.	_____.
0236	646.2020 Marking Line Epoxy 6-Inch	13,883.000 LF	_____.	_____.
0238	646.2025 Marking Line Grooved Black Epoxy 6-Inch	6,740.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0240	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	19,657.000 LF	_____.	_____.
0242	646.4020 Marking Line Epoxy 10-Inch	3,305.000 LF	_____.	_____.
0244	646.5020 Marking Arrow Epoxy	28.000 EACH	_____.	_____.
0246	646.5120 Marking Word Epoxy	9.000 EACH	_____.	_____.
0248	646.6120 Marking Stop Line Epoxy 18-Inch	412.000 LF	_____.	_____.
0250	646.8120 Marking Curb Epoxy	505.000 LF	_____.	_____.
0252	646.8220 Marking Island Nose Epoxy	11.000 EACH	_____.	_____.
0254	646.9000 Marking Removal Line 4-Inch	3,674.000 LF	_____.	_____.
0256	646.9100 Marking Removal Line 8-Inch	200.000 LF	_____.	_____.
0258	650.4000 Construction Staking Storm Sewer	61.000 EACH	_____.	_____.
0260	650.4500 Construction Staking Subgrade	12,675.000 LF	_____.	_____.
0262	650.5000 Construction Staking Base	179.000 LF	_____.	_____.
0264	650.5500 Construction Staking Curb Gutter and Curb & Gutter	12,712.000 LF	_____.	_____.
0266	650.6000 Construction Staking Pipe Culverts	2.000 EACH	_____.	_____.
0268	650.7000 Construction Staking Concrete Pavement	12,496.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0270	650.8501 Construction Staking Electrical Installations (project) 01. 7996-00-43	1.000 EACH	_____.	_____.
0272	650.9911 Construction Staking Supplemental Control (project) 01. 7996-00-43	1.000 EACH	_____.	_____.
0274	650.9920 Construction Staking Slope Stakes	12,675.000 LF	_____.	_____.
0276	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	7,302.000 LF	_____.	_____.
0278	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	1,992.000 LF	_____.	_____.
0280	652.0800 Conduit Loop Detector	1,812.000 LF	_____.	_____.
0282	653.0135 Pull Boxes Steel 24x36-Inch	3.000 EACH	_____.	_____.
0284	653.0154 Pull Boxes Non-Conductive 24x36-Inch	8.000 EACH	_____.	_____.
0286	653.0164 Pull Boxes Non-Conductive 24x42-Inch	35.000 EACH	_____.	_____.
0288	653.0900 Adjusting Pull Boxes	5.000 EACH	_____.	_____.
0290	653.0905 Removing Pull Boxes	14.000 EACH	_____.	_____.
0292	654.0101 Concrete Bases Type 1	8.000 EACH	_____.	_____.
0294	654.0102 Concrete Bases Type 2	9.000 EACH	_____.	_____.
0296	654.0105 Concrete Bases Type 5	29.000 EACH	_____.	_____.
0298	654.0120 Concrete Bases Type 10-Special	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0300	654.0230 Concrete Control Cabinet Bases Type L30	1.000 EACH	_____.	_____.
0302	655.0230 Cable Traffic Signal 5-14 AWG	1,620.000 LF	_____.	_____.
0304	655.0240 Cable Traffic Signal 7-14 AWG	3,079.000 LF	_____.	_____.
0306	655.0260 Cable Traffic Signal 12-14 AWG	2,743.000 LF	_____.	_____.
0308	655.0305 Cable Type UF 2-12 AWG Grounded	734.000 LF	_____.	_____.
0310	655.0320 Cable Type UF 2-10 AWG Grounded	665.000 LF	_____.	_____.
0312	655.0515 Electrical Wire Traffic Signals 10 AWG	2,823.000 LF	_____.	_____.
0314	655.0610 Electrical Wire Lighting 12 AWG	7,505.000 LF	_____.	_____.
0316	655.0620 Electrical Wire Lighting 8 AWG	11,413.000 LF	_____.	_____.
0318	655.0625 Electrical Wire Lighting 6 AWG	18,722.000 LF	_____.	_____.
0320	655.0700 Loop Detector Lead In Cable	3,972.000 LF	_____.	_____.
0322	655.0800 Loop Detector Wire	5,962.000 LF	_____.	_____.
0324	655.0900 Traffic Signal EVP Detector Cable	1,135.000 LF	_____.	_____.
0326	656.0201 Electrical Service Meter Breaker Pedestal (location) 01. CB100	1.000 EACH	_____.	_____.
0328	656.0201 Electrical Service Meter Breaker Pedestal (location) 02. CB200	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 **Project(s):** 7996-00-43
Federal ID(s): WISC 2023248
SECTION: 0001 Contract Items
Alt Set ID: **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0330	657.0100 Pedestal Bases	4.000 EACH	_____.	_____.
0332	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	33.000 EACH	_____.	_____.
0334	657.0310 Poles Type 3	1.000 EACH	_____.	_____.
0336	657.0315 Poles Type 4	4.000 EACH	_____.	_____.
0338	657.0322 Poles Type 5-Aluminum	28.000 EACH	_____.	_____.
0340	657.0347 Poles Type 9-Special	4.000 EACH	_____.	_____.
0342	657.0425 Traffic Signal Standards Aluminum 15-FT	4.000 EACH	_____.	_____.
0344	657.0541 Monotube Arms 40-FT-Special	4.000 EACH	_____.	_____.
0346	657.0609 Luminaire Arms Single Member 4-Inch Clamp 6-FT	6.000 EACH	_____.	_____.
0348	657.0610 Luminaire Arms Single Member 4 1/2-Inch Clamp 6-FT	47.000 EACH	_____.	_____.
0350	657.0704 Luminaire Arms Truss Type 4-Inch Clamp 10-FT	1.000 EACH	_____.	_____.
0352	658.0173 Traffic Signal Face 3S 12-Inch	22.000 EACH	_____.	_____.
0354	658.5070 Signal Mounting Hardware (location) 01. CTH B & 3M Drive / 610th Avenue	1.000 EACH	_____.	_____.
0356	659.1115 Luminaires Utility LED A	53.000 EACH	_____.	_____.
0358	659.1125 Luminaires Utility LED C	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 Project(s): 7996-00-43

Federal ID(s): WISC 2023248

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0360	659.2130 Lighting Control Cabinets 120/240 30-Inch	2.000 EACH	_____.	_____.
0362	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	22.000 EACH	_____.	_____.
0364	661.0201 Temporary Traffic Signals for Intersections (location) 01. CTH B & 3M Drive / 610th Avenue	1.000 EACH	_____.	_____.
0366	661.0201 Temporary Traffic Signals for Intersections (location) 02. CTH B & IH 94 Eastbound Ramps	1.000 EACH	_____.	_____.
0368	661.0201 Temporary Traffic Signals for Intersections (location) 03. CTH B & IH 94 Westbound Ramps	1.000 EACH	_____.	_____.
0370	690.0150 Sawing Asphalt	1,037.000 LF	_____.	_____.
0372	690.0250 Sawing Concrete	3,711.000 LF	_____.	_____.
0374	715.0720 Incentive Compressive Strength Concrete Pavement	14,308.000 DOL	1.00000	14,308.00
0376	740.0440 Incentive IRI Ride	9,203.000 DOL	1.00000	9,203.00
0378	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0380	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
0382	SPV.0060 Special 01. Temporary EVP System CTH B & IH 94 Eastbound Ramps	1.000 EACH	_____.	_____.
0384	SPV.0060 Special 02. Temporary EVP System CTH B & IH 94 Westbound Ramps	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231114041 **Project(s):** 7996-00-43
Federal ID(s): WISC 2023248
SECTION: 0001 Contract Items
Alt Set ID: **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0386	SPV.0060 Special 04. Salvage & Reinstall Traffic Signal Equipment CTH B & USH 12/STH 29	1.000 EACH	_____.	_____.
0388	SPV.0060 Special 05. Salvage & Reinstall Traffic Signal Equipment CTH B & IH 94 Eastbound Ramps	1.000 EACH	_____.	_____.
0390	SPV.0060 Special 06. Salvage & Reinstall Traffic Signal Equipment CTH B & IH 94 Westbound Ramps	1.000 EACH	_____.	_____.
0392	SPV.0060 Special 07. Traffic Signal Cabinet and Controller CTH B & 3M Drive/610th Avenue	1.000 EACH	_____.	_____.
0394	SPV.0060 Special 08. Salvage & Reinstall Ramp Closure Gates CTH B & IH 94 Eastbound Ramps	1.000 EACH	_____.	_____.
0396	SPV.0060 Special 09. Concrete Control Cabinet Double Base	1.000 EACH	_____.	_____.
0398	SPV.0060 Special 10. Adjusting Water Valve Box	2.000 EACH	_____.	_____.
0400	SPV.0090 Special 01. Install State Furnished CAT-5E Cable	231.000 LF	_____.	_____.
0402	658.0174 Traffic Signal Face 4S 12-Inch	2.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

