



Wisconsin Department of Transportation

December 7, 2023

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #05: 3997-00-60, WISC 2024056
C Watertown, Welsh Road
STH 26 Overpass
Loc Str
Dodge County**

Letting of December 12, 2023

This is Addendum No. 02, which provides for the following:

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
7 & 8	HMA Pavement removal for guardrail post note

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM



Addendum No. 02
ID 3997-00-60
Revised Sheet 7
December 7, 2023

There is HMA pavement from the concrete slope paving to back of curb underneath the structures on both sides of Welsh Road. Removal of the HMA for the post hole should stay to a minimum of 1'-6" by 1'-9" square or 1'-9" diameter where the post is placed. This removal is incidental to the MGS Guardrail bid item and is to be backfilled per standard specification 614.2.2 controlled low-strength backfill, which is also incidental to the MGS Guardrail bid item.

2

2

PROJECT NO: 3997-00-60	COUNTY: DODGE	PLAN DETAILS	SHEET
FILE NAME: R:\3500\3564\3564\087\39970060\3564SHEETS\01-20- PD.DWG	LAYOUT NAME: -01-20	FLYBY: ASHLEY S. NELSON	PLOT DATE: 12/7/2023 7:21 AM
PROJECT NO: 3997-00-60	COUNTY: DODGE	PLAN DETAILS	SHEET
FILE NAME: R:\3500\3564\3564\087\39970060\3564SHEETS\01-20- PD.DWG	LAYOUT NAME: -01-20	FLYBY: ASHLEY S. NELSON	PLOT DATE: 12/7/2023 7:21 AM

E

E

WISSOT/CADDIS SHEET 42

WISSOT/CADDIS SHEET 42



There is HMA pavement from the concrete slope paving to back of curb underneath the structures on both sides of Welsh Road. Removal of the HMA for the post hole should stay to a minimum of 1'-6" by 1'-9" square in diameter where the post is placed. This removal is incidental to the MGS guardrail bid item and is to be backfilled per standard specifications for concrete strength backfill which is also incidental to the MGS guardrail bid item.

Addendum No. 02
 ID 3997-00-60
 Revised Sheet 8
 December 7, 2023

