

Table of Contents

PART 100 General Requirements and Covenants

<u>Section 101 General Information, Definitions, and Terms</u>	2
101.2 Add acronymns for WisDOT testing methods and WisDOT modified ASTM & AASHTO testing methods.	
<u>Section 102 Bidding Requirements and Conditions</u>	10
102.5 Reasonable site investigations include reviewing contract documents & those provided on request.	
<u>Section 103 Contract Award and Execution</u>	15
<u>Section 104 Scope of Work</u>	17
104.6.1.2.2 Allow automated flagging assistance devices from the APL.	
104.6.1.2.4 Hazard protection now only specified for roads open to all traffic.	
104.10.2 Eliminated work is not in and of itself eligible for a CRI.	
<u>Section 105 Control of the Work</u>	28
<u>Section 106 Control of Materials</u>	34
<u>Section 107 Legal Relations and Responsibility to the Public</u>	40
<u>Section 108 Prosecution and Progress</u>	49
Revise 108.11(3) to update liquidated damages based on analysis of fiscal 2021 data.	
<u>Section 109 Measurement and Payment</u>	61

PART 200 Earthwork

<u>Section 201 Clearing and Grubbing</u>	71
<u>Section 202 Roadside Clearing</u>	74
<u>Section 203 Removing Old Culverts and Bridges</u>	75
<u>Section 204 Removing or Abandoning Miscellaneous Structures</u>	80
204.5.1 Change Removing Building & Site Clearance bid items - LS (station) or (parcel) to EACH (station) or (parcel)	
<u>Section 205 Roadway and Drainage Excavation</u>	86
<u>Section 206 Excavation for Structures</u>	94
206.5.1 Change Excavation and Cofferdams bid items - LS (structure) or (station) to EACH (structure).	
<u>Section 207 Embankment</u>	99
<u>Section 208 Borrow</u>	102
<u>Section 209 Granular Backfill</u>	105
<u>Section 210 Structure Backfill</u>	107
<u>Section 211 Preparing the Foundation</u>	109
211.5.1 Change Prepare Foundation bid items - LS (project) to EACH (project).	
<u>Section 213 Finishing Roadway</u>	112
<u>Section 214 Obliterating Old Road</u>	114

PART 300 Bases, Subbases, and Subgrade Aggregates

<u>Section 301 Base, Subbase, and Subgrade Aggregate</u>	117
<u>Section 305 Dense-Graded Base</u>	122
<u>Section 310 Open-Graded Base</u>	125
<u>Section 311 Breaker Run</u>	126
311.3 Recycled concrete breaker run affects surface water pH if placed near outfalls, pipes, culverts, & water bodies.	
<u>Section 312 Select Crushed Material</u>	127
<u>Section 313 Pit Run</u>	128
<u>Section 315 Asphaltic Base</u>	129
<u>Section 320 Concrete Base</u>	130
<u>Section 325 Pulverized and Re-laid Pavement</u>	132
<u>Section 330 Milled and Re-laid Pavement</u>	133
<u>Section 335 Rubblized Pavement</u>	134
<u>Section 340 Cracked and Seated Pavement</u>	136
<u>Section 350 Subbase</u>	137

Section 390 Base Patching	139
390.2 Rearrange sentence and revise link.	
PART 400 Pavements	
Section 405 Coloring and Stamping Concrete	142
Section 415 Concrete Pavement	145
415.3.16 Incorporate project reference plate and adopt ASTM procedure. ASP 6 Nov 21 let.	
415.5.2 Define threshold for pavement replacement. ASP 6 Nov 21 let.	
Section 416 Concrete Pavement - Appurtenant Construction	157
Section 420 Diamond Grinding	162
Section 450 General Requirements for Asphaltic Pavements	164
Section 455 Asphaltic Materials	172
455 Provide direct links to the Combined State Binder Group Method of Acceptance for Asphalt Binders.	
Section 460 Hot Mix Asphalt Pavement	176
460.2.2.3 Correct errata by adding US Standard equivalent sieves. ASP 6 Nov 21 let.	
460.2.6 New procedure for recovered binder testing. ASP 6 Nov 21 let.	
Section 465 Asphaltic Surface	190
Section 475 Seal Coat	192
PART 500 Structures	
Section 501 Concrete	195
501.2.5.3.3 High range water reducers need BTS approval before use.	
501.2.5.3.5 Hydration controlling admixtures need BTS approval & set time tests before use.	
501.2.6 Change heading name. ASP6 Nov 2021 let.	
501.2.6.2 Reference Wisconsin Testing Procedures (WTP) in CMM 870. ASP 6 Nov 21 let.	
501.3.2.2 Provide values for total cementitious material content with approved SCMs for class II and class III concrete as specified in 716. ASP 6 May 2022 let.	
501.3.2.3 Correct errata by changing “cement” to “cementitious material”.	
501.3.2.4.2 Allow SAM Meter to be used for Air Content Test. ASP 6 Nov 21 let.	
501.3.7.1 Allow up to 9-inch slump for BTS-approved superplasticizer mixtures. ASP 6 Nov 21 let.	
Section 502 Concrete Bridges	213
502.2.7 Add expansion device material requirements previously specified in STSP 502-020.	
502.3.6.3.3 Add expansion device construction requirements previously specified in STSP 502-020.	
502.4 Determine concrete quantity for bridges based on plan dimensions unless the engineer revises the plan.	
Section 503 Prestressed Concrete Members	234
Section 504 Culverts, Retaining Walls, and Endwalls	240
Section 505 Steel Reinforcement	242
505.3.3.4.1 Bar coupler material must develop 125% of the SPECIFIED yield strength.	
Section 506 Steel Bridges	247
Section 507 Timber Structures	266
Section 509 Concrete Overlay and Structure Repair	273
509.3.1 Repair rebar coating using ASTM specified materials and methods.	
Section 511 Temporary Shoring	278
Section 512 Steel Sheet Piling	279
Section 513 Railing	281
Section 514 Floor Drains, Deck Drains, and Downspouts	284
514.5 Change Railroad Deck Drain System bid items - LS (railroad structure) to EACH (railroad structure).	
Section 515 Steel Grid Floors	286
Section 516 Waterproofing	287
Section 517 Paint and Painting	289
517.5 Change Painting Epoxy System bid items - LS (structure) to EACH (structure).	

<u>Section 519 Brick Masonry and Concrete Brick or Block Masonry</u>	298
<u>Section 520 Pipe Culverts</u>	300
<u>Section 521 Corrugated Steel Culverts</u>	306
521.2 Furnish corrugated steel pipe & steel apron end walls of the thickness the contract designates.	
<u>Section 522 Reinforced Concrete Culverts</u>	307
<u>Section 524 Salvaged Culverts</u>	308
<u>Section 525 Corrugated Aluminum Culverts</u>	309
<u>Section 526 Temporary Structures</u>	310
526.5 Change Temporary Structure bid item - LS (station) to EACH (station).	
<u>Section 527 Structural Plate Pipe and Pipe Arches</u>	311
<u>Section 530 Corrugated Plastic Pipe Culverts</u>	313
<u>Section 531 Ancillary Structure Foundations</u>	314
531.5 Pay separately for excavating & backfilling drilled shafts for all 531 foundations. ASP 6 November 2021.	
<u>Section 532 Ancillary Superstructures</u>	317
<u>Section 550 Driven Piles</u>	323

PART 600 Miscellaneous Construction

<u>Section 601 Concrete Curb and Gutter</u>	330
<u>Section 602 Concrete Sidewalks, Loading Zones, Safety Islands, and Steps</u>	333
<u>Section 603 Concrete Barrier</u>	337
<u>Section 604 Slope Paving</u>	341
<u>Section 606 Riprap</u>	343
<u>Section 608 Storm Sewer</u>	345
<u>Section 611 Catch Basins, Manholes, and Inlets</u>	351
<u>Section 612 Underdrains</u>	354
612.2.5 Define requirements by use and size for corrugated polyethylene and polypropylene pipe underdrain.	
<u>Section 614 Semi-rigid Barrier Systems and End Treatments</u>	358
<u>Section 615 Rustic Timber Items and Historical Markers</u>	366
<u>Section 616 Property and Right-of-Way Fence</u>	368
<u>Section 618 Maintenance and Repair of Haul Roads</u>	374
<u>Section 619 Mobilization</u>	375
<u>Section 620 Concrete Corrugated Median and Concrete Median Nose</u>	376
<u>Section 621 Landmark Reference Monuments</u>	377
<u>Section 623 Dust Control Surface Treatment</u>	379
<u>Section 624 Water</u>	380
<u>Section 625 Topsoil and Salvaged Topsoil</u>	381
<u>Section 626 Peat Humus</u>	383
<u>Section 627 Mulching</u>	384
<u>Section 628 Erosion Control</u>	386
<u>Section 629 Fertilizer and Agricultural Limestone</u>	396
<u>Section 630 Seeding</u>	398
<u>Section 631 Sodding</u>	404
<u>Section 632 Furnishing and Planting Plant Materials</u>	406
<u>Section 633 Delineators and Markers</u>	415
<u>Section 634 Wood and Tubular Steel Sign Posts</u>	418
<u>Section 635 Structural Steel Sign Supports</u>	420
<u>Section 637 Signing</u>	421
<u>Section 638 State Owned Signs and Supports</u>	428
<u>Section 639 Drilling Wells</u>	430
<u>Section 642 Field Facilities</u>	435
642.2.2.1 Require functional cell phone service inside field office facilities. ASP 6 Nov 21 let.	
<u>Section 643 Traffic Control</u>	438

643.1	Move temporary pavement marking from section 649.	
643.2.2	Add channelizing curb systems and speed radar trailers to devices on APL.	
643.2.3.1	Add requirement for sign mounted on posts to conform to crashworthy requirements.	
643.2.5	Temporary pavement marking materials requirements by reference to 646.2.	
643.3.1	Specific criteria for reflective sheeting and allowable missing or defective material limits for temporary marking.	
643.3.3	Eliminate one-mile visibility criteria for arrow boards.	
643.3.6	Construction for channelizing curb systems, temporary pavement marking, and interim lane closures.	
643.4.5	Measurement for channelizing curb systems, temporary pavement marking, and interim lane closures.	
643.5.1	Bid items for Channelizing Curb Systems, Speed Radar Trailers, Temporary Marking, and Interim Lane Closures.	
643.5.4	Payment for temporary marking, and interim lane closures.	
Section 644 Temporary Pedestrian Facilities		445
644.2.2	Delete plywood and allow non-prefabricated plate and skid resistant matting temporary pedestrian surface options.	
644.2.5	Add yellow temporary detectible warning fields to the APL.	
644.3.1	Inspection and repair/replacement of disturbed pedestrian accommodations.	
644.3.2.3	Construction for skid resistant matting temporary pedestrian surface options.	
644.3.4	Prompt replacement of continuous pedestrian barricade after breaks made for contractor work operations.	
644.3.5	Construction for temporary detectible warning fields.	
644.4	Measurement for temporary detectible warning fields and pedestrian barricades.	
644.5	New bid item for Temporary Pedestrian Detectible Warning Field.	
Section 645 Geosynthetics		447
Section 646 Pavement Marking		454
646.3.1.1	Require permanent marking within 7 days of surface treatment for roads open to traffic.	
Section 648 Locating No-passing Zones		459
649	Delete 649. Temporary pavement marking is now covered under the traffic control section 643.	
Section 650 Construction Staking		462
650.1	Add sidewalk to construction staking.	
650.3.15	Construction for new sidewalk staking bid item.	
650.4	Add measurement for new sidewalk staking bid item. Change construction staking structure layout, electrical installations and staking supplemental control to EACH.	
650.5	New bid item for Construction Staking Sidewalk by project. Change Construction Staking Structure Layout, Electrical Installations and Supplemental Control bid items from LS to EACH).	
Section 651 General Requirements for Electrical Work		467
Section 652 Electrical Conduit		469
652.4	Measure conduit from center-to-center of concrete bases, pull boxes, junction boxes, and vaults.	
Section 653 Pull Boxes and Junction Boxes		472
Section 654 Bases		473
645.5	Add to description for payment for bases.	
Section 655 Electrical Wiring		474
655.2.6	Update to require use of manufacturer color code covering.	
655.3.1	Increase extra cable and wire length required in fixtures for splicing, vertical rises, and terminations.	
Section 656 Electrical Service		480
656.5	Change Electrical Service bid items - LS (location) to EACH (location).	
Section 657 Poles, Arms, Standards, and Bases		483
657.5	New bid item for 15-ft steel luminaire arms used on type 10 special pole.	
Section 658 Traffic Signals		487
658.5	Change the Signal Mounting Hardware bid item - LS (location) to EACH (location).	
Section 659 Lighting		489
659.5	Change the Underdeck Lighting bid item - LS (location) to EACH (structure).	

Section 660 High Mast Lighting Lowering Assemblies	491
Section 661 Temporary Traffic Signals and Temporary Ramp Meters	493
661.5 Change Traffic Signals & Ramp Meter bid items - LS (structure) or (location) to EACH (structure) or (location).	
Section 670 General Requirements for Intelligent Transportation Systems.....	499
670.5 Change Field System Integrator & ITS Documentation bid items - LS contract to EACH contract.	
Section 671 Intelligent Transportation Systems - Conduit.....	501
Section 673 Communication Vaults	503
Section 674 Intelligent Transportation Systems - Cable	504
Section 675 Controllers and Detectors	507
Section 677 Cameras	509
Section 678 Communication Systems	511
678.5 Change Communication System Testing bid items - LS to EACH.	
Section 690 Sawing.....	514
 PART 700 Quality Management Program 	
Section 701 General QMP Requirements	516
701.3.1 Allow SAM meter to be used for air content test. ASP 6 Nov 21 let. Correct errata with AGGTEC-I.	
Section 710 General Concrete QMP	520
710.2 Update class II small quantity and clarify aggregate reporting. ASP 6 Nov 21 let. Require mix design submittal in small quantity control plan.	
710.4 Define workability test for slip-form concrete. ASP 6 Nov 21 let.	
710.4 Establish mix modification submittal timeframe during concrete production. ASP 6 Nov 21 let.	
710.5.5 Specify the required size for flexural strength beams. ASP 6 Nov 21 let.	
710.5.6 Modify testing frequencies. ASP 6 Nov 21 let. Define QV small quantity testing frequency.	
710.5.7 Incorporate Class I: Pavements testing frequency in corrective action. ASP 6 Nov 21 let.	
Section 715 QMP Concrete Pavement, Cast-in-Place Barrier and Structures	525
715.1.1.2 Change structure concrete small quantity to 250 cy.	
715.1.1.4 Define timeline of quality control plan submittal.	
715.2.1 Coordinate mix design submittal requirements with DT2220 and DT2221 required under 710.4.	
715.2.2 Field strength data not allowed. SCM requirements listed in 501.3.2.2.2.	
715.3.1.1 Clarify test results for reporting, update lot sizes. ASP 6 Nov 21 let.	
715.3.1.2.3 Update lot and subplot sizes. ASP 6 Nov 21 let.	
715.3.2 Removed fixed strength disincentive cost. ASP 6 Nov 21 let. Update removal and replacement process.	
715.3.3 Establish when aggregate moisture content corrections are required for concrete mixtures. ASP 6 Nov 21 let.	
715.5.1(4) Pay for cast-in-place barrier based on specified cost per CY instead of per LF.	
715.5.2 New pay equations for compressive and flexural strength.	
Section 716 QMP Ancillary Concrete	531
716.1.1.2 Define mix design requirements.	
716.2.1(1) Documentation requirements for integral concrete.	
716.2.1(2) Test temperature for each 100 CY. Cast cylinders for each 200 CY per mix design. ASP 6 May 2022 let.	
Section 730 QMP Base Aggregate	533
730.3.1 Waive fracture testing for recycled materials.	
730.3.2 Increase allowed reporting time for aggregate with recycled material.	
730.3.3 Increase retain time and QV testing frequency, and for aggregate with recycled material, reporting time.	
730.3.4.1 Revise small quantity threshold and clarify QC testing requirements.	
Section 740 QMP Ride	537
Bid Items	542
100 Bid Items	542
200 Bid Items	542
204.0105 Rename to Removing "Concrete" Pavement Butt Joints to better reflect its use.	

204.0230 Convert part 200 lump sum (LS) bid items to EACH.	
300 Bid Items	543
400 Bid Items	544
500 Bid Items	547
514.1000 Convert part 500 lump sum (LS) bid items to EACH.	
526.0100 Convert part 500 lump sum (LS) bid items to EACH.	
600 Bid Items	561
611.2009 Add new bid items for 9-foot and 10-foot manholes.	
643.0650 Add new Traffic Control Channelizing Curb System bid item.	
643.1500 Add new Traffic Control Speed Radar Trailer bid item.	
643.3105 Add Temporary Marking bid item moved to 643 from 649.	
643.4100 Add new Traffic Control Interim Lane Closure bid item.	
644.1420 Retire Temporary Pedestrian Detectable Warning Field bid item.	
644.1440 Add new Temporary Pedestrian Surface Matting bid item.	
644.1065 Add new Temporary Pedestrian Detectable Warning Field bid item.	
649.0000 Retire 649 bid items. Temporary marking bid items moved to section 643.	
650.6500 Convert part 600 lump sum (LS) bid items to EACH.	
650.9500 Add new Construction Staking Sidewalk bid item.	
656.0100 Convert part 600 lump sum (LS) bid items to EACH.	
657.0830 New bid item for 15-ft steel luminaire arms used on type 10 special pole.	
658.5069 Convert part 600 lump sum (LS) bid items to EACH.	
678.0500 Convert part 600 lump sum (LS) bid items to EACH.	
700 Bid Items	580
Appendix	581
Conversion Table U.S. Standard Measure to SI Metric	581
Standard Sieve Sizes	582
Bid Item Unit Abbreviations	582